Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 06/18/13

LAVATORY SECTION | B2
3/4" = 1'–0"

TOILET ELEVATION

LAVATORY ELEVATION

LAV/TOIL ELEVATIONS | B1
1/4" = 1'–0"

LEGEND – TOILET RM ACCESSORIES

	ITEMS	MTD. HEIGHTS
1	36" X 1 1/4" GRAB BAR	2'–10" A.F.F. TO C.L.
2	42" X 1 1/4" GRAB BAR	2'–10" A.F.F. TO C.L.
3	TOILET TISSUE DISPENSER	1'–7" A.F.F. TO C.L.
4	SANITARY NAPKIN DISPOSAL	N.A.
5	COUNTER MTD. SOAP DISPENSER	N.A.
6	PAPER TOWEL DISPENSER	N.A.
7	8'–0"W X 48"H MIRROR	3'–3" TO BOT. OF GLASS

MGR'S APT. BATH/KIT. ELEV. | A1
1/4" = 1'–0"

ROBERT J. FOSTER – ARCHITECT
36 Groveside Road, Portland, Maine 04102
(207) 761–3822

REGISTERED ARCHITECT ROBERT J. FOSTER #1734 STATE OF MAINE

3-29-13

Project Title

CROSS INSURANCE RENOVATIONS

2331 CONGRESS STREET
Portland, Maine

Mark	Date	Description
	03–29–13	ISSUED FOR BID

Issue Dates

Drawing Title

ENLARGED PLANS AND DETAILS

Drawing Number

A90.1