ROOM FINISH SCHEDULE

ROOM NO.	ROOM NAME	FLOOR MAT	FLOOR FIN	BASE MAT	BASE FIN	WAINSCOT MAT	WAINSCOT FIN	WAINSCOT HT	WALLS NORTH	WALLS FIN	WALLS EAST	WALLS FIN	WALLS SOUTH	WALLS FIN	WALLS WEST	WALLS FIN	CEILING MAT	CEILING FIN	CEILING HT	REMARKS
101	LOBBY	←				EXISTING														→
102	RECEPTION	←				EXISTING														→
103	CORRIDOR	CARPET		WOOD	PT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		9'–0	
104	CORRIDOR	CARPET		WOOD	PT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		9'–0	
105	OFFICE	CARPET		WOOD	PT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		9'–0	
106	OFFICE	CARPET		WOOD	PT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		8'–0	
107	OFFICE	CARPET		WOOD	PT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		9'–0	
108	OFFICE	CARPET		WOOD	PT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		9'–0	
109	OFFICE	CARPET		WOOD	PT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		9'–0	
110	CONFERENCE RM	CARPET		WOOD	PT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		9'–0	
111	OFFICE	CARPET		WOOD	PT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		9'–0	
112	EXIT ACCESS	←				EXISTING														→
113	OFFICE	CARPET		WOOD	PT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		9'–0	
114	OFFICE	CARPET		WOOD	PT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		9'–0	
115	STORAGE	CARPET		WOOD	PT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		9'–0	
116	SECURE STORAGE	CARPET		WOOD	PT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		9'–0	
117	W. TOILET	←				EXISTING														→
118	M. TOILET	←				EXISTING														→



TYP. WOOD BASE — 3" = 1'–0" — C2







TYP. EXTERIOR WALL — 1 1/2" = 1'–0" — C1

ROBERT J. FOSTER ARCHITECT
36 Groveside Road, Portland, Maine 04102
(207) 761-3822

REGISTERED ARCHITECT — ROBERT J. FOSTER #1734 — STATE OF MAINE

Project Title

CROSS INSURANCE RENOVATIONS

2331 CONGRESS STREET
PORTLAND, MAINE

Mark	Date	Description
	08 - 26 - 16	ISSUED FOR PERMIT

Issue Dates

Drawing Title

FINISH SCHEDULE AND DETAILS

Drawing Number

A60.2