FIXTURE SCHEDULE

QUANTITY	TYPE	MANUFACTURER	CATALOG NUMBER	DESCRIPTION	LAMPS
44	A	RAB	SWISH2X4-39Y/D10	LED 2X4 DIRECT/INDIRECT	LED
34	B	RAB	SWISH2X2-29Y/D10	LED 2X2 DIRECT/INDIRECT	LED
1	C	DAY-BRITE	OWL430L835UNV	LED WRAPAROUND	LED
17	D	LIGHTOLIER	L6R20AEUVA/L6R20835VA/L6RBW	RECESSED DOWNLIGHT	LED
11	D1	NORA	NHIOICD-28LE3/NIOB-2RC35XWW	RECESSED ADJUSTABLE	LED
15	DR			LED RETRO-FIT KITS	LED
-	F				
4	G	LIGHTOLIER	L4R10AE1VA/L4R10835VA/L4RBW	RECESSED DOWNLIGHT	LED
4	H	LUMARK	XTOR3B	LED WALL PACK	LED
13	EXIT	DUAL-LITE	EVEURWE	EXIT SIGN	LED
9	EBU	DUAL-LITE	LZ15	EMERGENCY BATTERY UNIT	
2	SRH	DUAL-LITE	LZRSW0605	SINGLE REMOTE HEAD	
3	ORH	DUAL-LITE	OCRSW0605	OUTDOOR SINGLE REMOTE HEAD	

EXISTING PANEL P

SECTION 1

VOLTS: - 208/120V
PHASE: - 3
AMPS: - 225
BUS: - 225
AIC: - 22KAIC
MTD: -
LOC: -

CIRCUIT	TRIP	POLE	WATTS	SERVICE
1	20	1		LIGHTING - RM 123,124,125,126,132
3	20	1		LIGHTING - RM101,102 108,118,121,122,133
5	20	1		LIGHTING - RM103,104, 134,135,136,137,138
7	20	1		LIGHTING - BUILDING LIGHTS
9	20	1		RECEPTACLE - RM120,121,128,129
11	20	1		RECEPTACLE - RM 109
13	20	1		RECEPTACLE - RM 109
15	20	1		OFFICE FURNITURE - RM 109
17	20	1		RECEPTACLE - RM 103, 104
19	20	1		RECEPTACLE - RM 110, 111, 122
21	20	1		RECEPTACLE - RM 101, 102,123
23	20	1		PRINTER
25	20	1		PRINTER
27	20	1		RECEPTACLE - RM 124
29	20	1		FRIDGE - RM 123
31	20	1		RECEPTACLE - RM 123
33	20	1		RECEPTACLE - RM 126
35	20	1		RECEPTACLE - RM 135,136
37	20	1		OFFICE FURNITURE - RM 132
39	20	1		RECEPTACLE - RM 132
41	20	1		ERV
2	20	1		LIGHTING - RM 109,110,111
4	20	1		LIGHTING - RM116,117, 119,120,127,128,129,130,131
6	20	1		BUILDING SIGNS
8	20	1		RECEPTACLE - RM129, 130,131
10	20	1		RECEPTACLE - RM116,117
12	20	1		RECEPTACLE - RM 109
14	20	1		RECEPTACLE - RM 109
16	20	1		OFFICE FURNITURE - RM 109
18	20	1		COPIER RM 109
20	20	1		AUTOMATIC TOILETS
22	20	1		RECEPTION - 102
24	20	1		PRINTER
26	20	1		RECEPTACLE - RM124
28	20	1		RECEPTACLE - RM124
30	20	1		RECEPTACLE - RM123
32	20	1		RECEPTACLE - RM125
34	20	1		RECEPTACLE - RM137, 138
36	20	1		RECEPTACLE - RM132, 134
38	20	1		OFFICE FURNITURE - RM 132
40	20	1		COPIER RM 132
42				

EXISTING PANEL P

SECTION 2

VOLTS: - 208/120V
PHASE: - 3
AMPS: - 225
BUS: - 225
AIC: - 22KAIC
MTD: -
LOC: -

CIRCUIT	TRIP	POLE	WATTS	SERVICE
43	50	2		HEAT PUMP
45				
47	35	3		5TON A/C
49				
51				
53				
55	35	3		5TON A/C
57				
59				
61	20	1		RECEPTACLE - ROOF
63	20	1		EHW
65				
67				
69				
71				
73				
75				
77				
79				
81				
83				
44	25	3		3TON A/C
46				
48				
50	25	3		3TON A/C
52				
54				
56				
58				
60	20	1		RECEPTACLE - RM 119
62	20	1		FACP
64	20	1		RECIRC PUMP
66				
68				
70				
72				
74				
76				
78				
80				
82				
84				

PHASE A: watts
PHASE B:
PHASE C:

PANEL C TOTAL: watts

POWER LEGEND

- DUPLEX CONVENIENCE RECEPTACLE
- DUPLEX CONVENIENCE RECEPTACLE - 46" AFF TO TOP
- GROUND FAULT INTERRUPTER RECEPTACLE
- GROUND FAULT INTERRUPTER RECEPTACLE - 46" AFF TO TOP
- SPECIAL EQUIPMENT WIRING
- PC PARTIAL CIRCUIT
- VOICE/DATA RECEPTACLE 18" AFF TO TOP
- CATV OUTLET
- RECESSED MOUNTED LIGHTING & POWER PANEL
- FUSED DISCONNECT SWITCH
- S MOTOR SWITCH
- PP POWER POLE

LIGHTING & EMERGNECY LEGEND

- 2' x 4' LIGHT FIXTURE
- 2' x 2' LIGHT FIXTURE
- RECESSED LIGHT FIXTURE
- FLUORESCENT STRIP LIGHT FIXTURE
- FLUSH/SEMI-FLUSH LIGHT FIXTURE
- WALL MOUNTED LIGHT FIXTURE
- S SINGLE-POLE SWITCH
- S_3 THREE-WAY SWITCH
- OS MOTION SENSOR - CEILING MOUNTED
- LED EXIT SIGN
- COMBINATION EMERGENCY LIGHT FIXTURE & EXIT SIGN
- EMERGENCY LIGHT FIXTURES W/ BATTERY PACK - MOUNTED 84" AFF TO TOP OF BOX OR 6" BELOW CEILING, WHICH EVER IS LOWER
- EMERGENCY LIGHT REMOTE FIXTURES 84" AFF TO TOP OF BOX OR 6" BELOW CEILING, WHICH EVER IS LOWER

FIRE ALARM LEGEND

- P FIRE ALARM MANUAL PULL STATION - MOUNT 52" AFF TO TOP OF BOX
- KB FIRE ALARM KNOX BOX
- F FIRE ALARM HORN AND STROBE UNIT - MOUNT 84" AFF TO TOP OF BOX OR 6" BELOW CEILING, WHICH EVER IS LOWER
- F C FIRE ALARM HORN AND STROBE UNIT - CEILING MOUNT
- S FIRE ALARM STROBE UNIT - MOUNT ABOVE DOOR - MOUNT 84" AFF TO BOTTOM OF BOX OR 6" BELOW CEILING, WHICH EVER IS LOWER
- H HEAT DETECTOR - CEILING MOUNTED
- SD SMOKE DETECTOR - CEILING MOUNTED
- DS DUCT SMOKE
- DH DOOR HOLDER

STATE OF MAINE STEVEN A. MONASTRA #8485 LICENSED PROFESSIONAL ENGINEER

CITY OF PORTLAND, MAINE — RESURGAM

Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 03/06/18

Anthony Mancini, Inc.
179 SHERIDAN ST.
PORTLAND, ME 04101
P: (207)774-5829 F: (207)772-1686
E: info@mancinielectric.com
"We appreciate Your Business."

NO.	DATE	DESCRIPTION

PROJECT NAME & ADDRESS:
Cross Insurance
2367 Congress Street
Portland, Maine

SHEET NAME:
Legends & Schedules

Checked By: G.MANCINI
Drawn By: A.AMES
Date: 11.28.2017
Scale: As Noted

SHEET:
E2