ROOM FINISH SCHEDULE

ROOM		FLOOR		BASE		WAINSCOT			WALLS								CEILING			REMARKS
NO.	NAME	MAT	FIN	MAT	FIN	MAT	FIN	HT	NORTH	FIN	EAST	FIN	SOUTH	FIN	WEST	FIN	MAT	FIN	HT	
101	VESTIBULE	ENTRY MAT		---	--				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT/GPDW	PT	8'-5"	
102	RECEPTION	CARPET		WOOD	NAT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT/GPDW	PT	8'-6"	CHAIR RAIL – SEE DETAIL E1
103	CONFERENCE RM	CARPET		WOOD	NAT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		8'-6"	
104	OFFICE	CARPET		WOOD	NAT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		8'-6"	
105	CORRIDOR	CARPET		WOOD	NAT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		8'-6"	
106	OPEN OFFICE	CARPET		WOOD	NAT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		8'-6"	
107	W. TOILET	CERAMIC TILE		CERAMIC TILE		CERAMIC TILE		48"	GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		8'-6"	WAINSCOT TILE PATTERN – SEE DETAIL B5
108	M. TOILET	CERAMIC TILE		CERAMIC TILE		CERAMIC TILE		48"	GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		8'-6"	WAINSCOT TILE PATTERN – SEE DETAIL B5
109	CORRIDOR	CARPET		WOOD	NAT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		8'-6"	
110	OFFICE	CARPET		WOOD	NAT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		8'-6"	
111	OFFICE	CARPET		WOOD	NAT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		8'-6"	
112	CORRIDOR	CARPET		WOOD	NAT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		8'-6"	
113	UTILITY RM	CONC		RUBBER					GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	STRUC.		---	
114	FILE RM	VCT		RUBBER					GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		8'-6"	
115	CORRIDOR	CARPET		WOOD	NAT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		8'-6"	
116	CORRIDOR	CARPET		WOOD	NAT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	GPDW		8'-5"	
117	BREAK RM	VCT		RUBBER					GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		8'-6"	
118	PRINT/MAIL RM	VCT		RUBBER					GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		8'-6"	COAT RACK – SEE DETAIL B4
119	CONFERENCE RM	CARPET		WOOD	NAT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		8'-6"	
120	CONFERENCE RM	CARPET		WOOD	NAT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		8'-6"	CHAIR RAIL – SEE DETAIL E1
121	OFFICE	CARPET		WOOD	NAT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	8'-6"	
122	OFFICE	CARPET		WOOD	NAT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		8'-6"	
123	OFFICE	CARPET		WOOD	NAT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		8'-6"	
124	OFFICE	CARPET		WOOD	NAT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		8'-6"	
125	OFFICE	CARPET		WOOD	NAT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		8'-6"	
126	OPEN OFFICE	CARPET		WOOD	NAT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		8'-6"	
127	CORRIDOR	CARPET		WOOD	NAT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	8'-6"	
128	OFFICE	CARPET		WOOD	NAT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		8'-6"	
129	OFFICE	CARPET		WOOD	NAT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		8'-6"	
130	OFFICE	CARPET		WOOD	NAT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		8'-6"	
131	OFFICE	CARPET		WOOD	NAT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		8'-6"	
132	OFFICE	CARPET		WOOD	NAT				GPDW	PT	GPDW	PT	GPDW	PT	GPDW	PT	ACT		8'-6"	

BREAKROOM CASEWORK — 1/4" = 1'-0" — E2

CHAIR RAIL DTL. — 3" = 1'-0" — E1

MAILROOM CASEWORK — 1/4" = 1'-0" — D2

TYP. WOOD BASE — 3" = 1'-0" — D1

RECEPTION CASEWORK — 1/4" = 1'-0" — C2

COUNTER DTL. — 1 1/2" = 1'-0" — C1

1 DESK PLAN

WAINSCOT TILE PATTERN — 1/2" = 1'-0" — B5

COAT RACK DETAIL — 1 1/2" = 1'-0" — B4

CASEWORK DTL — 3/4" = 1'-0" — A3

CASEWORK DTL — 3/4" = 1'-0" — A2

CASEWORK DTL — 3/4" = 1'-0" — B1

CASEWORK DTL — 3/4" = 1'-0" — A1

2 DESK ELEV.

3 DESK ELEV.

4 DESK ELEV.

RECEPTION DESK — 1/4" = 1'-0" — A4

ROBERT J. FOSTER ARCHITECT
36 Groveside Road, Portland, Maine 04102
(207) 761-3822

REGISTERED ARCHITECT ROBERT J. FOSTER #1734 STATE OF MAINE

Project Title

CROSS INSURANCE RENOVATIONS

2367 CONGRESS STREET
PORTLAND, MAINE

Mark	Date	Description
	01 - 29 - 18	CONSTRUCTION DRAWINGS

Issue Dates

Drawing Title

ROOM FINISH SCHEDULE AND DETAILS

Drawing Number

A60.2

Date: 03/06/18