PIPING SYMBOLS **ABBREVIATIONS** ACCESS DOOR MINIMUM ——||—— UNION AUTHORITY HAVING JURISDICTION MTD MOUNTED NTS NOT TO SCALE ACCESS PANEL GROOVED COUPLING BACKFLOW PREVENTER PRE-ACTION ALARM CHECK VALVE (FIRE DEPARTMENT) PUMPER CONNECTION PIPE GUIDE OR SLEEVES BOTTOM OF PIPE POST INDICATING VALVE PIPE ELBOW TURNED DOWN PIPE ELBOW TURNED UP CLEAN AGENT ———— PIPING TEE-DOWN CFF CAPPED FOR FUTURE PRESSURE REDUCING VALVE ———— PIPING TEE-UP PRESSURE SWITCH PIPE RISER CONTINUATION REMOVE I CO CLEAN OUT RELOCATED COORDINATE PIPE PITCHES DOWN CONNECT TO EXISTING GENERIC VALVE, SEE REDUCED PRESSURE ZONE BFP SPECIFICATIONS FOR TYPE COLD WATER RELIEF VALVE GATE VALVE (WET PIPE) SPRINKLER ALARM CHECK VALVE DRY PIPE ALARM CHECK VALVE BALL VALVE SMOKE DETECTOR DIAMETER — ∫ butterfly valve (manual) STAND PIPE DOWN IN CHASE — CHECK VALVE DOWN IN WALL SPRINKLER GLOBE VALVE DOUBLE CHECK VALVE ASSEMBLY (FIRE DEPARTMENT) TEST HEADER OS&Y GATE VALVE TOP TOP OF PIPE BACK FLOW PREVENTER TAMPER SWITCH PRESSURE RELIEF VALVE TIGHT TO STEEL DOWNSPOUT STRAINER DROP AND TRANSITION TYPICAL UIC UP IN CHASE DRAWING STRAINER W/BLOWDOWN UP IN WALL ENCLOSURE PRESSURE SWITCH UNDERWRITER'S LABORATORY EXISTING FLOW SWITCH VALVED AND CAPPED FOR FUTURE FURNISHED BY OWNER VALVE WITH TAMPER SWITCH WALL INDICATING VALVE FLEXIBLE CONNECTION FLOOR CONTROL VALVE ASSEMBLY WATER MOTOR GONG __________ FIRE DEPARTMENT CONNECTION HOSE END DRAIN VALVE WITH CAP FIRE DEPARTMENT VALVE CONCENTRIC REDUCER/INCREASER FIRE DEPARTMENT VALVE CABINET ECCENTRIC REDUCER/INCREASER FIRE EXTINGUISHER ───── DIRECTION OF FLOW FIRE HOSE SIAMESE FIRE DEPARTMENT CONNECTION FHC FIRE HOSE CABINET FM FACTORY MUTUAL STORZ FIRE DEPARTMENT CONNECTION FS FLOW SWITCH WATER MOTOR GONG GENERAL CONTRACTOR ELECTRIC BELL GALLONS PER MINUTE HEATING, VENTILATING AND AIR CONDITIONING FIRE PUMP TEST HEADER INSPECTOR'S TEST STATION LFPC LIMIT OF FIRE PROTECTION CONTRACT FREE-STANDING FIRE PUMP TEST HEADER FIRE DEPARTMENT VALVE MFR MANUFACTURER FIRE DEPARTMENT VALVE CABINET FIRE HOSE CABINET COMBINATION FIRE HOSE/VALVE CABINET FLOOR CONTROL VALVE ASSEMBLY PIPING SYSTEMS ALARM CHECK VALVE — CA — CLEAN AGENT PENDENT SPRINKLER HEAD — D — DRY PIPE SPRINKLER UPRIGHT SPRINKLER HEAD ---- DR ---- DRAIN UPRIGHT SPRINKLER HEAD - EXTENDED COVERAGE — F — FIRE SERVICE CONCEALED SPRINKLER HEAD — FP — COMBINATION FIRE PROTECTION RECESSED SPRINKLER HEAD — G — DELUGE SPRINKLER SIDEWALL SPRINKLER HEAD —— PA —— PRE-ACTION SPRINKLER SIDEWALL SPRINKLER HEAD - EXTENDED COVERAGE — SPK (X) — WET-PIPE SPRINKLER (ZONE X) DRY SIDEWALL SPRINKLER HEAD —— SP —— STAND PIPE VERTICAL PENDENT SIDEWALL WINDOW SPRINKLER DRY PENDENT SPRINKLER HEAD 1234 HYDRAULIC REFERENCE POINT HYDRANT

SPECIFICATIONS

21 00 00 - GENERAL REQUIREMENTS

1. THE FOLLOWING APPLIES TO FIRE PROTECTION PIPING TRADES.

2. OBTAIN ALL PERMITS AND APPROVALS TO PERFORM THE WORK.

OBSTRUCTIONS, AND EXISTING CONFIGURATIONS AND

3. VERIFY ALL MEASUREMENTS AND EXISTING CONDITIONS IN THE FIELD. GENERAL SCHEMATIC LAYOUT IS INDICATED; ALL OFFSETS

4. INSTALL ALL NEW AND RELOCATED EXISTING COMPONENTS IN ACCORDANCE WITH MANUFACTURER RECOMMENDATIONS, APPLICABLE CODES AND STANDARDS.

CONSTRAINTS MUST BE FIELD VERIFIED.

OWNER AND GENERAL CONTRACTOR.

5. COORDINATE WITH OWNER FURNISHED EQUIPMENT AND SYSTEMS.

6. THIS RENOVATION WORK WILL TAKE PLACE IN OCCUPIED SPACE. INSTALLATIONS SHALL NOT AFFECT ONGOING OPERATIONS. COORDINATE HOURS AVAILABLE TO PERFORM WORK WITH THE

7. SEAL INTERIOR PIPE PENETRATIONS WITH FIRE SEALANT. SEAL EXTERIOR WALL PIPE PENETRATIONS WATER TIGHT.

8. CUT AND PATCH SURFACES, RESTORING ORIGINAL FINISHES.

9. EQUIPMENT LISTED IS THE BASIS OF DESIGN, OR APPROVED EQUAL.

SUBMITTALS, PRE-CONSTRUCTION: SUBMIT CATALOG CUT SHEETS
OF PROPOSED EQUIPMENT FOR ENGINEER REVIEW AND
APPROVAL PRIOR TO PURCHASE AND INSTALLATION.

11. SUBMITTALS, DURING CONSTRUCTIONS: SUBMIT COPIES OF PIPE ROUGH-IN PRESSURE TESTS AS COMPLETED.12. SUBMITTALS, POST CONSTRUCTION: SUBMIT COPIES OF FINAL

PRESSURE TEST, FLUSHING AND PLUMBING DISINFECTION REPORTS. SUBMIT COPIES OF COMPLETED MANUFACTURER START UP REPORTS FOR EQUIPMENT.

13. OPERATIONS AND MAINTENANCE MANUALS: SUBMIT ALL TESTING DATA AND COPIES OF APPROVED PRODUCT DATA, INCLUDING MAINTENANCE INFORMATION IN A TABBED, NEATLY ORGANIZED THREE RING BINDER. INCLUDE VALVE IDENTIFICATION CHARTS PROVIDE 3 COPIES TO THE OWNER.

14. PIPE IDENTIFICATION; LABELING SHALL APPEAR AT INTERVALS OF NOT MORE THAN 20 FEET AND AT LEAST ONCE IN EACH ROOM AND EACH STORY TRAVERSED BY THE PIPING SYSTEM. ALL PIPING SHALL BE CLEARLY IDENTIFIED SPECIFICALLY FOR TYPE OF SERVICE WITH COILED PLASTIC PIPE MARKERS AND FLOW DIRECTION ARROWS.

15. VALVE IDENTIFICATION; PROVIDE A CIRCULAR BRASS TAG AND CHAIN ON EACH VALVE. TAG TO INCLUDE A DISCRETE NUMBER AND SHALL BE COORDINATED WITH ANY CURRENT FACILITY NUMBERING SCHEME OR STANDARD.

16. RECORD DRAWINGS; MAINTAIN A CURRENT SET OF MARKED UP CONSTRUCTION DRAWINGS ON SITE AT ALL TIMES. PROVIDE A COMPLETE SET OF THESE RECORD MARK-UPS TO THE ARCHITECT AT THE END OF THE PROJECT.

 $\frac{21\ 05\ 00\text{ - SPRINKLER SYSTEM DESIGN AND GENERAL}}{\text{REQUIREMENTS}}$

 DESIGN AND PERFORM FIRE SPRINKLER WORK PER THE REQUIREMENTS OF THE INTERNATIONAL BUILDING CODE (WITH MAINE AMENDMENTS), FM GLOBAL, AND NFPA 13.

 DESIGN AND INSTALL COMPLETE SYSTEMS, INCLUDING BUT NOT LIMITED TO: PIPE, FITTINGS, SPRINKLERS AND ACCESSORIES (ESCUTCHEONS AT THRU-WALL PENETRATIONS). PROVIDE FLOW, PRESSURE AND SUPERVISORY DEVICES. COORDINATE SYSTEM SUPERVISION WITH THE FIRE ALARM CONTRACTOR.

3. PROVIDE SUPPORTS PER NFPA 13, INCLUDING SEISMIC BRACING.

 PROVIDE AUTOCAD GENERATED SHOP/LAYOUT DRAWINGS AND HYDRAULIC CALCULATIONS FOR REVIEW AND APPROVAL PRIOR TO INSTALLATION.

5. DESIGN CRITERIA:5.1. GENERAL OFFICE SPACE: FM HC-1 OCCUPANCY:0.1 GPM OVER 1500 SF PLUS 250 GPM HOSE

5.2. BUILDING SERVICE AREAS, MECHANICAL ROOMS, ELECTRICAL ROOM, PRINT SHOP AND GENERAL STORAGE AREAS: FM HC-2 OCCUPANCY: 0.2 GPM/SF OVER 2500 SF PLUS 250 GPM HOSE

ALLOWANCE.
5.2.1. EXACT STORAGE ARRANGEMENT AND
PRODUCTS TO BE STORED TO BE VERIFIED.
STORAGE OCCUPANCIES TO BE DESIGNED
IN ACCORDANCE WITH NFPA 13 CHAPTERS
12-20 AND FM DATA SHEETS.

5.3. STORAGE OCCUPANCIES: PER FM DATA SHEETS.5.4. ALL OTHER AREAS: IN ACCORDANCE WITH NFPA13

DATA AS NECESSARY TO SERVE AS THE BASIS FOR HYDRAULICALLY CALCULATED SYSTEMS.

7. HYDRAULIC DESIGN CRITERIA, GENERAL:
A. MAXIMUM PIPE LINE VELOCITY: 25 FPS

B. MINIMUM CUSHION BETWEEN AVAILABLE WATER

6. WATER SUPPLY PERFORMANCE: OBTAIN FLOW TEST

SUPPLY AND SYSTEM REQUIREMENTS (FACTOR OF SAFETY) 10 PSIG.

9. INSTALL SYSTEM AS TIGHT TO STRUCTURE AS POSSIBLE TO MAXIMIZE AVAILABLE HEADROOM. ARRANGE SPRINKLERS IN LOGICAL PATTERNS.

CENTER HEADS IN CEILING TILES WHERE

APPLICABLE.

10. PROVIDE NEW SPRINKLER HEADS WITHIN SCOPE OF WORK AREA. COORDINATE BRANCH PIPE ROUTING WITH ALL MEP SYSTEMS. COORDINATE SPRINKLER HEAD LOCATION WITH CEILING MOUNTED DIFFUSERS, LIGHTS AND OTHER CEILING MOUNTED DEVICES AND PER NFPA 13 AND FM GLOBAL REQUIREMENTS.

22 10 00 - FIRE PROTECTION SPRINKLER PIPING SYSTEMS

 PROVIDE COMPONENTS AND INSTALLATIONS CAPABLE OF PRODUCING PIPING SYSTEMS WITH THE FOLLOWING MINIMUM WORKING PRESSURE RATINGS, UNLESS OTHERWISE NOTED:

A. FIRE PROTECTION SPRINKLER SYSTEMS: 175 PSIG.2. SYSTEM COMPONENTS TO BE UL LISTED OR FM

APPROVED.

3. ABOVE GRADE WET SYSTEM SPRINKLER PIPING (SPK)

PIPING THROUGHOUT.

A. PIPING 2-INCH AND SMALLER: SCHEDULE 40 STEEL WITH THREADED IRON FITTINGS.
B. PIPING 2-1/2-INCH AND LARGER: SCHEDULE 10 STEEL WITH GROOVED FITTINGS.

C. DRY PIPE SPRINKLER SYSTEM : SCHEDULE 40 STEEL

5. SPRINKLER SYSTEM VALVES AND SPECIALTIES: PROVIDE VALVES, INSPECTOR'S TEST STATIONS AND TRIM AS

NECESSARY.

D. INCLUDE HYDRAULIC PLACCARDS AND OTHER SIGNAGE AS REQUIRED BY NFPA 13.

E. BUTTERFLY CONTROL VALVES UP TO 2-1/2"

6. FIRE SPRINKLERS: QUICK RESPONSE, FM APPROVED SPRINKLERS THROUGHOUT. NON QUICK RESPONSE SPRINKLERS MUST BE APPROVED BY FM GLOBAL.

A. ROOMS WITH SUSPENDED CEILING: SEMI-RECESS

VICTAULIC #706 - 300 PSI SERIES.

TYPE SPRINKLERS WITH CHROME FINISH TO MATCH EXISTING

B. ROOMS WITHOUT CEILING: UPRIGHT WITH SPRINKLER GUARDS FOR SPRINKLERS SUBJECT TO MECHANICAL DAMAGE.


C. ROOMS WITH HARD DRYWALL CEILING: CONCEALED

TYPE SPRINKLERS.

D. PROVIDE SPRINKLERS WITH TEMPERATURE

RATINGS IN ACCORDANCE WITH NFPA 13.

7. FIRE SPRINKLER SYSTEM TESTING: TEST SYSTEMS PER NFPA 13 AREQUIREMNTS, AND AS DIRECTED BY THE AHJ. MAKE CORRECTIONS AND RETEST AS NECESSARY. PROVIDE NFPA 13 ABOVE-GRADE TEST REPORTS.




1. COMBINATION DRAIN AND TEST VALVE IS ACCEPTABLE IN LIEU OF INDIVIDUAL COMPONENTS, VICTAULIC STYLE 718 OR EQUAL.

INSPECTORS TEST STATION DETAIL (A1)

			F
			E
			ľ
	ISSUED FOR CONSTRUCTION	12-21-17	
V	DESCRIPTION	DATE	
	ISSUED FOR CONSTRUCTION		

12-21-17
CURRENT ISSUE STATUS:



SMRT Architects and Engineers 144 Fore Street Portland, Maine 04104 1.877.700.7678

1.877.700.7678
www.smrtinc.com
architecture | engineering | planning | interiors | energy
MAINE MEDICAL CENTER
M.M.C. HUTCHINS DRIVE

M.M.C. HUTCHINS DRIVE
RENOVATION

102 HUTCHINS DRIVE PORTLAND, ME

FIRE PROTECTION I FGEN

FIRE PROTECTION LEGEND,
DETAILS AND SPECIFICATIONS

SHEET TITLE:

0 1/4" 1/2" 1" 2"

SCALE: AS NOTED

PROJECT MANAGER: RSC PROJECT NO:

A/E OF RECORD: KDD

JOB CAPTAIN:

SMRT FILE:

SDL FP001

CWF FP001-17123 SHEET No. ©COPYRIGHT 2016 SM