



NOTE:

- SEE SHEET E-001 FOR LEGEND AND GENERAL NOTES.
- EXTEND EXISTING SIMPLE FIRE ALARM SYSTEM TO NEW NOTIFICATION AND INITIATING DEVICES SHOWN. PROVIDE ALL BOXES, CONDUIT, WIRING, DEVICES, EQUIPMENT, POWER SUPPLIES AND PROGRAMMING TO MAINTAIN A COMPLETE & OPERABLE SYSTEM.

KEYED NOTE:

- SEE SHEET EP102 FOR FLOOR BOX SPECIFICATION.
- RELOCATE SMOKE DETECTOR FROM CURRENT LOCATION SHOWN ON ED101. EXTEND EXISTING WIRING AS REQUIRED TO ACCOMMODATE NEW DEVICE LOCATION.
- MOUNT DATA OUTLET 60" AFF TO CENTER OF DEVICE.
- PROVIDE EMPTY OUTLET BOX AND 3/4" CONDUIT TO ABOVE CEILING FOR OWNER INSTALLED CARD READERS.
- MOUNT SMOKE DETECTORS INSIDE NEW ERU-1 SUPPLY AND RETURN DUCTS AND PROVIDE A REMOTE TEST STATION WALL MOUNTED IN SECOND FLOOR ELECTRICAL ROOM. UPON ACTIVATION DUCT SMOKE DETECTORS TO SHUT DOWN ERU-1 AND REPORT A TROUBLE SIGNAL TO THE FIRE ALARM CONTROL PANEL.

SECOND FLOOR PLAN (A1)
1/8" = 1'-0"

1	ADDENDUM 1	1-9-18
0	ISSUED FOR CONSTRUCTION	12-21-17
REV	DESCRIPTION	DATE

ISSUED FOR CONSTRUCTION
12-21-17

CURRENT ISSUE STATUS:

PROJECT NORTH:
SMRT Architects and Engineers
144 Fore Street
Portland, Maine 04104
1.877.700.7678
www.smrtinc.com

DAVID
TIBBATT
LICENSED PROFESSIONAL ENGINEER

ARCHITECTURE | ENGINEERING | PLANNING | INTERIORS | ENERGY **SMRT**

**MAINE MEDICAL CENTER
M.M.C. HUTCHINS DRIVE
RENOVATION**
102 HUTCHINS DRIVE PORTLAND, ME

**SECOND FLOOR
SYSTEMS PLAN**

SHEET TITLE:
0 1/4" 1/2" 1" 2" 3"

SCALE: AS NOTED

PROJECT MANAGER:	RSC	PROJECT NO.:	17123
A/E OF RECORD:	DJT		
JOB CAPTAIN:	SDL		
DRAWN BY:	CDS		
SMRT FILE:	EY102-17123	SHEET NO.:	EY102