



**NOTE:**  
 1. SEE SHEET M001 FOR LEGEND AND ABBREVIATIONS.

KEYNOTE NUMBER	KEYNOTE DESCRIPTION
1	GRILLES AND DIFFUSERS TO BE RELOCATED AS NECESSARY TO FIT NEW CEILING GRID LAYOUT.
2	REBALANCE EXISTING RGD TO INDICATED CFM.
3	EXISTING HEAT PUMPS TO BE FULLY DUCTED.
4	BALANCE EXHAUST GRILLES TO MAINTAIN POSITIVE PRESSURE IN THE SPACE AS DETERMINED DURING TAB.
5	BALANCE VOLUME DAMPER TO 1200 CFM.
6	BALANCE VOLUME DAMPER TO 600 CFM.
7	SET EXISTING HUMIDIFIER TO MAINTAIN RELATIVE HUMIDITY AT 45%-10% MAINTAIN TEMPERATURE BETWEEN 68-70 °F.

**FIRST FLOOR HVAC DUCTWORK NEW WORK PLAN** (A1)  
 1/8" = 1'-0"

1	ADDENDUM 1	1-9-18
0	ISSUED FOR CONSTRUCTION	12-21-17
REV	DESCRIPTION	DATE
<b>ISSUED FOR CONSTRUCTION</b>		
12-21-17		
CURRENT ISSUE STATUS:		
PROJECT NORTH: SMRT Architects and Engineers 144 Fore Street Portland, Maine 04104 1.877.700.7678 www.smrtinc.com		
<b>MAINE MEDICAL CENTER</b> <b>M.C. HUTCHINS DRIVE</b> <b>RENOVATION</b> 102 HUTCHINS DRIVE, PORTLAND, ME		
<b>FIRST FLOOR HVAC DUCTWORK</b> <b>NEW WORK PLAN</b>		
SHEET TITLE:		
SCALE: AS NOTED		
PROJECT MANAGER: RSC	PROJECT NO: 17123	
AVE OF RECORD: KDD		
JOB CAPTAIN: SDL		
DRAWN BY: CWF		
SMRT FILE: MH101-17123	SHEET NO.	
		<b>MH101</b>