



NOTE:
 1. SEE SHEET M001 FOR LEGEND AND ABBREVIATIONS.

KEYNOTE NUMBER	KEYNOTE DESCRIPTION
1	GRILLES AND DIFFUSERS TO BE RELOCATED AS NECESSARY TO FIT NEW CEILING GRID LAYOUT.
2	REBALANCE EXISTING RGD TO INDICATED CFM.
3	EXISTING HEAT PUMPS TO BE FULLY DUCTED.
4	BALANCE EXHAUST GRILLES TO MAINTAIN POSITIVE PRESSURE IN THE SPACE AS DETERMINED DURING TAB.
5	BALANCE VOLUME DAMPER TO 1200 CFM.
6	BALANCE VOLUME DAMPER TO 600 CFM.
7	SET EXISTING HUMIDIFIER TO MAINTAIN RELATIVE HUMIDITY AT 45%-10% MAINTAIN TEMPERATURE BETWEEN 68-70 °F.

FIRST FLOOR HVAC DUCTWORK NEW WORK PLAN (A1)
 1/8" = 1'-0"

1	ADDENDUM 1	1-9-18
0	ISSUED FOR CONSTRUCTION	12-21-17
REV	DESCRIPTION	DATE

ISSUED FOR CONSTRUCTION
 12-21-17

CURRENT ISSUE STATUS:

PROJECT NORTH:
 SMRT Architects and Engineers
 144 Fore Street
 Portland, Maine 04104
 1.877.700.7678
 www.smrtinc.com

MAINE MEDICAL CENTER
M.C. HUTCHINS DRIVE
RENOVATION
 102 HUTCHINS DRIVE, PORTLAND, ME

FIRST FLOOR HVAC DUCTWORK
NEW WORK PLAN

SHEET TITLE:
 0 1/4" 1/2" 1" 2" 3"

SCALE: AS NOTED

PROJECT MANAGER: RSC	PROJECT NO: 17123
AVE OF RECORD: KDD	
JOB CAPTAIN: SDL	
DRAWN BY: CWF	
SMRT FILE: MH101-17123	SHEET NO.

MH101