DOOR AND FRAME SCHEDULE - 1000 FACILITIES

DOOR #	DOOR WIDTH	DOOR HEIGHT	DOOR THICK	DOOR MAT'L	DOOR ELEV	GLAZ	FRAME MAT'L	FRAME ELEV	FRAME HEAD	FRAME JAMB	FRAME SILL	HARDWARE SET	FIRE RATING	DOOR #	REMARKS
1002A	3' - 0"	7' - 0"	0' - 1 3/4"											1002A	EXISTING
1002B	3' - 0"	7' - 0"	0' - 1 3/4"											1002B	EXISTING, CR
1003A	3' - 10"	8' - 2"	0' - 1 3/4"											1003A	EXISTING, CR
1003B	3' - 0"	7' - 0"	0' - 1 3/4"											1003B	EXISTING
1004A	3' - 0"	7' - 0"	0' - 1 3/4"											1004A	EXISTING
1004B	3' - 0"	7' - 0"	0' - 1 3/4"											1004B	EXISTING
1006	3' - 0"	7' - 0"	0' - 1 3/4"											1006	EXISTING, CONFIRM/PROVIDE CLOSER & POSITIVE LATCH
1007	3' - 0"	7' - 0"	0' - 1 3/4"	HM	F		HM	F1	N16/AE602	L16/AE602		HW3		1007	EXISTING, CONFIRM/PROVIDE CLOSER & POSITIVE LATCH
1014	6' - 0 3/16"	7' - 0"	0' - 1 3/4"	HM	N	FIRE	HM	F1	N16/AE602	L16/AE602		HW1	45 MIN.	1014	AO, CLOSER & POSITIVE LATCH
1020	3' - 0"	7' - 0"	0' - 1 3/4"	HM	N	FIRE	HM	F1	N16/AE602	L16/AE602		HW3	45 MIN.	1020	CR, CLOSER & POSITIVE LATCH
1021	3' - 0"	7' - 0"	0' - 1 3/4"	HM	F		HM	F1	N16/AE602	L16/AE602		HW3	45 MIN.	1021	CLOSER & POSITIVE LATCH
1022	3' - 0"	7' - 0"	0' - 1 3/4"	HM	F		HM	F1	N16/AE602	L16/AE602		HW3	45 MIN.	1022	CR, CLOSER & POSITIVE LATCH
1023	3' - 0"	7' - 0"	0' - 1 3/4"	HM	F		HM	F1	N16/AE602	L16/AE602		HW3		1023	EXISTING, CONFIRM/PROVIDE CLOSER & POSITIVE LATCH
1025	6' - 0"	7' - 0"	0' - 1 3/4"											1025	EXISTING, CONFIRM/PROVIDE CLOSER & POSITIVE LATCH
1031	3' - 0"	7' - 0"	0' - 1 3/4"											1031	EXISTING, CONFIRM/PROVIDE CLOSER & POSITIVE LATCH
1032	3' - 0"	7' - 0"	0' - 1 3/4"											1032	EXISTING, CONFIRM/PROVIDE CLOSER & POSITIVE LATCH

DOOR AND FRAME SCHEDULE - 1100 SHARED SPACES

DOOR #	DOOR WIDTH	DOOR HEIGHT	DOOR THICK	DOOR MAT'L	DOOR ELEV	GLAZ	FRAME MAT'L	FRAME ELEV	FRAME HEAD	FRAME JAMB	FRAME SILL	HARDWARE SET	FIRE RATING	DOOR #	REMARKS
1102	3' - 6"	7' - 0"	0' - 1 3/4"											1102	EXISTING
1103	6' - 0"	7' - 0"	0' - 1 3/4"											1103	EXISTING
1106	3' - 0"	7' - 0"	0' - 1 3/4"											1106	EXISTING
1107	3' - 0"	7' - 0"	0' - 1 3/4"											1107	EXISTING
1108A	3' - 0"	7' - 0"	0' - 1 3/4"											1108A	EXISTING, CR
1109	3' - 8"	7' - 0"	0' - 1 3/4"									HW1		1109	EXISTING - REINSTALL @ NEW HEIGHT
1111	3' - 0"	7' - 0"	0' - 1 3/4"											1111	EXISTING
1111A	3' - 0"	7' - 0"	0' - 1 3/4"											1111A	EXISTING
1112	3' - 0"	7' - 0"	0' - 1 3/4"											1112	EXISTING
1112A	3' - 0"	7' - 0"	0' - 1 3/4"											1112A	EXISTING
1113	3' - 0"	7' - 0"	0' - 1 3/4"											1113	EXISTING, CONFIRM/PROVIDE CLOSER & POSITIVE LATCH
1114A	4' - 0"	7' - 0"	0' - 1 3/4"	WD	N	FIRE	HM	F1	N16/AE602	L16/AE602		HW1	45 MIN.	1114A	CLOSER & POSITIVE LATCH
1114B	4' - 0"	7' - 0"	0' - 1 3/4"	HM	N	FIRE	HM	F1	N16/AE602	L16/AE602		HW1	45 MIN.	1114B	CLOSER & POSITIVE LATCH
1115	6' - 0"	7' - 0"	0' - 1 3/4"											1115	EXISTING, CONFIRM/PROVIDE CLOSER & POSITIVE LATCH
1116	3' - 0"	7' - 0"	0' - 1 3/4"	HM	F		HM	F1	N16/AE602	L16/AE602		HW2		1116	

DOOR AND FRAME SCHEDULE - 1200 N.I.S. - 2

DOOR #	DOOR WIDTH	DOOR HEIGHT	DOOR THICK	DOOR MAT'L	DOOR ELEV	GLAZ	FRAME MAT'L	FRAME ELEV	FRAME HEAD	FRAME JAMB	FRAME SILL	HARDWARE SET	FIRE RATING	DOOR #	REMARKS
1201A	3' - 0"	7' - 0"	0' - 1 3/4"											1201A	EXISTING
1201B	3' - 0"	7' - 0"	0' - 1 3/4"	HM	N	FIRE	HM	F1	N16/AE602	L16/AE602		HW3	45 MIN.	1201B	

DOOR AND FRAME SCHEDULE - 1300 N.I.S. - 4

DOOR #	DOOR WIDTH	DOOR HEIGHT	DOOR THICK	DOOR MAT'L	DOOR ELEV	GLAZ	FRAME MAT'L	FRAME ELEV	FRAME HEAD	FRAME JAMB	FRAME SILL	HARDWARE SET	FIRE RATING	DOOR #	REMARKS
1301	6' - 0"	7' - 0"	0' - 1 3/4"	HM	F		HM	F3	N16/AE602	L16/AE602		HW3		1301	

DOOR AND FRAME SCHEDULE - 1400 N.I.S. - 1

DOOR #	DOOR WIDTH	DOOR HEIGHT	DOOR THICK	DOOR MAT'L	DOOR ELEV	GLAZ	FRAME MAT'L	FRAME ELEV	FRAME HEAD	FRAME JAMB	FRAME SILL	HARDWARE SET	FIRE RATING	DOOR #	REMARKS
1401	6' - 0"	7' - 0"	0' - 1 3/4"	HM	N	FIRE	HM	F1	N16/AE602	L16/AE602		HW3	45 MIN.	1401	CLOSER & POSITIVE LATCH

DOOR AND FRAME SCHEDULE - 1500 PRINT SHOP

DOOR #	DOOR WIDTH	DOOR HEIGHT	DOOR THICK	DOOR MAT'L	DOOR ELEV	GLAZ	FRAME MAT'L	FRAME ELEV	FRAME HEAD	FRAME JAMB	FRAME SILL	HARDWARE SET	FIRE RATING	DOOR #	REMARKS
1501A	3' - 0"	7' - 0"	0' - 1 3/4"	HM	HG	TEMP	HM	F1	N16/AE602	L16/AE602		HW1		1501A	CLOSER & POSITIVE LATCH
1501B	6' - 0"	7' - 0"	0' - 1 3/4"	HM	N	FIRE	HM	F1	N16/AE602	L16/AE602		HW1	45 MIN.	1501B	AO, CLOSER & POSITIVE LATCH
1502	6' - 0"	7' - 0"	0' - 1 3/4"											1502	EXISTING
1504	3' - 0"	7' - 0"	0' - 1 3/4"	HM	HG	TEMP	HM	F1	N16/AE602	L16/AE602		HW1		1504	
1505	3' - 0"	7' - 0"	0' - 1 3/4"	HM	HG	TEMP	HM	F1	N16/AE602	L16/AE602		HW1		1505	
1506	3' - 0"	7' - 0"	0' - 1 3/4"	WD	F		HM	F1	N16/AE602	L16/AE602		HW3		1506	

DOOR AND FRAME SCHEDULE - 1600 WAREHOUSE

DOOR #	DOOR WIDTH	DOOR HEIGHT	DOOR THICK	DOOR MAT'L	DOOR ELEV	GLAZ	FRAME MAT'L	FRAME ELEV	FRAME HEAD	FRAME JAMB	FRAME SILL	HARDWARE SET	FIRE RATING	DOOR #	REMARKS
1601A	3' - 0"	7' - 0"	0' - 1 3/4"											1601A	EXISTING
1601B	3' - 0"	7' - 0"	0' - 1 3/4"											1601B	EXISTING
1601C	8' - 0"	8' - 0"	0' - 2"											1601C	EXISTING
1601D	8' - 0"	8' - 0"	0' - 2"											1601D	EXISTING
1601E	8' - 0"	8' - 0"	0' - 2"											1601E	EXISTING
1601F	8' - 0"	8' - 0"	0' - 2"											1601F	EXISTING
1602B	14' - 0"	14' - 0"	0' - 3"											1602B	EXISTING
1603A	8' - 0"	8' - 0"	0' - 2"											1603A	EXISTING
1603B	8' - 0"	8' - 0"	0' - 2"											1603B	EXISTING
1603C	8' - 0"	8' - 0"	0' - 2"											1603C	EXISTING
1603D	8' - 0"	8' - 0"	0' - 2"											1603D	EXISTING
1603E	8' - 0"	8' - 0"	0' - 2"											1603E	EXISTING
1603F	8' - 0"	8' - 0"	0' - 2"											1603F	EXISTING
1603G	3' - 0"	7' - 0"	0' - 1 3/4"			TEMP	HM	F1	N16/AE602	L16/AE602		HW1	45 MIN.	1603G	CLOSER & POSITIVE LATCH
1604A	3' - 0"	7' - 0"	0' - 1 3/4"											1604A	EXISTING, CONFIRM/PROVIDE CLOSER & POSITIVE LATCH
1604B	6' - 0"	7' - 0"	0' - 1 3/4"	HM	N	TEMP	HM	F1	N16/AE602	L16/AE602		HW3		1604B	CLOSER & POSITIVE LATCH
1604C	3' - 8"	7' - 0"	0' - 1 3/4"	HM	F		HM	F1	N16/AE602	L16/AE602		HW3	45 MIN.	1604C	CLOSER & POSITIVE LATCH
1605	3' - 0"	7' - 0"	0' - 1 3/4"											1605	EXISTING

DOOR AND FRAME SCHEDULE - N.I.S.

DOOR #	DOOR WIDTH	DOOR HEIGHT	DOOR THICK	DOOR MAT'L	DOOR ELEV	GLAZ	FRAME MAT'L	FRAME ELEV	FRAME HEAD	FRAME JAMB	FRAME SILL	HARDWARE SET	FIRE RATING	DOOR #	REMARKS
1700A	6' - 0"	7' - 0"	0' - 1 3/4"											1700A	EXISTING, CONFIRM/PROVIDE CLOSER & POSITIVE LATCH
1700B	3' - 0"	7' - 0"	0' - 1 3/4"											1700B	EXISTING
1803	4' - 0"	7' - 0"	0' - 1 3/4"											1803	EXISTING, CONFIRM/PROVIDE CLOSER & POSITIVE LATCH

DOOR AND FRAME SCHEDULE - 2000 FACILITIES

DOOR #	DOOR WIDTH	DOOR HEIGHT	DOOR THICK	DOOR MAT'L	DOOR ELEV	GLAZ	FRAME MAT'L	FRAME ELEV	FRAME HEAD	FRAME JAMB	FRAME SILL	HARDWARE SET	FIRE RATING	DOOR #	REMARKS
2002	3' - 0"	7' - 0"	0' - 1 3/4"										45 MIN.	2002	EXISTING
2003	3' - 0"	7' - 0"	0' - 1 3/4"										45 MIN.	2003	EXISTING, CR
2004	3' - 0"	7' - 0"	0' - 1 3/4"											2004	EXISTING, CR
2007	3' - 0"	7' - 0"	0' - 1 3/4"										45 MIN.	2007	EXISTING
2008	3' - 0"	7' - 0"	0' - 1 3/4"	HM	F		HM	F1	N16/AE602	L16/AE602		HW1	45 MIN.	2008	
2010	3' - 0"	7' - 0"	0' - 1 3/4"										45 MIN.	2010	EXISTING, CONFIRM/PROVIDE CLOSER & POSITIVE LATCH
2011	3' - 0"	7' - 0"	0' - 1 3/4"											2011	EXISTING, CONFIRM/PROVIDE CLOSER & POSITIVE LATCH
2022	3' - 0"	7' - 0"	0' - 1 3/4"	HM	F		HM	F1	N16/AE602	L16/AE602		HW3		2022	CR

DOOR AND FRAME SCHEDULE - 2100 SHARED SPACES

DOOR #	DOOR WIDTH	DOOR HEIGHT	DOOR THICK	DOOR MAT'L	DOOR ELEV	GLAZ	FRAME MAT'L	FRAME ELEV	FRAME HEAD	FRAME JAMB	FRAME SILL	HARDWARE SET	FIRE RATING	DOOR #	REMARKS
2101	6' - 0"	7' - 0"	0' - 1 3/4"											2101	EXISTING, CR

DOOR AND FRAME SCHEDULE - 2200 ADMINISTRATION

DOOR #	DOOR WIDTH	DOOR HEIGHT	DOOR THICK	DOOR MAT'L	DOOR ELEV	GLAZ	FRAME MAT'L	FRAME ELEV	FRAME HEAD	FRAME JAMB	FRAME SILL	HARDWARE SET	FIRE RATING	DOOR#	REMARKS
2202	3' - 0"	7' - 0"	0' - 1 3/4"											2202	EXISTING
2215A	3' - 0"	7' - 0"	0' - 1 3/4"											2215A	REUSE EXISTING SALVAGED DOOR AND FRAME
2215B	3' - 0"	7' - 0"	0' - 1 3/4"											2215B	REUSE EXISTING SALVAGED DOOR AND FRAME
2215C	5' - 0"	7' - 0"	0' - 1 3/4"											2215C	EXISTING
2216	3' - 0"	7' - 0"	0' - 1 3/4"	WD	HG	TEMP	HM	F1	N16/AE602	L16/AE602		HW1		2216	
2217	3' - 0"	7' - 0"	0' - 1 3/4"	WD	HG	TEMP	HM	F1	N16/AE602	L16/AE602		HW1		2217	
2218	3' - 0"	7' - 0"	0' - 1 3/4"											2218	EXISTING
2219	3' - 0"	7' - 0"	0' - 1 3/4"											2219	EXISTING
2222A	3' - 0"	7' - 0"	0' - 1 3/4"	WD	HG	TEMP	HM	F1	N16/AE602	L16/AE602		HW1		2222A	
2222B	3' - 0"	7' - 0"	0' - 1 3/4"	HM	F		HM	F1	N16/AE602	L16/AE602		HW3		2222B	CR
2223	3' - 0"	7' - 0"	0' - 1 3/4"	WD	F		HM	F1	N16/AE602	L16/AE602		HW2		2223	
2224	3' - 0"	7' - 0"	0' - 1 3/4"	WD	F		HM	F1	N16/AE602	L16/AE602		HW2		2224	
2225	3' - 0"	7' - 0"	0' - 1 3/4"									*		2225	EXISTING, PRIVACY HARDWARE
2226	3' - 0"	7' - 0"	0' - 1 3/4"											2226	EXISTING

WINDOW HEAD/JAMB DETAIL (C15)
3" = 1'-0"

DOOR JAMB DETAIL (A15)
3" = 1'-0"

DOOR HEAD DETAIL (A12)
3" = 1'-0"

WINDOW HEAD/JAMB DETAIL (A9)
3" = 1'-0"

WINDOW TYPES (E1)
1/4" = 1'-0"

DOOR FRAME TYPES (C1)
1/4" = 1'-0"

DOOR LEAF TYPES (A1)
1/4" = 1'-0"

Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 02/09/18

FIELD PAINT HINGES PRIOR TO PAINTING TO PROVIDE A CLEAN FINISHED APPEARANCE.
10. ALL LABELS ON RATED DOORS TO BE FREE OF PAINT AND CLEARLY VISIBLE UPON INSPECTION.

DOOR ABBREVIATIONS:

AL	ALUMINUM
FG	FIBERGLASS
HM	HOLLOW METAL
IN	INSULATED
SF	STOREFRONT
SS	STAINLESS STEEL
TEMP	TEMPERED GLASS
WIRE	WIRED GLASS

DOOR HARDWARE SETS:

HW1: LOCKSET (PASSAGE FUNCTION), HINGES, DOOR STOP, DOOR SILENCERS

HW2: LOCKSET (PRIVACY FUNCTION), HINGES, DOOR STOP, DOOR SILENCERS

HW3: LOCKSET (STORAGE FUNCTION), HINGES, DOOR STOP, DOOR SILENCERS

HW4: LOCKSET (OFFICE/CLASSROOM FUNCTION), HINGES, DOOR STOP, DOOR SILENCERS

CR = CARD READER
AO = AUTO OPERATOR

DOOR HARDWARE NOTES:

1. DOORS LABELED AS "EXISTING" SHALL HAVE THEIR CYLINDERS REPLACED WITH M.M.C. STANDARD DOOR CYLINDERS. COORDINATE KEYING WITH OWNER.
2. ALL FIRE RATED DOORS TO RECEIVE SMOKE SEALS AND CLOSERS.
3. NEW DOORS HARDWARE TO HAVE LEVER HANDLES THAT MEET ADA REQUIREMENTS.
4. MMC STANDARDS FOR HARDWARE:

LOCKSETS	SARGENT
CYLINDERS	SARGENT REMOVABLE CORES (NO EXCEPTIONS)
EXIT DEVICES	SARGENT (NO EXCEPTIONS)
DOOR CLOSERS	SARGENT (NO EXCEPTIONS)
OPERATORS	HORTON, LOW ENERGY

REV	DESCRIPTION	DATE
2	SUPPLEMENTAL INSTRUCTION 002	2-6-18
1	SUPPLEMENTAL INSTRUCTION 001	1-25-18
0	ISSUED FOR CONSTRUCTION	12-21-17

SUPPLEMENTAL INSTRUCTION 002
2-6-18

CURRENT ISSUE STATUS:

LICENSED ARCHITECT REBECCA S. SADOW No. 2315 12/21/17 STATE OF MAINE

SMRT Architects and Engineers
144 Fore Street/P.O. Box 618
Portland, Maine 04104
ARCHITECTURE | ENGINEERING | PLANNING | INTERIORS | ENERGY

MAINE MEDICAL CENTER
M.M.C. HUTCHINS DRIVE RENOVATION
PROJECT LOCATION

DOOR SCHEDULE

SHEET TITLE:

SCALE: AS NOTED

PROJECT MANAGER:	RSC	PROJECT NO:	17123
A/E OF RECORD:	RSC		
JOB CAPTAIN:	SDL	AE601	
DRAWN BY:	SDL/JMM		
SMRT FILE:	AE601-17123	SHEET No.	

COPYRIGHT 2017 SMRT INC