NOTE:

1. SEE SHEET M001 FOR LEGEND AND ABBREVIATIONS.

KEYNOTES

KEYNOTE NUMBER	KEYNOTE DESCRIPTION
1	REBALANCE RGD TO INDICATED AIRFLOW.
2	22"x14" SA & 22"x14" RA UP TO ERU-1 ON ROOF. REFER TO PL401 FOR PARTIAL ROOF PLAN.
3	RS/RL UP TO CONDENSING UNIT. SEE TO PL401 FOR PARTIAL ROOF PLAN.
4	BALANCE (E) RTU-2 TO PROVIDE 25% OA (ADJ). TO MAINTAIN NEGATIVE SPACE PRESSURE RELATIONSHIP IN PRINTSHOP.
5	RELOCATED T-STAT.

HVAC DUCTWORK ROOF PART PLAN A13
1/8" = 1'-0"

SECOND FLOOR HVAC DUCTWORK NEW WORK PLAN A1
1/8" = 1'-0"

CITY OF PORTLAND, MAINE
RESURGAM

Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 02/09/18

REV	DESCRIPTION	DATE
1	ADDENDUM 1	1-9-18
0	ISSUED FOR CONSTRUCTION	12-21-17

ISSUED FOR CONSTRUCTION
12-21-17

CURRENT ISSUE STATUS:

PROJECT NORTH:

STATE OF MAINE
KERRY D. DINEEN
13301
LICENSED
PROFESSIONAL ENGINEER
1-9-18

SMRT Architects and Engineers
144 Fore Street
Portland, Maine 04104
1.877.700.7678
www.smrtinc.com
ARCHITECTURE | ENGINEERING | PLANNING | INTERIORS | ENERGY
SMRT

MAINE MEDICAL CENTER
M.M.C. HUTCHINS DRIVE
RENOVATION
102 HUTCHINS DRIVE PORTLAND, ME

SECOND FLOOR HVAC DUCTWORK
NEW WORK PLAN

SHEET TITLE:

0 1/4" 1/2" 1" 2" 3"

SCALE: AS NOTED

PROJECT MANAGER:	RSC	PROJECT NO:	17123
A/E OF RECORD:	KDD		
JOB CAPTAIN:	SDL		
DRAWN BY:	CWF		
SMRT FILE:	MH102-17123	SHEET No.	MH102

©COPYRIGHT 2016 SMRT INC.