NOTE:

1. SEE SHEET M001 FOR LEGEND AND ABBREVIATIONS.

KEYNOTES

KEYNOTE NUMBER	KEYNOTE DESCRIPTION
1	GRILLES AND DIFFUSERS TO BE RELOCATED AS NECESSARY TO FIT NEW CEILING GRID LAYOUT.
2	REBALANCE EXISTING RGD TO INDICATED CFM
3	EXISTING HEAT PUMPS TO BE FULLY DUCTED.
4	BALANCE EXHAUST GRILLES TO MAINTAIN POSITIVE PRESSURE IN THE SPACE AS DETERMINED DURING TAB.
5	BALANCE VOLUME DAMPER TO 1200 CFM.
6	BALANCE VOLUME DAMPER TO 600 CFM.
7	SET EXISTING HUMIDIFIER TO MAINTAIN RELATIVE HUMIDITY AT 45% ±10% MAINTAIN TEMPERATURE BETWEEN 68-70 °F .

FIRST FLOOR HVAC DUCTWORK NEW WORK PLAN (A1)
1/8" = 1'-0"

CITY OF PORTLAND, MAINE — RESURGAM

Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 02/09/18

REV	DESCRIPTION	DATE
1	ADDENDUM 1	1-9-18
0	ISSUED FOR CONSTRUCTION	12-21-17

ISSUED FOR CONSTRUCTION
12-21-17

CURRENT ISSUE STATUS:

PROJECT NORTH:

STATE OF MAINE — KERRY D. DINEEN — 13301 — LICENSED PROFESSIONAL ENGINEER — 1-18-18

SMRT Architects and Engineers
144 Fore Street
Portland, Maine 04104
1.877.700.7678
www.smrtinc.com
ARCHITECTURE | ENGINEERING | PLANNING | INTERIORS | ENERGY

MAINE MEDICAL CENTER
M.M.C. HUTCHINS DRIVE
RENOVATION
102 HUTCHINS DRIVE PORTLAND, ME

FIRST FLOOR HVAC DUCTWORK
NEW WORK PLAN

SHEET TITLE:

SCALE: AS NOTED

PROJECT MANAGER:	RSC	PROJECT NO:	17123
A/E OF RECORD:	KDD		
JOB CAPTAIN:	SDL		
DRAWN BY:	CWF		
SMRT FILE:	MH101-17123	SHEET No.	MH101

©COPYRIGHT 2016 SMRT INC.