NOTE:

1. SEE SHEET M001 FOR LEGEND AND ABBREVIATIONS.

KEYNOTES	
KEYNOTE NUMBER	KEYNOTE DESCRIPTION
1	DISCONNECT FROM HP AND CAP EXISTING 3/4" HPWS/R.
2	TAB CONTRACTOR TO PERFORM PRE-CONSTRUCTION. TAB ON ALL EXISTING SUPPLY AND RETURN GRILLES AND ASSOCIATED EQUIPMENT (EXHAUST FANS, AIR HANDLING UNITS, HEAT PUMPS, ETC.). REPORT FINDINGS TO OWNER AND ENGINEER PRIOR TO DEMOLITION.
3	EXISTING T-STAT TO BE RELOCATED. SEE MH102 FOR NEW LOCATION.

SECOND FLOOR HVAC DUCTWORK DEMOLITION PLAN (A1)
1/8" = 1'-0"

CITY OF PORTLAND, MAINE — RESURGAM

Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 02/09/18

REV	DESCRIPTION	DATE
0	ISSUED FOR CONSTRUCTION	12-21-17

ISSUED FOR CONSTRUCTION
12-21-17
CURRENT ISSUE STATUS:

PROJECT NORTH:

STATE OF MAINE — KERRY J. DINEEN 13301 — LICENSED PROFESSIONAL ENGINEER — 12-21-17

SMRT Architects and Engineers
144 Fore Street
Portland, Maine 04104
1.877.700.7678
www.smrtinc.com
ARCHITECTURE | ENGINEERING | PLANNING | INTERIORS | ENERGY

MAINE MEDICAL CENTER
M.M.C. HUTCHINS DRIVE
RENOVATION
102 HUTCHINS DRIVE PORTLAND, ME

SECOND FLOOR HVAC DUCTWORK DEMOLITION PLAN

SHEET TITLE:

0 1/4" 1/2" 1" 2" 3"
SCALE: AS NOTED

PROJECT MANAGER:	RSC	PROJECT NO:	17123
A/E OF RECORD:	KDD		
JOB CAPTAIN:	SDL		
DRAWN BY:	CWF		
SMRT FILE:	MD102-17123	SHEET No.	MD102

© COPYRIGHT 2016 SMRT Inc.

30x42