NOTE:

1. SEE SHEET E-001 FOR LEGEND AND GENERAL NOTES.
2. EXTEND EXISTING SIMPLEX FIRE ALARM SYSTEM TO NEW NOTIFICATION AND INITIATING DEVICES SHOWN. PROVIDE ALL BOXES, CONDUIT, WIRING, DEVICES, EQUIPMENT, POWER SUPPLIES AND PROGRAMMING TO MAINTAIN A COMPLETE & OPERABLE SYSTEM.

KEYED NOTE:

1. SEE SHEET EP102 FOR FLOOR BOX SPECIFICATION.
2. RELOCATE SMOKE DETECTOR FROM CURRENT LOCATION SHOWN ON ED101. EXTEND EXISTING WIRING AS REQUIRED TO ACCOMMODATE NEW DEVICE LOCATION.
3. MOUNT DATA OUTLET 60" AFF TO CENTER OF DEVICE.
4. PROVIDE EMPTY OUTLET BOX AND 3/4" CONDUIT TO ABOVE CEILING FOR OWNER INSTALLED CARD READERS.
5. MOUNT SMOKE DETECTORS INSIDE NEW ERU-1 SUPPLY AND RETURN DUCTS AND PROVIDE A REMOTE TEST STATION WALL MOUNTED IN SECOND FLOOR ELECTRICAL ROOM. UPON ACTIVATION DUCT SMOKE DETECTORS TO SHUT DOWN ERU-1 AND REPORT A TROUBLE SIGNAL TO THE FIRE ALARM CONTROL PANEL.

SECOND FLOOR PLAN (A1)
1/8" = 1'-0"

CITY OF PORTLAND, MAINE — RESURGAM

Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 02/09/18

REV	DESCRIPTION	DATE
1	ADDENDUM 1	1-9-18
0	ISSUED FOR CONSTRUCTION	12-21-17

ISSUED FOR CONSTRUCTION
12-21-17
CURRENT ISSUE STATUS:

PROJECT NORTH:

STATE OF MAINE — DANIEL J. TIBBETS — 7/18/2018 — 9830 — LICENSED PROFESSIONAL ENGINEER

SMRT Architects and Engineers
144 Fore Street
Portland, Maine 04104
1.877.700.7678
www.smrtinc.com
ARCHITECTURE | ENGINEERING | PLANNING | INTERIORS | ENERGY

MAINE MEDICAL CENTER
M.M.C. HUTCHINS DRIVE
RENOVATION
102 HUTCHINS DRIVE PORTLAND, ME

SECOND FLOOR
SYSTEMS PLAN

SHEET TITLE:

SCALE: AS NOTED

PROJECT MANAGER:	RSC	PROJECT NO:	17123
A/E OF RECORD:	DJT		
JOB CAPTAIN:	SDL		
DRAWN BY:	CDS		
SMRT FILE:	EY102-17123	SHEET No.	EY102

©COPYRIGHT 2016 SMRT INC.