NOTE:

1. SEE SHEET E-001 FOR LEGEND AND GENERAL NOTES.
2. ALL EXISTING LIGHTS SHOWN SHALL REMAIN. EXISTING LIGHTS TO BE CLEANED, RELAMPED AND REPAIRED IF NEEDED PRIOR TO OWNER OCCUPYING THE SPACE.
3. ALL EMERGENCY LIGHTING BATTERY CABINETS FEEDING REMOTE HEADS SHALL BE TESTED TO VERIFY THEY COMPLY WITH LIFE SAFETY CODE REQUIREMENTS FOR EGRESS LIGHTING. REPLACE ANY BATTERIES THAT DO NOT COMPLY WITH TESTING REQUIREMENTS OF NFPA 101.

KEYED NOTE:

1. RELOCATE EXIT SIGN AND EMERGENCY LIGHTING REMOTE HEADS FROM CURRENT LOCATION SHOWN ON ED102 TO NEW LOCATION SHOWN. EXTEND EXISTING WIRING AS REQUIRED TO ACCOMMODATE NEW DEVICE LOCATIONS.
2. UTILIZE TWO EXISTING 20 AMP, SINGLE POLE SPARE CIRCUIT BREAKERS IN EXISTING PANELBOARD LP3 TO FEED NEW LIGHTS SHOWN. CIRCUIT #10 CURRENTLY FEEDS LIGHTS IN ELECTRICAL ROOM AND WILL BE EXTEND OUT TO FEED LIGHTS NEW OFFICES. CIRCUIT #12 CURRENTLY FEEDS LIGHTS THAT ARE SHOWN TO BE REMOVED ON ED102 AND WILL BE EXTENDED AS REQUIRED TO FEED NEW LIGHTS INDICATED.
3. NEW EXIT SIGNS TO BE FED FROM SAME UNSWITCHED CIRCUIT THAT FEEDS EMERGENCY LIGHTING UNITS.

SECOND FLOOR PLAN (A1)
1/8" = 1'-0"

CITY OF PORTLAND, MAINE · RESURGAM

Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 02/09/18

REV	DESCRIPTION	DATE
1	SUPPLEMENTAL INSTRUCTION 002	2-6-18
0	ISSUED FOR CONSTRUCTION	12-21-17

SUPPLEMENTAL INSTRUCTION 002
2-6-18

CURRENT ISSUE STATUS:

TRUE NORTH

PROJECT NORTH:

SMRT Architects and Engineers
144 Fore Street
Portland, Maine 04104
1.877.700.7678
www.smrtinc.com
ARCHITECTURE | ENGINEERING | PLANNING | INTERIORS | ENERGY
SMRT

MAINE MEDICAL CENTER
M.M.C. HUTCHINS DRIVE
RENOVATION
102 HUTCHINS DRIVE PORTLAND, ME

SECOND FLOOR
LIGHTING PLAN

SHEET TITLE:

0 1/4" 1/2" 1" 2" 3"

SCALE: AS NOTED

PROJECT MANAGER:	RSC	PROJECT NO:	17123
A/E OF RECORD:	DJT		
JOB CAPTAIN:	SDL		
DRAWN BY:	CDS		
SMRT FILE:	EL102-17123	SHEET No.	EL102

© COPYRIGHT 2016 SMRT Inc.