NOTE:

1. SEE SHEET E-001 FOR LEGEND AND GENERAL NOTES.

KEYED NOTE:

1. MOUNT RECEPTACLE 42" AFF TO BOTTOM OF DEVICE.
2. FURNISH & INSTALL A HUBBELL MODEL #PT2XTBL OR EQUAL POKE THROUGH FLOOR BOX WITH BLACK FURNITURE FEED COVER.
3. FURNISH & INSTALL A HUBBELL MODEL #PT2XTBL OR EQUAL POKE THROUGH FLOOR BOX AND TWO VOICE DATA INSERTS. WIRING TO BE 4#12 AWG, #10 AWG NEUTRAL & #10 AWG GND, 3/4"C.
4. MOUNT RECEPTACLE 60" AFF TO CENTER OF DEVICE.
5. INDOOR SECTION OF SPLIT SYSTEM TO BE FED VIA OUTDOOR CONDENSING UNIT. COORDINATE WITH MECHANICAL CONTRACTOR FOR WIRING REQUIRED BETWEEN INDOOR UNIT AND CONDENSING UNIT.
6. MOUNT RECEPTACLE RECESSED IN CEILING FOR PROJECTOR. MOUNT RECEPTACLE ADJACENT TO PROJECTOR SUPPORTS.
7. PROVIDE POWER FOR MOTOR OPERATED SCREEN AND WIRING FROM SCREEN OPERATOR TO SCREEN CONTROLLER. COORDINATE WITH OWNER FOR MOUNTING LOCATION OF SCREEN CONTROLLER.
8. IN EXISTING PANELBOARDS PP5-1, PP5-2, PP6-1, PP6-2 AND PP7-1 UTILIZE EXISTING 20 AMP, SINGLE POLE SPARE CIRCUIT BREAKERS TO FEED NEW MODULAR FURNITURE AND RECEPTACLES. EXISTING WIRING FOR MODULAR FURNITURE MAY STILL REMAIN IN FIRST FLOOR CEILING CAVITY.
9. IN EXISTING PANELBOARD MP4 UTILIZE THREE EXISTING 20 AMP, SINGLE POLE SPARE CIRCUIT BREAKERS TO FEED MOTORIZED SCREEN AND RECEPTACLES. PROVIDE THREE NEW 20 AMP, TWO POLE SPARE CIRCUIT BREAKERS TO FEED NEW CONDENSING UNITS CU-1303, CU-2009. CU-2022 AND A 40 AMP, TWO POLE CIRCUIT BREAKER TO FEED NEW CONDENSING UNIT CU-1022.
10. IN EXISTING PANELBOARDS LP3 UTILIZE AN EXISTING 20 AMP, SINGLE POLE SPARE CIRCUIT BREAKER TO FEED NEW HEAT PUMP.
11. IN EXISTING PANELBOARD MP3-1 UTILIZE AN EXISTING 30 AMP, THREE POLE SPARE CIRCUIT BREAKER TO FEED NEW AIR HANDLING UNIT.
12. PROVIDE POWER FOR SPLIT SYSTEM AND HEAT PUMP CONDENSATE PUMPS. COORDINATE WITH MECHANICAL CONTRACTOR FOR EXACT PLACEMENT OF PUMPS.

SECOND FLOOR PLAN (A1)
1/8" = 1'-0"

CITY OF PORTLAND, MAINE — RESURGAM

Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 02/09/18

REV	DESCRIPTION	DATE
0	ISSUED FOR CONSTRUCTION	12-21-17

ISSUED FOR CONSTRUCTION
12-21-17

CURRENT ISSUE STATUS:

PROJECT NORTH:

STATE OF MAINE — DANIEL J. TIBBETTS — 9838 — LICENSED PROFESSIONAL ENGINEER — 12/21/17

SMRT Architects and Engineers
144 Fore Street
Portland, Maine 04104
1.877.700.7678
www.smrtinc.com
ARCHITECTURE | ENGINEERING | PLANNING | INTERIORS | ENERGY
SMRT

MAINE MEDICAL CENTER
M.M.C. HUTCHINS DRIVE
RENOVATION
102 HUTCHINS DRIVE PORTLAND, ME

SECOND FLOOR
POWER PLAN

SHEET TITLE:

0 1/4" 1/2" 1" 2" 3"

SCALE: AS NOTED

PROJECT MANAGER:	RSC	PROJECT NO:	17123
A/E OF RECORD:	DJT		
JOB CAPTAIN:	SDL		
DRAWN BY:	CDS		
SMRT FILE:	EP102-171123	SHEET No.	EP102

© COPYRIGHT 2016 SMRT Inc.