Inspections Division
Date: 09/09/13

Submittal Data: ASU12RLF

FUJITSU

Job Name: Location:

Purchaser:

Engineer:

Submitted To: For: ❑ Reference ❑ Approval ❑ Construction

Submitted By:

Unit Designation: Schedule No. Model No.:

Capacities:

Cooling	12,000 BTU/h
Outdoor Design Temp. *F° DB/WB*	95/75
Heating	13,500 BTU/h
Outdoor Design Temperature *F° DB/WB*	47/43
HSPF	
Ducted	9.3
Non-Ducted	9.8
Mixed	9.5
SEER	
Ducted	14.7
Non-Ducted	17.0
Mixed	15.8
EER *Cooling*	
Ducted	8.7
Non-Ducted	9.25
Mixed	8.97
Voltage/Frequency/Phase	208-230/60/1

Indoor Unit:

Noise Level Cooling *db (A) - H/ M/ L/ Q*	40/36/30/25
Noise Level Heating *db (A) - H/ M/ L/ Q*	40/36/31/25
Weight	18 lbs.

Refrigerant Piping:*

Discharge Vapor Line (O.D.)	1/4 in.
Suction (O.D.)	3/8 in.

OUTLINE AND DIMENSIONS

Standard Features:

- Seven year compressor warranty
- Five year parts warranty
- Digital wireless remote control
- Auto Louver: Up/Down
- Apple Catechin / Ion Deodorizing Filters
- Sleep Timer
- Auto Restart/ Reset
- 24 hour timer
- Quiet Mode
- Dry mode
- Refrigerant R410A

Notes:

*Piping lengths vary by outdoor unit. See outdoor unit submittal sheet for detailed specifications.

Halcyon HFI Hybrid Flex Inverter