

DISPLAY THIS CARD ON PRINCIPAL FRONTAGE OF WORK



# CITY OF PORTLAND BUILDING PERMIT



This is to certify that  
CITY OF PORTLAND

Located at  
0 RAND RD (97 Technology Park)

PERMIT ID: 2016-02853      ISSUE DATE: 01/25/2017      CBL: 249 A001001

has permission to **For the installation of a Water-Based Fire Suppression System for "Patrons Oxford Insurance".**

provided that the person or persons, firm or corporation accepting this permit shall comply with all of the provisions of the Statues of Maine and of the Ordinances of the City of Portland regulating the construction, maintenance and use of the buildings and structures, and of the application on file in the department.

Notification of inspection and written permission procured before this building or part thereof is lathed or otherwise closed-in. 48 hour notice is required.

A final inspection must be completed before this building or part thereof is occupied. If a certificate of occupancy is required, it must be procured prior to occupancy.

*/s/ David Petruccelli*

*/s/ Michael Russell, MS, Director*

**Fire Official**

**Building Official**

**THIS CARD MUST BE POSTED ON THE STREET SIDE OF THE PROPERTY  
THERE IS A PENALTY FOR REMOVING THIS CARD**

*Approved Property Use - Zoning*

*Building Inspections*

*Fire Department*

**Classification:**

Business

ENTIRE

BUILDING PERMIT INSPECTION PROCEDURES  
Please call 874-8703  
or email: [buildinginspections@portlandmaine.gov](mailto:buildinginspections@portlandmaine.gov)

**Check the Status of Permit or Schedule an Inspection at  
<http://www.portlandmaine.gov/planning/permitstatus.asp>**

With the issuance of this permit, the owner, builder or their designee is required to provide adequate notice to the City of Portland Inspections Division for the inspections listed below. Appointments must be requested 48 to 72 hours in advance. The inspection date will need to be confirmed by this office.

- **Please read the conditions of approval that are attached to this permit.**
- **Permits expire in 6 months if the project is not started or ceases for 6 months.**
- **If the inspection requirements below are not followed, then additional fees may be incurred due to the issuance of a "Stop Work Order" and subsequent release to continue.**
- **Per Section 107.3.1 of the Maine Uniform Building and Energy Code (MUBEC), one set of printed approved stamped construction documents will be kept at the site of work and open to inspection by building officials.**

## **REQUIRED INSPECTIONS:**

FP Sprinkler

The project cannot move to the next phase prior to the required inspection and approval to continue.

If the permit requires a certificate of occupancy, it must be paid and issued to the owner or designee before the space may be occupied.

<b>City of Portland, Maine - Building or Use Permit</b>		<b>Permit No:</b> 2016-02853	<b>Date Applied For:</b> 11/08/2016	<b>CBL:</b> 249 A001001
389 Congress Street, 04101 Tel: (207) 874-8703, Fax: (207) 874-8716				
<b>Proposed Use:</b> Same: Office - ("Patrons Oxford Insurance")		<b>Proposed Project Description:</b> For the installation of a Water-Based Fire Suppression System for "Patrons Oxford Insurance".		
<b>Dept:</b> Zoning	<b>Status:</b> Approved	<b>Reviewer:</b> Jennifer Thompson	<b>Approval Date:</b> 01/05/2017	
<b>Note:</b>				<b>Ok to Issue:</b> <input checked="" type="checkbox"/>
<b>Conditions:</b>				
<b>Dept:</b> Fire	<b>Status:</b> Approved w/Conditions	<b>Reviewer:</b> David Petrucci	<b>Approval Date:</b> 01/24/2017	
<b>Note:</b>				<b>Ok to Issue:</b> <input checked="" type="checkbox"/>
<b>Conditions:</b>				
1) The approved plans with the Building Department Approved stamp shall be maintained on site for inspection.				
2) Notice: The first scheduled final inspection fee is at no charge. Additional inspections shall be billed at \$75 for each inspector.				
3) Through-penetrations and membrane penetrations in fire walls, fire barrier walls, and fire resistance rated horizontal assemblies shall be protected by firestop systems or devices in conformance with NFPA 101:8.3.5 (ASTM E 814 or ANSI/UL 1479). Providing firestop labels at each firestop system or device and an onsite manual containing the detail for each firestop system or device used for the project will streamline final inspection approvals.				
4) A Knox Box is required.				
5) The entire sprinkler system shall be maintained in accordance with NFPA 25, Standard for Inspection, Testing and Maintenance of Water-Based Fire Protection Systems, 2008 edition.				
6) System acceptance and commissioning must be coordinated with a fire alarm technician and suppression system contractors and the Fire Department. Call 874-8400 to schedule.				
7) Fire department connection shall be two 2 ½" inlets. Unobstructed by plantings, with an improved surface.				
8) A sprinkler supervisory system shall be provided in accordance with NFPA 101, Life Safety Code, and NFPA 72, National Fire Alarm and Signaling Code. Sprinkler supervisory systems shall monitor for water flow and sprinkler supervisory signals via an approved fire alarm panel to central station. One smoke detector shall be located over the panel, a manual pull station located at the front door, and an audible water flow alarm provided. A separate fire alarm permit is required from a certified fire alarm company.				
9) Sprinkler supervision shall be provided in accordance with NFPA 101, Life Safety Code, and NFPA 72, National Fire Alarm and Signaling Code.				
10) Installation shall be in accordance with the City of Portland Fire Department Regulations and NFPA 13 as published. A copy of the State Sprinkler permit with RMS date and signature and the Contractor's Material and Test Certificate for Aboveground Piping (NFPA 13 figure 24.1) shall be provided prior to scheduling of the final inspection.				