JOB#:

ITEM MANUFACTURING

(Barlo) BarloMex Sub Other: _____

ITEM INSTALLATION

(Barlo) BarloMex Sub Other: _____

ITEM SCOPE OF WORK

ITEM A - MANUFACTURE & INSTALL
(1) LEXAN FACE TO REPLACE THE EXISTING.
RELAMP

Sign Area: 118.5 SQ. FT.

GENERAL NOTES

RELAMP EXISTING SIGN

COLORS

SIGN

Cabinet: EXISTING

Retainer: EXISTING

Face B/G: WHITE LEXAN w/ APPLIED VINYL

Copy:
"HVAC/R..." 3630-22 BLACK (REVERCE CUT WHITE)

"CE":
3630-97 BRISTOL BLUE, 3630-156
VIVID GREEN, 3630-54 ORANGE, 3630-43
TOMATO RED.

"BRYANT":
3630-43 TOMATO RED.
3630-22 BLACK

"HOMANS":
3630-015 YELLOW (MATCH PMS 7405)
3630-157 SULTAN BLUE (MATCH PMS 286)

"MITSUBISHI":
LOGO - 3033-36 RED
3630-22 BLACK

ALL COLORS ARE FOR REPRESENTATION ONLY. SEE ACTUAL SAMPLES FOR COLOR MATCH.

SIGN DISPOSITION

☐Store for Barlo ☐Leave @ Site ☐Dispose
☐Store for Customer ☐Chargeable ☐N/A

MANUFACTURING INFORMATION

(S/F) D/F	(ILL.) Non-ILL
Interior (Exterior)	(Custom) Extrusion
Cabinet Depth:	**Ret.Size:**
Framing: **Steel** **Alum.**	
Face Mat: LEXAN	**Th:** 3/16"
Copy: VINYL	
UL Sticker Loc: (Stnd) **Top**	
Illumination: (Fluorescent) **Neon** **LED** **HID** **Other**	
Ballast: **Standard** (Electronic)	

ITEM A - (1) LEXAN FACE. (FACE REPLACEMENT)

SCALE: 1/4"=1'-0"

EXISTING

PROPOSED SCALE: 1/8"=1'-0"

ELECTRIC	Existing	Required	STEEL	Existing	Required
Circuits			Size		
Amp			Length		
Voltage			W. Thickness		
U.L.			Stub Size		
Suitable Location: ☐Wet ☐Damp ☐Dry			Stub Length		
Notes:			W. Thickness		
			PLATE	W L	Th
			GUSSETS	W L	Th

This sign is intended to be installed in accordance with the requirements of Article 600 of the National Electric Code and/or other applicable local codes. This includes proper grounding and bonding of the sign

REVISIONS

Date	Comment
9/16/13	CHANGE GRAPHICS ON A SIGN (LOGOS)
9/17/13	LAYOUT CHANGE

TIME SUMMARY

0-Art/Eng. _____ Arte/Ingenieria	5-Neon _____ Neon
1-Pat/Vin. _____ Patrones/Vinyl	6-Finish _____ Acabado
2-Let. Fab. _____ Letras Fabricacion	7-Paint _____ Pintura
3-Screen _____ Pantalla	8-Install _____ Instalacion
4-Met. Fab. _____ Fabricacion	9-Misc. _____ Miselaneos

PROJECT APPROVAL - PRESALE	
Design:	Date:
Sales:	Date:
PROJECT APPROVAL - PROD.	
Design:	Date:
Estimating:	Date:
Engineering:	Date:
Sales:	Date:
Production:	Date:
Installation	Date:

Job Name: HOMANS

Location: 111C PINETREE INDUSTRIAL PARKWAY, PORTLAND ME 04103

Design Specifications Accepted By:

Client:

Landlord:

Drawn By: NM

Sales Rep: MALT

Date: 10/18/13

© COPYRIGHT 2013 THE BARLO GROUP
THIS DESIGN CONCEPT IS THE PROPERTY OF THE BARLO GROUP, ALL PRODUCTION AND DUPLICATION RIGHTS ARE RESERVED BY THE BARLO GROUP. THIS PRINT IS DESIGNED FOR YOUR PERSONAL USE AND IS NOT TO BE USED OUTSIDE YOUR ORGANIZATION OR EXHIBITED IN ANY FASHION.

Underwriters Laboratories Inc.®

BARLO SIGNS
158 Greeley St., Hudson, NH 03051
(603) 882-2638 Fax (603) 882-7680
For Service: 800-227-5674

File Name: Homans Portland ME 130811777 J

B-13-08-11777

SHEET: 1.0