



- NOTES:
1. OBSERVE POLARITY ON ADDRESSABLE LOOP (BLACK-, RED+).
  2. ALL ADDRESSABLE DEVICES MUST BE LOCATED IN HEATED AREAS.
  3. LOCATE ALL REMOTE BOOSTERS IN ACCESSIBLE HEATED AREAS WITH SMOKE DETECTORS.

SEQUENCE OF OPERATION MATRIX

INPUTS	OUTPUTS
MANUAL PULL STATION	DISPLAY ON FACP
AREA SMOKE DETECTOR	ACTIVATE DIALER FOR ALARM (FIRE DEPARTMENT/OWNER)
	ACTIVATE HORNS AND STROBES
	ACTIVATE DIALER FOR SUPERVISORY (OWNER)
	ACTIVATE DIALER FOR TROUBLE (OWNER)
	ACTIVATE RED BEACON

SPRINKLER BELL DETAIL

GAUGELA SETTINGS
CORRIDORS @ 15cd
20x20 @ 15cd
30x30 @ 30cd
40x40 @ 75cd
50x50 @ 110cd

Revised Date: 03/29/10 Original Release: 03/29/10

Location: WB Mason Portland, ME

Fire Alarm Riser

RB ALLEN Co., Inc. Sheet 1 of 1

Rev # 76534

DATE 03/29/10

DESIGNED BY: [Signature]

DATE 03/29/10

PROJECT: [Signature]

DATE 03/29/10

BY: [Signature]