



## REPORT OF SOILS FIELD COMPACTION TESTING

**CLIENT:** Old Dominion Freight Lines                      **PROJECT:** Old Dominion Building Expansion  
 500 Old Dominion Way    185 Rand Road  
 Thomasville, NC. 27360    Portland, ME  
 Attn: Philip Danner

**DATE:** August 13, 2014    **REPORT #:** 14-55-00014-001

**General Location:** Foundation Fill  
**Field Rep:** Nickolas Brown  
**Contractor:** DL Chase  
**Earthwork:** Shaw Brothers  
**Air Temp:** 66°F  
**Weather:** Rain  
**Soil Type:** Structural Fill  
**Soil ID#:** 14-930  
**Sample Source:** Shaw Brothers H Pit

**Proctor Value:** 116.2    **Optimum Moisture:** 9.8%

**Gauge Type:** Troxler 3430    **Required Compaction:** 95%

TEST NUMBER	DEPTH/ELEV.	MOISTURE %	DRY DENSITY PCF	PERCENT COMPACTION
	8''/60'	2.8%	111.4	95.8%
<b>LOCATION: 10' east of B, 13' north of 11</b>				
	8''/60'	3.1%	112.3	96.6%
<b>LOCATION: 8' west of A, 2' south of 13</b>				
	8''/60'	2.6%	111.5	95.9%
<b>LOCATION: 12' west of A, 3' north of 14</b>				
<b>LOCATION:</b>				
<b>LOCATION:</b>				
<b>LOCATION:</b>				
<b>LOCATION:</b>				
<b>LOCATION:</b>				
<b>REMARKS:</b>				

**NH MA ME CT VT RI**

**JOHN TURNER CONSULTING**

**CONSULTJTC.COM**

19 DOVER STREET  
DOVER, NH 03820  
T 603.749.1841 F 603.516.6851

66 SOUTHGATE STREET  
WORCESTER MA 01603  
T 508.505.0126

6 CLINTON AVENUE  
WESTFIELD MA 01085  
T 413.642.0138

4775 ROUTE 14, UNIT 3  
WRJ, VT 05001  
T 802.295.1100

73 RAINMAKER DRIVE  
PORTLAND ME 04103-1291  
T 207.883.7878