Door Schedule

Door No.	Size	Type	Remarks
101			Existing Front door
102	3'-0" x 6'-8"	Solid Wood	Mortise Lock – TBD
103	Custom	TBD	Shed door with lock for snow blower
104	Custom	TBD	Shed Doors
105	3'-0" x 6'-8"	Solid Wood	Mortise Lock – TBD
106	3'-0" x 6'-8"	Solid Wood	Interior – ADA Bathroom
107	3'-0" x 6'-8"	Solid Wood	Interior
108	3'-0" x 6'-8"	Solid Wood	Interior
201	TBD	TBD	TBD

Window Schedule

See 3/4.1 Window Key

KEY	TYPE	UNIT FRAME (Nominal W x H)	MODEL # Andersen A Series	EGRESS ◊	TEMPERED	REMARKS
A	Casement	2'-6" x 4'-8"	ACW 2648			
B	Casement	5'-0" x 4'-8"	Mulled (2) ACW 2648			
C	Fixed/Casement	6–0" x 4–8"	Custom Mulled / ACW2048			
D	Fixed	See item 3/4.1 for Dims	Custom			
E	Fixed	See item 3/4.1 for Dims	Custom			
F	Casement	4'-0" x 4'-0"	Mulled (2) ACW 2040			
G	Casement	2'-0" x 3'-4"	ACW 2040			
H	Skylight	33 1/2" x 49 1/2"	VELUX 3046 Outside Curb			

1 WINDOW AND DOOR SCHEDULES
NTS

Finish Schedule

Location		Floor	Base	Walls				Ceiling	REMARKS
Room No.	Room Name	Material / Finish	Material / Finish	North	East	South	West	Material / Finish	
101	Studio	Concrete, Entry Mat	1x6 Painted	GWB	GWB	GWB	GWB	GWB	Recess Slab
102	ADA Bathroom	Ceramic Tile	1x6 Painted	GWB / Tile	GWB / Tile	GWB / Tile	GWB / Tile	GWB	Recess Slab
103	Office	Existing	Existing	Existing	Existing	Existing	Existing	Existing	
104	Family Room	Concrete, Entry Mat	1x6 Painted	GWB	GWB	GWB	GWB	GWB	Recess Slab

2 FINISH SCHEDULE
NTS

3 WINODW KEY
SCALE: 3" = 1'-0"

4 TYPICAL HEAD DETAIL @ NEW WALLS
SCALE: 3" = 1'-0"

5 TYPICAL SILL DETAIL
SCALE: 3" = 1'-0"

6 TYPICAL JAMB DETAIL
SCALE: 3" = 1'-0"

Copyright 2013 Richard I Renner Architects

RRIA
Richard Renner | Architects
Portland, ME Sherborn, MA
207.773.9699 508.651.2385

REGISTERED ARCHITECT RICHARD K. RENNER No. 1306 STATE OF MAINE

Reviewed for Code Compliance
Inspectional Services
Approved as Noted
Date: 06/24/15

Consultants:

Casco Bay Engineering
Peter D. Rand, P.E.
Senior Project Manager
424 Fore Street
Portland, Maine 04101
c. 207–842–2801
p. 207–842–2801, ext. 203
f. 207–842–2828
www.cascobayengineering.com

Redman Residence: Addition

480 Capisic Street
Portland, ME 04102

Permit Set 6.19.2015

Schedules and Window Details

Drawn by: RRIA **File Name:**
Scale: 3" = 1'-0" **Project No.** 2014–12.00
Date: 03/31/15 **Revised:** 06/19/15

Redman Addition

A4.1