



**COMMERCIAL BUILDING PRODUCTS**

**MAIN OFFICE**  
 P.O. Box 2489  
 Woburn, MA 01888  
 Tel (781) 938-0909  
 Fax (781) 935-1696

**Londonderry, NH**  
 Tel (603) 432-6490  
 Fax (603) 432-6499

**Rockland, MA**  
 Tel (781) 871-1212  
 Fax (781) 871-9496

**Williston, VT**  
 Tel (802) 658-3730  
 Fax (802) 658-4171

**Portland, ME**  
 Tel (207) 775-6512  
 Fax (207) 774-3384

**Shrewsbury, MA**  
 Tel (508) 842-5170  
 Fax (508) 842-5217

**Lebanon, ME**  
 Tel (207) 339-8848  
 Fax (207) 339-0102

**PICKING TICKET**

**BILL TO**

**SHIP TO**

271 MAINE CASH  
 100 RIVERSTREET ST  
 PORTLAND, ME 04103  
 TEL (207) 8512

SAME AS BILL TO

Our Order #: 547113  
 Order Date: 07/27/00  
 Location: 13  
 Ship Via: CPU  
 Ship Date:

336 Jacob St. Woburn

Account #: MAJICA  
 Your P/O #:  
 Placed By:  
 Labor N/L:  
 Job #/ Name:

Quantity Ordered	Sell Unit	Quantity Shipped	Item Number	Unit Price	Extended Price
13	CTN	12	ARM 824 CORTECA 3/8 2X2 LI 40"		

Total Ship Unit: 640.0000  
 Reported date: 07/27/2000 648.12  
 Check number: 1001

Received in good order by:

*[Signature]*

Order filled by:

Date:

ARRIVAL TIME:

DEPARTURE TIME:

DRIVER SIGN-OFF:

# CORTEGA™

Tile, Square Lay-In & Tegular  
medium texture

LEED Credits					
Waste Management	Recycled Content	Local Materials	Renewable Materials	Energy Performance	Daylight & Views
✓	✓	*	✓		

\* Credit is location-dependent



## Visual Selection

## Performance Selection

GRID FACE	EDGE PROFILE	ITEM NUMBER	DIMENSIONS	UL Classified	ACOUSTICS		FIRE	SAG RESIST	ANTI-MOLD/MILDEW	ANTI-ODOR/STAIN BACTERIA	AVERAGE LIGHT REFLECT	DURABILITY
					NRC	CAC						
<b>CORTEGA Tile</b>												
Concealed	Beveled K4C4	745 745M	12 x 12 x 5/8" 300 x 300 x 15mm		0.50	35	Class A	Standard	-	R	0.86	Standard
<b>CORTEGA Square Lay-In</b>												
15/16"	Square lay-in	770 770M	24 x 24 x 5/8" 600 x 600 x 15mm		0.55	33	Class A	Standard	-	R	0.82	Standard
		824 824M	24 x 24 x 5/8" 600 x 600 x 15mm		0.55	35	Class A	Standard	-	R	0.82	Standard
		769 769M	24 x 48 x 5/8" 600 x 1200 x 15mm		0.55	35	Class A	Standard	-	R	0.82	Standard
		747 747M	24 x 48 x 5/8" 600 x 1200 x 15mm		0.55	40	Class A	Standard	-	R	0.82	Standard
		761* 761M*	24 x 48 x 5/8" 600 x 1200 x 15mm		0.55	35	Class A	Standard	-	R	0.82	Washable
		823 823M	24 x 48 x 5/8" 600 x 1200 x 15mm		0.55	35	Class A	Standard	-	R	0.82	Standard
		773 773M	20 x 60 x 5/8" 500 x 1500 x 15mm		0.55	35	Class A	Standard	-	R	0.82	Standard
		772 772M	24 x 60 x 5/8" 600 x 1500 x 15mm		0.55	35	Class A	Standard	-	R	0.82	Standard
		780 780M	30 x 60 x 3/4" 750 x 1500 x 19mm		0.55	35	Class A	Standard	-	R	0.82	Standard
<b>CORTEGA Tegular</b>												
9/16"	Beveled Tegular	2195 2195M	24 x 24 x 5/8" 600 x 600 x 15mm		0.55	35*	Class A	Standard	-	R	0.82	Standard
15/16"	Angled Tegular	704 704M	24 x 24 x 5/8" 600 x 600 x 15mm		0.55	33	Class A	Standard	-	R	0.82	Standard
		816	24 x 24 x 5/8"		0.55	35	Class A	Standard	-	R	0.82	Standard
		703 703M	24 x 48 x 5/8" 600 x 1200 x 15mm		0.55	35	Class A	Standard	-	R	0.82	Standard

\* Washable plastic finish

\* Installations in Healthcare facilities need to meet HIPAA oral privacy requirements

Contact TechLine<sup>SM</sup> for specific information on recycled content.



## Physical Data

### Material

Wet-formed mineral fiber  
761 - Wet-formed mineral fiber with plastic finish

### Surface Finish

Factory-applied latex paint  
761 - Factory-applied plastic finish

### Fire Performance

Class A: Flame Spread 25 or under (UL Labeled) per ASTM E 1264  
Fire Guard: A fire resistive ceiling when used in applicable UL assemblies

### ASTM E 1264 Classification

Type III, Form 2, Pattern C D  
761 - Type IX, Form 2, Pattern C D

### Recycled Content

27-45%; Fire Guard™ items 30-40%

### Treatment for Odor- and Stain-causing Bacteria

Available upon request

### Insulation Value

745 -  
R Factor - 1.6 (BTU units)  
R Factor - 0.28 (Watts units)  
2195, 704, 816, 703 -  
R Factor - 1.6 (BTU units)  
R Factor - 0.28 (Watts units)  
747, 770, 772, 761,  
769, 773, 780, 823, 824 -  
R Factor - 1.5 (BTU units)  
R Factor - 0.26 (Watts units)

### Backloading Recommendation

Contact TechLine for specific information

### Weight; Square Feet/ Carton

703 - 0.70 lbs/SF; 80 SF/ctn  
704, 2195 - 0.70 lbs/SF; 64 SF/ctn  
745 - 0.90 lbs/SF; 40 SF/ctn  
747 - 0.85 lbs/SF; 64 SF/ctn  
761, 769 - 0.60 lbs/SF; 96 SF/ctn  
770 - 0.60 lbs/SF; 64 SF/ctn  
772, 773 - 0.60 lbs/SF; 100 SF/ctn  
780 - 0.60 lbs/SF; 75 SF/ctn  
816 - 1.00 lbs/SF; 48 SF/ctn  
823, 824 - 1.00 lbs/SF; 64 SF/ctn

### Warranty

See warranty details in the back of this catalog

### Application Considerations

Tech Black products should be handled with gloves to prevent marking with fingerprints. Objectionable surface dust may occur with frequent handling of Tech Black products. In these situations, Tech Black products are not recommended for bright open spaces.

### Recommended Suspension System

ITEMS	SUSPENSION SYSTEM	DRAWING DETAIL (PG. 236-239)
745	PRELUDE® Concealed Tee Grid (Pg. 212) CONCEALED Z grid or glue (Pg. 210)	45
770, 747, 761, 769, 773, 772, 780	15/16" PRELUDE (Pg. 213, 215)	1
823, 824	15/16" PRELUDE XL Fire Guard (Pg. 215)	1
2195	9/16" TRIMLOK® Screw-Slot (Pg. 220) 9/16" SILHOUETTE® Bolt-Slot (Pg. 216-217)	34 33
703, 704	15/16" PRELUDE (Pg. 215)	6
816	15/16" PRELUDE XL Fire Guard (Pg. 215)	6

### Also Compatible With

2195*	9/16" SUPRAFINE™ (Pg. 219)	31
CAC 33	9/16" INTERLUDE® (Pg. 211)	32
	9/16" SONATA™ (Pg. 218)	54

26 ft

Back Porch

Back Door

906 Brighton Ave.

grill range hood  
Kitchen

Exit ↑

Steam table

Food storage

Office storage

Hand sink

10

3 bay sink closet

Dining

6

Bath  
8 2/3 x 6

2-4

27 x 14  
378 SF

Possible Dining  
11.5 x 12  
138 SF

Dining

2

2

2

4

Exit ↓

Front Door

Porch

906 Bright Ave

Scale  
1 in = 4 ft

38 ft

2

W

2

2

2

2

2

W W W