



- There will be no new walls or structural beams
- No stairs built
- No window/door schedule as structure will retain existing windows/doors
- Foundation will remain as existing
- Insulation will be Roxul stone wool with a value of R-15
- No decks will be built, existing will be retained