

PITCHED ROOF



30 deg

Permitting and Inspections Department Approved with Conditions

03/07/2019

Project Details

NAME DATE 2019-02-20 Leeman

LOCATION Portland, ME, 04102 **TOTAL MODULES** 16

MODULE Q. Cells :Q.PEAK DUO L-G5.2 385 (35mm) **TOTAL WATTS** 6,160

DIMENSIONS 79.33" x 39.37" x 1.38" (2,015 x 1,000 x 35mm) ATTACHMENT PTS 56

Load Assumptions

Building Details

В

WIND SPEED 100 mph **BUILDING HEIGHT** 25 ft

GROUND SNOW LOAD 70 psf **RISK CATEGORY**

2.0 ft Comp Shingle ATTACHMENT SPACING **ROOF TYPE**

Engineering

WIND EXPOSURE

XR100 SPAN DETAILS (Portrait)

Roof Zone	Max Span	Max Cantilever
1	4'	1' 7"
2	4'	1' 7"
3	4'	1' 7"

MAXIMUM REACTION FORCES (Portrait)

ROOF SLOPE

Roof Zone	Down	Uplift	Lateral
1	189.00	-53.00	106.00
2	189.00	-61.00	106.00
3	189.00	-61.00	106.00

System Weight

TOTAL WEIGHT 943 lbs WEIGHT/ATTACHMENT 16.8 lbs 2.7 psf DISTRIBUTED WEIGHT **RACKING WEIGHT** 114.3 lbs



PITCHED ROOF




Reviewed for Code Compliance Permitting and Inspections Department Approved with Conditions

03/07/2019

Array Details

Array	Cols	Rows	Orientation	Row Length	Cantilever	Violations	Provided Rails	Attachments	Clamps	Splices
Α	7	1	PORTRAIT	23' 3.8"	8"	None	56'[4 x 14']	24	16	2
Α	5	1	PORTRAIT	16' 8.3"	4"	None	34'[2 x 17']	18	12	0
А	4	1	PORTRAIT	13' 4.6"	8"	None	28'[2 x 14']	14	10	0



Leeman


PITCHED ROOF




Reviewed for Code Compliance Permitting and Inspections Department Approved with Conditions

03/07/2019





Clamp Detail






PITCHED ROOF

Grounding Diagram



Reviewed for Code Compliance Permitting and Inspections Department Approved with Conditions

03/07/2019



*Grounding Lugs and wire are not required in systems using certain Enphase microinverters or certain Sunpower modules. Equipment grounding is achieved with the Engage cable for Enphase or the AC module cable system for Sunpower via their integrated EGC.

Leeman

PITCHED ROOF

Bill of Materials



Reviewed for Code Compliance
Permitting and Inspections Department
Approved with Conditions
03/07/2019

GROUP	PART	DESCRIPTION	TOTAL QTY
RAILS & SPLICES	XR-100-168A	XR100, Rail 168" (14 Feet) Clear	6
	XR-100-204A	XR100, Rail 204" (17 Feet) Clear	2
	XR-100-SPLC-M1	XR100 Bonded Splice (Incl. Self-tapping Screws)	2
CLAMPS & GROUNDING	UFO-CL-01-A1	Universal Module Clamp, Clear	38
	UFO-STP-35MM-M1	Stopper Sleeve, 35MM, Mill	12
	XR-LUG-03-A1	Grounding Lug, Low Profile	3
ATTACHMENTS	LFT-03-M1	Slotted L-Foot, Mill	56
	BHW-SQ-02-A1	Square-Bolt Bonding Hardware	56





