



22 Oakmont Drive
Old Orchard Beach, ME 04064-4121
Phone: (207) 934-8038
Fax: (207) 934-8039

FIELD NOTES

JOB NAME: Motor City Fiat
JOB NO.: 09053
DATE OF VISIT: April 15, 2011
TIME: 1:00 P.M
WEATHER: 60°, clear
CLIENT: Archetype, P.A.
OBSERVERS: David Tetreault, SDC

The foundation extension at the southwest corner of the existing building has been formed. Expansion anchors with threaded rods have been set into the existing foundation instead of drilled and epoxied rebar. This change is acceptable. The expansion anchors are spaced at 24" o.c. both ways. Temperature/shrinkage reinforcing consisting of #4@24" both ways was tied in place. The contract documents called for #5@24" both ways. The change from #5 to #4 bars is acceptable. All forming and reinforcing was found to be acceptable. Concrete placement is scheduled for later today.

SIGNATURE: _____

David Tetreault