

SECTION 03300 – CAST -IN-PLACE CONCRETE

PART 1 GENERAL

1.01 RELATED DOCUMENTS

- A. The drawings and general conditions of the contract including General and Supplementary Conditions and other Division 1 Specification sections apply to work of this section.
- B. Examine all other sections of the Specifications for requirements which affect work of this Section whether or not such work is specifically mentioned in this Section.
- C. Coordinate work with that of all trades affecting or affected by work of this Section. Cooperate with such trades to assure the steady progress of all work under the Contract.

1.02 DESCRIPTION OF WORK:

- A. Work included: Provide labor, materials, and equipment necessary to complete the work of this Section and, without limiting the generality thereof, furnish and include the following:
 - 1. The extent of cast-in-place concrete work is shown on drawings and includes (but not by way of limitation) formwork, reinforcing, cast-in-place concrete, accessories, and casting in of items specified under other Sections of the Specifications or furnished by Owner that are required to be built-in with the concrete.
 - 2. Equipment support pads indicated on mechanical drawings to be installed by the Building Contractor.
 - 3. Cast-in-place retaining walls, exterior slabs on grade and other concrete shown on site drawings.

1.03 RELATED WORK:

- A. Metal Fabrications: Section 05500
 - 1. Expansion Anchors - Section 05120
 - 2. Embedded Items - Section 05500
- B. Anchor Bolts: Section 05120
- C. Joint Sealants: Section 07920
- D. Underslab Vapor Retarders/Wall Waterproofing: Division 7

1.04 QUALITY ASSURANCE:

- A. Codes and Standards: Comply with provisions of the latest edition of the following except where more stringent requirements are shown or specified:
1. ACI 211.1 "Standard Practice for Selecting Proportions for Normal, Heavyweight and Mass Concrete."
 2. ACI 212.3R "Chemical Admixtures for Concrete."
 3. ACI 301 "Specifications for Structural Concrete for Buildings."
 4. ACI 302.1R "Guide for Concrete Floor and Slab Construction."
 5. ACI 304R "Guide for Measuring, Mixing, Transporting and Placing Concrete."
 6. ACI 304.2R "Placing Concrete by Pumping Methods."
 7. ACI 306 R "Cold Weather Concreting."
 8. ACI 308 "Standard Practice for Curing Concrete."
 9. ACI 309R "Guide for Consolidation of Concrete."
 10. ACI 315 "ACI Detailing Manual."
 11. ACI 318 "Building Code Requirements for Reinforced Concrete."
 12. ACI 347R "Guide to Formwork for Concrete."
 13. Concrete Reinforcing Steel Institute, "Placing Reinforcing Bars."
 14. "Code of Federal Regulations, Part 1926" per the Occupational Safety and Health Administration (OSHA), Department of Labor (Latest Revision).
- B. Materials and installed work may require testing and retesting, as directed by the Architect, at any time during progress of work. Allow free access to material stockpiles and facilities. Tests not specifically indicated to be done at Owner's expense, including retesting of rejected materials and installed work, shall be done at Contractor's expense.

1.05 SUBMITTALS:

- A. Unless otherwise specified, submittals required in this section shall be submitted for review. Submittals shall be prepared and submitted in accordance with section 01330.
- B. General Contractor shall submit a Submittal Schedule to the engineer within 30 days after they have received the Owner's Notice to Proceed.
- C. All submittals shall be reviewed and returned to the Architect within 10 working days.

- D. Incomplete submittals will not be reviewed.
- E. Submittals not reviewed by the General Contractor prior to submission to the Engineer will not be reviewed. Include on the submittal statement or stamp of approval by Contractor, representing that the Contractor has seen and examined the submittal and that all requirements listed in this Section and Section 01330 have been complied with.
- F. Engineer will review submittals a maximum of two review cycles as part of their normal services. If submittals are incomplete or otherwise unacceptable and re-submitted, General Contractor shall compensate Engineer for additional review cycles.
- G. Product Data: Submit producer's or manufacturer's specifications and installation instructions for the following products. Include laboratory test reports and other data to show compliance with specifications (including specified standards).
 - 1. Reinforcement certified mill reports covering chemical and physical properties and yield strength.
 - 2. Patching products.
 - 3. Non-shrink grout.
 - 4. Curing compounds, where applicable.
 - 5. Admixtures.
 - 6. Expansion/Adhesive Anchors.
- H. Shop Drawings:
 - 1. Shop Drawing Preparation: Electronic files of structural drawings will not be provided to the contractor for preparation of shop drawings. Submit shop drawings for fabrication, bending and placement of concrete reinforcement. Comply with ACI 315, showing bar schedules, stirrup and tie spacing, diagrams of bent bars, and arrangement of concrete reinforcement. Include special reinforcement required at openings through concrete elements. Include supplemental reinforcing and bar supports necessary to support reinforcing steel at proper location within forms or slabs.
 - a. Review of the shop drawings will be made for the size and arrangement of reinforcement. Conformance of the Shop Drawings to the Contract Drawings remains the responsibility of the General Contractor. Engineer's review in no way relieves the General Contractor of this responsibility. Submit one print and one reproducible. Print will be reviewed and a reproducible will be returned to Contractor for printing and distribution. Multiple copies will not be marked by Engineer.

- b. Shop drawings will not be reviewed as partial submittals. A complete submittal shall be provided all items listed prior. **Incomplete submittals will not be reviewed.**
- I. Mix designs: Submit all laboratory test reports and materials for each mix design listed within. Prepare mixes by the field experience method and/or trial mixtures per the requirements of chapter 5 of ACI 318. Include the calculation of average strength and standard deviation. Proportioning by water cement ratio method will not be permitted.
- J. Samples: Submit samples of materials as specified and as otherwise requested by Architect, including names, sources and descriptions.
- K. Contraction/Construction Joints: Submit plan indicating proposed location of contraction and construction joints in walls and slabs.

PART 2 PRODUCTS

2.01 FORM MATERIALS:

- A. Forms for Exposed Finish Concrete: Unless otherwise indicated, construct formwork for exposed concrete surfaces with plywood, metal, metal-framed plywood faced or other acceptable panel-type materials, to provide continuous, straight, smooth, exposed surfaces. Furnish in largest practicable sizes to minimize number of joints and to conform to joint system shown on drawings. Provide form material with sufficient thickness to withstand pressure of newly-placed concrete without bow or deflection.
 - 1. Use plywood complying with U.S. Product Standard PS-1 "B-B (Concrete Form) Plywood", Class I, Exterior Grade or better, mill-oiled and edge-sealed, with piece bearing legible inspection trademark.
- B. Forms for Unexposed Finish Concrete: Form concrete surfaces which will be unexposed in finished structure with plywood, lumber, metal or other acceptable material. Provide lumber dressed on at least 2 edges and one side for tight fit.
- C. Form Coatings: Provide commercial formulation form-coating compounds that will not bond with, stain nor adversely affect concrete surfaces, and will not impair subsequent treatments of concrete surfaces. See Section 1.06 for VOC requirements.

2.02 REINFORCING MATERIALS:

- A. Reinforcing Bars: ASTM A 615, Grade 60, deformed.
- B. Welded Wire Fabric: ASTM A 185, welded steel wire fabric. Provide welded wire fabric in flat sheets.
- C. Diamond Dowels/Load Plates: PNA Construction Technologies, Inc.; Manufacturer's representative: (508) 238-6775

D. Supports for Reinforcement: Provide supports for reinforcement including bolsters, chairs, spacers, and other devices for spacing, supporting and fastening reinforcing bars and welded wire fabric in place. Use wire bar type supports or concrete block supports complying with CRSI recommendation, unless otherwise specified. Wood, clay brick and other devices are not acceptable.

1. For slabs-on-grade, use supports with sand plates or horizontal runners where base material will not support chair legs.
2. For exposed-to-view concrete surfaces, where legs of supports are in contact with forms, provide supports with legs which are plastic protected (CRSI, Class I) or stainless steel protected (CRSI, Class 2).

2.03 CONCRETE MATERIALS:

A. Portland Cement: ASTM C 150, Type I or Type II, unless otherwise approved Use one brand of cement throughout project, unless otherwise acceptable to Architect.

B. Normal Weight Aggregates: ASTM C 33. Provide from a single source for exposed concrete. Do not use aggregates containing soluble salts or other substances such as iron sulfides, pyrite, marcasite, or ochre which can cause stains on exposed concrete surfaces.

C. Light Weight Aggregates: ASTM C 330.

D. Water: Potable.

E. Air-Entraining Admixture: ASTM C 260.

F. High-Range Water-Reducing Admixture (Super Plasticizer): ASTM C 494, Type F or Type G containing not more than 1% chloride ions.

1. Fiber reinforcing shall be added and distributed prior to incorporation of Super Plasticizer.

G. Normal range water reducing admixture: ASTM C 494 Type A containing no calcium chloride.

H. Accelerating Admixture: ASTM C 494, Type C or E.

I. Blast Furnace Slag: ASTM C989

J. Fly Ash: ASTM C618, Class C or F

K. Calcium Chloride is not permitted.

2.04 RELATED MATERIALS:

- A. Underslab Vapor Retarder: Provide vapor retarder over prepared sub base. Refer to architectural drawings, geotechnical report and/or division 7 specifications for additional requirements and vapor retarder location.
- B. Non-Shrink Cement-based Grout: Provide grout consisting of pre-measured, prepackaged materials supplied by the manufacturer requiring only the addition of water. Manufacturer's instructions must be printed on the outside of each bag.
 - 1. Non-shrink: No shrinkage (0.0%) and a maximum 4.0% expansion when tested in accordance with ASTM C-827. No shrinkage (0.0%) and a maximum of 0.2% expansion in the hardened state when tested in accordance with CRD-C-621.
 - 2. Compressive strength: A minimum 28 day compressive strength of 5000 psi when tested in accordance with ASTM C-109.
 - 3. Setting time: A minimum initial set time of 60 minutes when tested in accordance with ASTM C-191.
 - 4. Composition: Shall not contain metallic particles or expansive cement.
- C. Absorptive Cover: Burlap cloth made from jute or kenaf, weighing approximately 9 oz. per sq. yd., complying with AASHTO M182, Class 2.
- D. Moisture-Retaining Cover: One of the following, complying with ANSI/ASTM C 171.
 - 1. Waterproof paper.
 - 2. Polyethylene film.
 - 3. Polyethylene-coated burlap.
- E. Liquid Membrane-Forming Curing Compound: Liquid type membrane forming curing compound complying with ASTM C 309, Type I, Class A unless other type acceptable to Architect. Curing compound shall not impair bonding of any material, including floor finishes, to be applied directly to the concrete. Demonstrate the non-impairment prior to use.
- F. Preformed Expansion Joint Formers:
 - 1. Bituminous Fiber Type, ASTM D 1751.
 - 2. Felt Void, Poly-Styrene Cap with removable top as manufactured by SUPERIOR.
- G. Slab Joint Filler: Multi-component polyurethane sealant (self-leveling type).

H. Waterstops shall be Bentonite/Butyl Rubberbased product. Use in conjunction with manufacturer's approved mastic. Acceptable products include:

1. "Waterstop Rx," by American Colloid Co.
2. "Adeka Ultra Seal MC-2010," by Asahi Denka Koeyo, Kik MN.

2.05 PROPORTIONING AND DESIGN OF MIXES:

A. Prepare design mixes for each type and strength of concrete by either laboratory trial batch or field experience methods as specified in ACI 318. Use material, including all admixtures, proposed for use on the project. If trial batch method used, use an independent testing facility acceptable to Architect for preparing and reporting proposed mix designs. The testing facility shall not be the same as used for field quality control testing unless otherwise acceptable to Architect.

B. Submit written reports to Architect of each proposed mix for each class of concrete. Do not begin concrete production until mixes have been reviewed by Architect.

C. Proportion design mixes to provide concrete with the following properties: *[Carefully review mix designs per project requirements. Consider ACI 318, section 4.2 for air content and w/c ratio for frost and deicing chemical exposure. Consider low w/c ratio and larger aggregates to reduce shrinkage in concrete slabs]*

1. Footings and foundation walls

- a. Strength: 3000 psi at 28 days.
- b. Aggregate: 3/4"
- c. W/C Ratio: 0.54 maximum
- d. Entrained Air: 6% +/- 1.5%
- e. Slump: 4" maximum

2. Interior Slabs on grade:

- a. Strength: 3000 psi at 28 days
- b. Aggregate: 3/4" minimum, 1 1/2" maximum.
- c. W/C Ratio: 0.54 maximum
- d. Entrapped Air only (no entrainment)
- e. Slump: 4" maximum

3. Exterior Slabs and all other exposed Site Concrete not specified elsewhere:

- a. Strength: 4500 psi at 28 days
 - b. Aggregate: 3/4"
 - c. W/C Ratio: 0.45 maximum
 - d. Entrained Air: 6% +/- 1.5%
 - e. Slump: 4" maximum
4. Add air entraining admixture at manufacturers prescribed rate to result in concrete at point of placement having the above noted air contents.
5. Additional slump may be achieved by the addition of a mid-range or high-range water reducing admixture. Maximum slump after the addition of admixture shall be 6 or 8 inches for mid-range or high range water reducing admixtures, respectively.
- D. Adjustment to Concrete Mixes: Mix design adjustments may be requested by Contractor, when characteristics of materials, job conditions, weather, test results, or other circumstances warrant, at no additional cost to Owner and as accepted by Architect. Laboratory test data for revised mix design and strength results must be submitted to and accepted by Structural Engineer before using in work.
 1. Water may be added at the project only if the maximum specified slump and design mix maximum water/cement ratio is not exceeded.
 2. Additional dosages of superplasticizer should be used when delays occur and required slump has not been maintained. A maximum of two additional dosages will be permitted per ACI 212.3R recommendations.

2.06 CONCRETE MIXING:

- A. Job-Site Mixing will not be permitted.
- B. Ready-Mix Concrete: Must comply with the requirements of ASTM C 94, and as herein specified. Provide batch ticket for each batch discharged and used in work, indicating project name, mix type, mix time and quantity.
 1. During hot weather, or under conditions contributing to rapid setting of concrete, a shorter mixing time than specified in ASTM C94 may be required by Structural Engineer.
 2. When the air temperature is between 85 degrees F. and 90 degrees F., reduce the mixing and delivery time from 1 1/2 hours to 75 minutes, and when the air temperature is above 90 degrees F., reduce the mixing and delivery time to 60 minutes.

PART 3 EXECUTION

3.01 FORMS:

- A. Design, erect, support, brace and maintain formwork to support vertical and lateral loads that might be applied until such loads can be supported by concrete structure. Construct formwork so concrete members and structures are of correct size, shape, alignment, elevation and position.
- B. Design, construct, erect, maintain, and remove forms for cast-in-place concrete work in compliance with ACI 347.
- C. Design formwork to be readily removable without impact, shock or damage to cast-in-place concrete surfaces and adjacent materials.
- D. Construct forms to sizes, shapes, lines and dimensions shown, and to obtain accurate alignment, location, grades, level and plumb work in finished structures. Provide for openings, offsets, keyways, recesses, moldings, rustications, reglets, chamfers, blocking, screeds, bulkheads, anchorages and inserts, and other features required in work. Use selected materials to obtain required finishes. Solidly butt joints and provide backup at joints to prevent leakage of cement paste.
- E. Fabricate forms for easy removal without hammering or prying against concrete surfaces. Provide crush plates or wrecking plates where stripping may damage cast concrete surfaces. Provide top forms for inclined surfaces where slope is too steep to place concrete with bottom forms only. Kerf wood inserts for forming keyways, reglets, recesses, and the like to prevent swelling and for easy removal.
- F. Provide temporary openings where interior area of formwork is inaccessible for clean out, for inspection before concrete placement and for placement of concrete. Securely brace temporary openings and set tightly to forms to prevent loss of concrete mortar. Locate temporary openings on forms at inconspicuous locations.
- G. Chamfer exposed corners and edges as indicated, using wood, metal, PVC or rubber chamfer strips fabricated to produce uniform smooth lines and tight edge joints.
- H. Form Ties: Factory-fabricated, adjustable-length, removable or snap-off metal form ties, designed to prevent form deflection, and to prevent spalling concrete surfaces upon removal.
 - 1. Unless otherwise indicated, provide ties so portion remaining within concrete after removal is 1" inside concrete and will not leave holes larger than 1" diameter in concrete surface.
- I. Provision for Other Trades: Provide openings in concrete formwork to accommodate work of other trades. Determine size and location of openings, recesses, and chases from trades providing such items. Accurately place and securely support items built into forms.

- J. Cleaning and Tightening: Thoroughly clean forms and adjacent surfaces to receive concrete. Remove chips, wood, sawdust, dirt or other debris just before concrete is placed. Retighten forms and bracing after concrete placement as required to eliminate mortar leaks and maintain proper alignment.

3.02 PLACING REINFORCEMENT:

- A. Comply with Concrete Reinforcing Steel Institute's recommended practice for "Placing Reinforcing Bars", for details and methods of reinforcement placement and supports, and as herein specified.
 - 1. Subgrade tolerance shall conform to a tolerance of +/- 1-1/2 in. Confirm compliance prior to removal of excavation material with surveyed measurements taken at 20 ft. intervals in each direction.
 - 2. Clean reinforcement of loose rust and mill scale, earth, ice, and other materials which reduce or destroy bond with concrete.
 - 3. Accurately position, support and secure reinforcement against displacement by formwork, construction, or concrete placement operations. Locate and support reinforcing by metal chairs, runners, bolsters, spacers and hangers, as required.
 - 4. Place reinforcement to obtain specified coverage for concrete protection within tolerances of ACI-318. Arrange, space and securely tie bars and bar supports to hold reinforcement in position during concrete placement operations. Set wire ties so ends are directed into concrete, not toward exposed concrete surfaces.
 - 5. Install diamond dowels at construction joints in slab-on-grade per manufacturer's recommendations and as indicated on Drawings.
 - 6. Install welded wire fabric in flat sheets in as long lengths as practicable. Lap adjoining pieces at least one full mesh and lace splices with wire. Offset end laps in adjacent widths to prevent continuous laps in either direction.

3.03 JOINTS:

- A. Construction Joints: Locate and install construction joints, which are not shown on drawings, so as not to impair strength and appearance of the structure, as acceptable to Architect. Submit plan indicating proposed location of construction joints for review prior to beginning work.
 - 1. Provide keyways at least 1-1/2" deep in construction joints in walls, and slabs; accepted bulkheads designed for this purpose may be used for slabs.
 - 2. Roughened surfaces shall be used between walls and footings unless shown otherwise on the drawings. The footing surface shall be roughened to at least an amplitude of 1/4" for the width of the wall before placing the wall concrete.

3. Place construction joints perpendicular to the main reinforcement. Continue reinforcement across construction joints.
4. Joints in slabs on grade shall be located and detailed as indicated on the drawings. If saw-cut joints are required, the early-entry dry-cut process shall be used. Refer to ACI 302, section 8.3.12.

3.04 INSTALLATION OF EMBEDDED ITEMS:

- A. General: Set and build into work anchorage devices and other embedded items required for other work that is attached to, or supported by, cast-in-place concrete. Use setting drawings, diagrams, instructions and directions provided by suppliers of items to be attached thereto. Notify other trades to permit installation of their work. Templates to be utilized for setting of anchorage devices shall be constructed in a manner to allow mechanical consolidation of concrete. “Wet Setting” of embedded items into plastic concrete will not be permitted without special permission from the Engineer.
- B. Edge Forms and Screed Strips for Slabs: Set edge forms or bulkheads and intermediate screed strips for slabs to obtain required elevations and contours in finished slab surface.

3.05 INSTALLATION OF GROUT

- A. Place grout for base plates in accordance with manufacturer's recommendations.
- B. Grout below setting plates as soon as practicable to facilitate erection of steel and prior to removal of temporary bracing and guys. If leveling bolts or shims are used for erection grout shall be installed prior to addition of any column load.
- C. Pack grout solidly between bearing surfaces and bases or plates to ensure that no voids remain. Finish exposed surfaces, protect installed materials and allow to cure. For proprietary grout materials, comply with manufacturer's instructions.

3.06 PREPARATION OF FORM SURFACES:

- A. Coat contact surfaces of forms with a form-coating compound before reinforcement is placed.
- B. Thin form-coating compounds only with thinning agent of type, and in amount, and under conditions of form-coating material manufacturer's directions. Do not allow excess form coating to accumulate in forms or to come into contact with concrete surfaces against which fresh concrete will be placed. Apply in compliance with manufacturer's instructions.

3.07 CONCRETE PLACEMENT:

- A. Preplacement Review: Footing bottoms, reinforcement and all work shall be subject to review by the Structural Engineer. Verify that reinforcing, ducts, anchors, seats, plates and other items cast into concrete are placed and securely held. Notify Structural Engineer of Record/Project Special Inspector 48 hours prior to scheduled placement and obtain approval or waiver of review prior to placement. Be sure that all debris and foreign matter is removed from forms.
- B. Concrete shall be placed in the presence of an approved testing agency.
- C. General: Comply with ACI 304, and as herein specified.
 - 1. Deposit concrete continuously or in layers of such thickness that no concrete will be placed on concrete which has hardened sufficiently to cause the formation of seams or planes of weakness. If a section cannot be placed continuously, provide construction joints as herein specified. Deposit concrete as nearly as practicable to its final location to avoid segregation due to rehandling or flowing.
 - 2. Concrete shall be handled from the mixer to the place of final deposit as rapidly as practicable by methods which will prevent segregation or loss of ingredients and in a manner which will assure that the required quality of the concrete is maintained.
 - 3. Conveying equipment shall be approved and shall be of a size and design such that detectable setting of concrete shall not occur before adjacent concrete is placed. Conveying equipment shall be cleaned at the end of each operation or work day. Conveying equipment and operations shall conform to the following additional requirements:
 - a. Belt conveyors shall be horizontal or at a slope which will not cause excessive segregation or loss of ingredients. Concrete shall be protected against undue drying or rise in temperature. An arrangement shall be used at the discharge end to prevent apparent segregation. Mortar shall not be allowed to adhere to the return length of the belt. Long runs shall be discharged into a hopper or through a baffle.
 - b. Chutes shall be metal or metal-lined and shall have a slope not exceeding 1 vertical to 2 horizontal and not less than 1 vertical to 3 horizontal. Chutes more than 20 feet long, and chutes not meeting the slope requirements may be used provided they discharge into a hopper before distribution.
 - c. Pumping or pneumatic conveying equipment shall be of suitable kind with adequate pumping capacity. Pneumatic placement shall be controlled so that segregation is not apparent in the discharged concrete.
 - d. Concrete shall not be conveyed through pipe made of aluminum alloy. Standby equipment shall be provided on the site.

- e. Tined rakes are prohibited as a means of conveying fiber reinforced concrete.
 4. Do not use reinforcement as bases for runways for concrete conveying equipment or other construction loads.
- D. Placing Concrete in Forms: Deposit concrete in forms in horizontal layers not deeper than 18 inches and in a manner to avoid inclined construction joints. Where placement consists of several layers, place each layer while preceding layer is still plastic to avoid cold joints.
1. Consolidate placed concrete by mechanical vibrating equipment. Hand-spading, rodding or tamping as the sole means for the consolidation of concrete will only be permitted with special permission from the Engineer. Use equipment and procedures for consolidation of concrete in accordance with ACI recommended practices.
 2. Use vibrators designed to operate with vibratory equipment submerged in concrete, maintaining a speed of not less than 8000 impulses per minute and of sufficient amplitude to consolidate the concrete effectively. Do not use vibrators to transport concrete inside forms. Insert and withdraw vibrators vertically at uniformly spaced locations not farther than visible effectiveness of machine, generally at points 18 inches maximum apart. Place vibrators to rapidly penetrate placed layer and at least 6 inches into the preceding layer. Do not insert vibrators into lower layers of concrete that have begun to set. At each insertion maintain the duration of vibration for the time necessary to consolidate concrete and complete embedment of reinforcement and other embedded items without causing segregation of mix, generally from 5 to 15 seconds. A spare vibrator shall be kept on the job site during all concrete placing operation.
- E. Placing Concrete Slabs: Deposit and consolidate concrete slabs in a continuous operation, within limits of construction joints, until the placing of a panel or section is completed.
1. Consolidate concrete using internal vibrators during placing operations so that concrete is thoroughly worked around reinforcement and other embedded items and into corners.
 2. Bring slab surfaces to correct level with straightedge and strike off. Use bull floats or darbies to smooth surface, free of humps or hollows. Do not disturb slab surfaces prior to beginning finishing operations. Do not sprinkle water on plastic surface.
 3. Maintain reinforcing in proper position during concrete placement operations.

4. Slab thicknesses indicated on the drawings are minimums. Provide sufficient concrete to account for structure deflection, subgrade fluctuations, and to obtain the specified slab elevation at the flatness and levelness indicated here within.
- F. Cold Weather Placing: Protect concrete work from physical damage or reduced strength which could be caused by frost, freezing actions, or low temperatures, in compliance with ACI 306 and as herein specified.
1. When air temperature has fallen to or is expected to fall below 40 degrees F (4 degrees C), uniformly heat water and aggregates before mixing to obtain a concrete mixture temperature of not less than 50 degrees F (10 degrees C), and not more than 80 degrees F (27degrees C) at point of placement.
 2. Do not use frozen materials or materials containing ice or snow. Do not place concrete on frozen subgrade or on subgrade containing frozen materials.
 3. Do not use calcium chloride, salt and other materials containing antifreeze agents or chemical accelerators.
 4. All temporary heat, form insulation, insulated blankets, coverings, hay or other equipment and materials necessary to protect the concrete work from physical damage caused by frost , freezing action, or low temperature shall be provided prior to start of placing operations.
 5. When the air temperature has fallen to or is expected to fall below 40 degrees F, provide adequate means to maintain the temperature in the area where concrete is being placed between 50 and 70 degrees F.
- G. Hot Weather Placing: When hot weather conditions exist that would seriously impair quality and strength of concrete, place concrete in compliance with ACI 305 and as herein specified.
1. Cool ingredients before mixing to maintain concrete temperature at time of placement below 90 degrees F. Mixing water may be chilled, or chopped ice may be used to control the concrete temperature provided the water equivalent of the ice is calculated to the total amount of mixing water.
 2. Cover reinforcing steel with water-soaked burlap if it becomes too hot, so that the steel temperature will not exceed the ambient air temperature immediately before embedment in concrete.
 3. Wet forms thoroughly before placing concrete.
 4. Do not use retarding admixtures without the written acceptance by the Architect.

3.08 FINISH OF FORMED SURFACES:

- A. Rough Form Finish: For formed concrete surfaces not exposed-to-view in the finish work or by other construction, unless otherwise indicated. This concrete surface shall have texture imparted by form facing material, with tie holes and defective areas repaired and patched and fins and other projections exceeding 1/4 in. in height rubbed down or chipped off.
- B. Smooth Form Finish: For formed concrete surfaces exposed-to-view, or that are to be covered with a coating material applied directly to concrete, or a covering material applied directly to concrete, such as waterproofing, damp-proofing, painting or other similar system. This as-cast concrete surface shall be obtained with selected form facing material, arranged orderly and symmetrically with a minimum of seams. Repair and patch defective areas with fins or other projections completely removed and smoothed.
- C. Grout Cleaned Finish: Provide grout cleaned finish to scheduled concrete surfaces which have received smooth form finish treatment. Combine one part Portland cement to 1-1/2 parts fine sand by volume and mix with water to consistency of thick paint. Proprietary additives may be used at Contractor's option. Blend standard Portland cement and white Portland cement, amounts determined by trial patches, so that final color of dry grout will closely match adjacent surfaces.
 - 1. Thoroughly wet concrete surfaces and apply grout to coat surfaces and fill small holes. Remove excess grout by scraping and rubbing with clean burlap. Keep damp by fog spray for at least 36 hours after rubbing.
- D. Related Unformed Surfaces: At tops of walls and grade beams, horizontal offset surfaces occurring adjacent to formed surfaces, strike-off, smooth and finish with a texture matching adjacent unformed surfaces. Continue final surface treatment of formed surfaces uniformly across adjacent unformed surfaces, unless otherwise indicated.

3.09 FLOOR FLATNESS AND LEVELNESS

- A. Floor flatness/levelness tolerances: Tolerances for various floor uses should conform to the requirements set forth in ACI 117 and ACI 302 for "flat" floor profile.

3.10 MONOLITHIC SLAB FINISHES:

- A. Scratch Finish: Apply scratch finish to monolithic slab surfaces that are to receive concrete floor topping or mortar setting beds, and as otherwise indicated.
 - 1. After placing slabs, plane surface to a tolerance not exceeding 1/2 in. in 10 ft. when tested with a 10-ft. straightedge. Slope surfaces uniformly to drains where required. After leveling, roughen surface before final set with stiff brushes, brooms or rakes.

- B. Float Finish: Apply float finish to monolithic slab surfaces to receive trowel finish and other finishes as hereinafter specified, and slab surfaces which are to be covered with membrane or elastic waterproofing, and as otherwise indicated.
- C. Trowel Finish: Apply trowel finish to monolithic slab surfaces indicated, including slab surfaces to be covered with carpet, resilient flooring, paint or other thin-film finish coating system.
- D. Non-Slip Broom Finish: Apply non-slip broom finish to exterior concrete platforms, steps and ramps, and elsewhere as indicated.

3.11 CONCRETE CURING AND PROTECTION:

- A. General: Protect freshly placed concrete from premature drying and excessive cold or hot temperatures. Protect concrete work from physical damage or reduced strength which could be caused by frost, freezing actions, or low temperatures, in compliance with the requirements of ACI 306 as herein specified.
- B. Curing Methods: Perform curing of concrete by moist curing, by moisture-retaining cover curing, by curing compound, and by combinations thereof, as herein specified. Slabs-on-grade shall be cured by moist curing methods.
- C. Curing Formed Surfaces: Cure formed concrete surfaces, including undersides of beams, supported slabs and other similar surfaces by moist curing with forms in place for full curing period or until forms are removed. If forms are removed, continue curing by methods specified above, as applicable.
- D. Protection From Mechanical Injury: During the curing period, the concrete shall be protected from damaging mechanical disturbances, such as load stresses, heavy shock, and excessive vibration. All finished concrete surfaces shall be protected from damage by construction equipment, materials, or methods, by application of curing procedures, and by rain or running water. Self-supporting structures shall not be loaded in such a way as to overstress the concrete.

3.12 REMOVAL OF FORMS:

- A. Formwork not supporting weight of concrete, such as sides of beams, walls, columns, and similar parts of the work, may be removed after cumulatively curing at not less than 50 degrees F for 24 hours after placing concrete, provided concrete is sufficiently hard to not be damaged by form removal operations, and provided curing and protection operations are maintained.
- B. Formwork supporting weight of concrete, such as joints, slabs and other structural elements, may not be removed in fewer than 14 days or until concrete has attained design minimum compressive strength at 28 days. Determine potential compressive strength of in-place concrete by testing field-cured specimens representative of concrete location or members.

- C. Form facing material may be removed 4 days after placement only if shores and other vertical supports have been arranged to permit removal of form facing material without loosening or disturbing shores and support.

3.13 REUSE OF FORMS:

- A. Clean and repair surfaces of forms to be reused in work. Split, frayed, delaminated or otherwise damaged form facing material will not be acceptable for exposed surfaces. Apply new form coating compound as specified for new formwork.
- B. When forms are extended for successive concrete placement, thoroughly clean surfaces, remove fins and latency, and tighten forms to close joints. Align and secure joint to avoid offsets. Do not use "patched" forms for exposed concrete surfaces, except as acceptable to Architect.

3.14 MISCELLANEOUS CONCRETE ITEMS:

- A. Fill in holes and openings left in concrete structures for passage of work by other trades, unless otherwise shown or directed, after work of other trades is in place. Mix, place, and cure concrete as herein specified, to blend with in-place construction. Provide other miscellaneous concrete filling shown or required to complete work.

3.15 CONCRETE SURFACE REPAIRS:

- A. Patching Defective Areas: Repair and patch defective areas with cement mortar immediately after removal of forms, when acceptable to the Architect.
 - 1. Cut out honeycomb, rock pockets, voids over 1/4 inch in any dimension, and holes left by tie rods and bolts, down to solid concrete but in no case to a depth of less than 1 inch. Make edges of cuts perpendicular to the concrete surface. Thoroughly clean, dampen with water, and brush coat the area to be patched with specified bonding agent. Place patching mortar after bonding compound has dried.
 - 2. For exposed-to-view surfaces, blend white Portland cement and standard Portland cement so that, when dry, patching mortar will match color surrounding. Provide test areas at inconspicuous location to verify mixture and color match before proceeding with patching. Compact mortar in place and strike-off slightly higher than surrounding surface.
- B. Repair of Formed Surfaces: Remove and replace concrete having defective surfaces if defects cannot be repaired to satisfaction of Architect. Surface defects, as such, include color and texture irregularities, cracks, spalls, air bubbles, honeycomb, rock pockets, fins, and other projections on surface and stains and other discolorations that cannot be removed by cleaning.

3.16 QUALITY CONTROL TESTING DURING CONSTRUCTION:

- A. Inspection Agency/Project Special Inspector shall verify reinforcement, including foundation reinforcement and slab reinforcement (WWF or reinforcing bar). Inspector shall verify WWF or reinforcement has been chair/placed with proper clearances.
- B. The Owner shall employ a testing laboratory to inspect, sample and test the materials and the production of concrete and to submit test reports. Concrete testing shall be performed by technicians certified by the Maine Concrete Technician Certification Board or ACI Concrete Field Testing Technician Grade I.
- C. Concrete shall be sampled and tested for quality control during placement. Quality control testing shall include the following, unless otherwise directed by the Architect.
- D. Sampling Fresh Concrete: ASTM C 172.
 - 1. Slump: ASTM C143; one test for each concrete load at point of discharge and one test for each set of compressive strength test specimens. Sample shall be taken from middle third of the load per ASTM C172. A slump test must be run prior to the incorporation of the CFP fibers per recommendations of ACI 544. A slump test must be run prior to the addition of a high-range water reducer (superplasticizer) per recommendations of ACI 301.
 - 2. Air Content: ASTM C231 "Pressure method for normal weight concrete." One test for each concrete load, measured at point of discharge and one test for each set of compressive strength specimens.
 - 3. Concrete Temperature: Per ASTM C-1064; One test for each load and one test each time a set of compression test specimens are made.
 - 4. Compression Test Specimen: ASTM C31; one set of 4 standard cylinders for each compressive strength test, unless otherwise directed. Mold and store cylinders for laboratory cured test specimens except when field-cure test specimens are required.
 - a. An insulated Cure Box for specimen curing shall be supplied by Inspection Agency for initial curing as defined in ACI C31.
 - b. Means of heating or cooling the Cure Box shall be provided by the Inspection Agency in order to maintain a temperature between 60 and 80 degrees F. Contractor shall provide an electrical source to the Inspection Agency.
 - c. A maximum-minimum thermometer shall be provided in the Cure Box by the Inspection Agency to record the temperature range of the Cure Box during specimen curing. The Inspection Agency shall record the max/min temperature of the Cure Box when transferring the specimens to the laboratory.
 - d. Test Specimens shall be moist cured.

- e. Refer to ACI C31 for additional requirements for Test Specimens.
- 5. Compressive Strength Tests: ASTM C39; one set for each 50 cu. yds. or fraction thereof, of each concrete class placed in any one day or for each 4,000 sq. ft. of surface area placed; 1 specimen tested at 7 days, 2 specimens tested at 28 days, 1 specimen retained in reserve for later testing if required.
- 6. Pumped concrete shall be tested at point of discharge per ACI 301.
- 7. Testing shall be performed for each concrete slab placement, or per 5,000sf floor area, whichever is more stringent.
- 8. Flatness/Levelness testing shall be performed within 24 hours after placement.
- E. Additional Tests: The testing service will make additional tests of in-place concrete when test results indicate specified concrete strengths and other characteristics have not been attained in the structure, as directed by the Architect. Testing service may conduct tests to determine adequacy of concrete by cored cylinders complying with ASTM C42, or by other methods, as directed. Contractor shall pay for such tests conducted, and any other additional testing as may be required, when unacceptable concrete is verified.

END OF SECTION