

Interior Renovations Batteries and Bulbs

	IBC 2009		NFPA 101 2009	
Sprinklers		NFPA 13		NFPA 13
Occupant Load	T 1004.1.1	1,140 sf Mercantile space (30 gsf/oc) = 38 150 sf Office area (100 sf/oc) = 2 939 sf Storage stock shipping areas (300 gsf/occ) = 4 Total Occupant Load = 44	7.3.1.2	1,140 sf Mercantile space (30 gsf/oc) = 38 150 sf Office area (100 sf/oc) = 2 939 sf Storage stock shipping areas (300 gsf/occ) = 4 Total Occupant Load = 44
Use Group(s)	309.1	Mercantile	36.1.4.2.1	Mercantile Class C
Construction Type	T 503	2B - non-combustible unprotected		II (000) non-combustible unprotected
	1016.1	250' Travel Distance to exits with Sprinklers	36.2.6.3	250' Travel distance to exit
	1014.3	75' Common Path of Travel	36.2.5.3.1	100' Common Path of Travel
	1018.4	50' Dead End	36.2.5.2.1	50' Dead End
Egress Corridors	1018.2	44" min. when Occ. > 50		
	1018.2	36" min. when Occ. <= 50		
	1018.2	24" min. at service corridors to mechanical equipment		