GENERAL NOTES

1. ALL WORK TO CONFORM WITH THE REQUIREMENTS OF THE INTERNATIONAL BUILDING CODE, 2003 EDITION, AND OTHER APPLICABLE CODES AND STANDARDS, INCLUDING, BUT NOT LIMITED TO, NFPA FIRE CODES, THE LOCAL PLUMBING, ELECTRICAL, AND MECHANICAL CODES, THE AMERICANS WITH DISABILITIES ACT, ETC.

2. THE CONTRACTOR SHOULD INSPECT THE PROPOSED CONSTRUCTION AREA PRIOR TO PRICING AND BEGINNING THE WORK. COORDINATION WITH EXISTING SYSTEMS AND REMOVAL/RELOCATION OF ANY OBSTRUCTIONS SHOULD BE INCLUDED IN PRICING. ANY DISCREPANCIES BETWEEN FIELD CONDITIONS AND CONSTRUCTION DOCUMENTS SHOULD BE BROUGHT TO THE ATTENTION OF THE ARCHITECT. DO NOT PROCEED WITH UNRESOLVED ITEMS WITHOUT CONSENT OF THE ARCHITECT.

3. THE CONTRACTOR SHALL, PRIOR TO COMMENCEMENT OF THE WORK, FURNISH CERTIFICATES EVIDENCING THAT THE FOLLOWING INSURANCE LIMITS ARE IN EFFECT, NAMING THE OWNER AS AN ADDITIONAL INSURED, AND REFERENCING THE PROJECT BY NAME AND ADDRESS: WORKMEN'S COMPENSATION = STATUTORY LIMITS, AND COMPREHENSIVE GENERAL LIABILITY = $2,000,000.

4. THE CONTRACTOR SHALL SECURE AND PAY FEES FOR ALL NECESSARY PERMITS AND LICENSES, AND SHALL COORDINATE ALL INSPECTIONS BY AUTHORITIES HAVING JURISDICTION OVER THE WORK.

5. THE CONTRACTOR SHALL USE ONLY WORKERS PROPERLY SKILLED AND EQUIPPED FOR THE VARIOUS TRADES OPERATIONS REQUIRED. CONTRACTOR SHALL CONFIRM UNION LABOR REQUIREMENTS PRIOR TO SUBMISSION OF BID.

6. THE CONTRACTOR SHALL MAINTAIN THE SITE IN A SECURE, CLEAN, SAFE AND ORDERLY CONDITION AT ALL TIMES, CONTAINING ALL DUSTS AND NUISANCES AND SHALL DISPOSE OF ALL RUBBISH AND DEMOLITION/SCRAP MATERIALS IN LEGAL, OFF-SITE DISPOSAL AREAS. PROVIDE NECESSARY ENCLOSURES, SIGNAGE AND PROTECTION AROUND THE WORK AREA, INCLUDING BUSINESSES THAT ARE TO REMAIN OPEN DURING CONSTRUCTION.

7. AS A CONDITION OF FINAL PAYMENT, THE CONTRACTOR SHALL FURNISH A GENERAL RELEASE OF LIEN.

8. THE CONTRACTOR SHALL PROVIDE TO THE OWNER A GUARANTEE OF NOT LESS THAN ONE YEAR ON ALL WORK, FROM THE DATE OF SUBSTANTIAL COMPLETION, OR STATUTORY LIMITS, WHICHEVER IS GREATER, UNLESS OTHERWISE SPECIFICALLY NOTED. ANY DEFECTS IN MATERIALS AND WORKMANSHIP OCCURING WITHIN THIS PERIOD SHALL BE CORRECTED BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE OWNER.

9. THE CONTRACTOR SHALL INCLUDE ALL PROFIT, OVERHEAD AND TAXES, WHICH SHOULD BE ADDED TO ALLOWANCE FIGURES, WHEN QUOTED. CONTRACTOR SHOULD INCLUDE WITH BID A PROPOSED PROFIT AND OVERHEAD MARKUP TO BE APPLIED TO ANY CHANGE ORDERS WHICH MAY OCCUR.

10. THE CONTRACTOR IS TO PROVIDE ALL NECESSARY BLOCKING TO ACCOMPLISH THE WORK AS SHOWN.

11. ALL FINISHES SHALL MEET OR EXCEED FIRE CODE REQUIREMENTS, CONSTRUCTION TO CONFORM TO ALL APPLICABLE FIRE RESISTIVE CONSTRUCTION REQ'TS.

13. ALL MECH., ELECT., PLUMBING AND FIRE PROTECTION ENGINEERING AND WORK TO BE PERFORMED BY THE CONTRACTOR AND LICENSED SUBS, IN CONFORMANCE WITH ALL APPLICABLE CODES AND STANDARDS. PROVIDE SSWITCHES, CONTROLS AND RECEPTACLES AS REQUIRED BY CODE. PROVIDE SHOP AND RECORD DRAWINGS TO OWNER AND ARCHITECT SHOWING CIRCUITRY AND EQUIPMENT LOCATIONS. PROVIDE CODE-REQUIRED POWER, SWITCHES, LIGHTS AND ALARM DEVICES.

14. ALL SITE WORK INDICATED ON DRAWINGS, INCLUDING, BUT NOT LIMITED TO SIDEWALKS, UTILITY CONNECTIONS, ELECTRIC SERVICE, LANDSCAPE, CURBS, PAVEMENT STRIPING, ETC. SHALL BE BY OTHERS UNLESS NOTED OTHERWISE.

15. PROVIDE EMERGENCY LIGHTING, EXIT SIGNS, VISUAL STROBES, HORNS AND PULL STATIONS AS REQUIRED BY CODE. CONFIRM WITH LOCAL FIRE DEPARTMENT.

16. ALL DIMENSIONS ARE TO FACE OF MASONRY OR WALL FINISH U.N.O. (UNLESS NOTED OTHERWISE).

17. METAL STUDS SHALL MEET MFR'S. ENGINEERING DESIGN FOR SIZE, GAUGE, SPACING AND BRACING.

18. SLOPES AT CURB CUTS AND RAMPS SHALL NOT EXCEED 1:12 (8.33%). CROSS SLOPES SHALL NOT EXCEED 1:50 (2%).

19. TENANT STORES TO REMAIN OPEN DURING DEMOLTION AND CONSTRUCTION. CONTRACTOR COORDINATE THE WORK WITH LANDLORD AND EXISTING TENANTS.

SYMBOLS



ABBREVIATIONS

A	AMPERE	F/O	FACE OF	REQD	REQUIRED
AC	ABOVE COUNTER	FPM	FEET PER MINUTE	RESIL	RESILIENT
ACE	ADVANCED CONSUMER ELECTRONICS	FR	FIRE RETARDANT	REV	REVISION
ACST	ACOUSTIC (AL)	FRP	FIBERGLASS REINFORCED PANEL	RL	RAIN LEADER
AD	AREA DRAIN	FT	FOOT, FEET	RM	ROOM
ADD.	ADDENDUM	FTG	FOOTING	RTU	ROOF TOP UNIT
ADJ	ADJACENT	FTR	FLUE THRU ROOF	RO	ROUGH OPENING
ADJT	ADJUSTABLE	FUR.	FURRING (ED)	RP	RECEPTACLE PANEL
AFF	ABOVE FINISH FLOOR				
AIC	AMPERE INTERRUPTING CAPACITY	GA	GAGE	S	SOUTH
AL	ALUMINUM	GALV	GALVANIZED	SAN	SANITARY
ALT	ALTERNATE	GC, GCC	GENERAL CONTRACTOR	SATC	SUSPENDED ACOUSTICAL TILE CEILING
ALUC	ALUCOBOND	GEN	GENERAL	SCHED	SCHEDULE (D)
AMP	AMPERE	GL	GLASS	SECT	SECTION
AP	ACCESS PANEL	GPM	GALLONS PER MINUTE	SF	STOREFRONT
APPROX	APPROXIMATE	GR	GRADE	SH	SHEET
ARCH	ARCHITECT (URAL)	GRD	GROUND	SIM	SIMILAR
ASPH	ASPHALT	GYP	GYPSUM	SQ	SQUARE
ASTM	AMERICAN SOCIETY FOR TESTING AND MATERIALS	GFCI	GROUND FAULT CIRCUIT INTERRUPTER	SS	STAINLESS STEEL
				ST	STREET
BAL	BALANCE	HCP, HP	HANDICAPPED	STD	STANDARD
BD	BOARD	HDW	HARDWARE	STL	STEEL
BET.	BETWEEN	HDWD	HARDWOOD	STOR	STORAGE
BIT.	BITUMINOUS	HM	HOLLOW METAL	STS	SECURITY/TELEPHONE SYSTEM
BKR	BREAKER	HORIZ	HORIZONTAL	SUSP	SUSPENDED
BLDG	BUILDING	HP	HORSEPOWER; HIGHPOINT	SW	SWITCH
BLKG	BLOCKING	HT	HEIGHT	SWGR	SWITCHGEAR
BM	BEAM	HVAC	HEATING/VENTILATING/ AIR CONDITIONING	SYM	SYMMETRY (ICAL)
BOT	BOTTOM			SYS	SYSTEM
BRIDG	BRIDGING	HW	HOT WATER		
BRG	BEARING	HWH	HOT WATER HEATER	T	TREAD
BS	BOTH SIDES			TEL	TELEPHONE
BTU	BRITISH THERMAL UNIT	KV	KILOVOLT	TEMP	TEMPERATURE; TEMPORARY
BUR.	BUILT UP ROOFING	KVA	KILOVOLT – AMPERE	THK	THICK (NESS)
		KW	KILOWATT	THR	THRESHOLD
CAB.	CABINET			THRU	THROUGH
CAP.	CAPACITY	LAM	LAMINATE (D)	T/O	TOP OF
CB	CIRCUIT BREAKER	LAV	LAVATORY	TOW	TOP OF WALL
CFM	CUBIC FEET PER MINUTE	LBS	POUNDS	TS	TIME SWITCH
CI	CAST IRON	LC	LIGHT CONTACTOR	TYP	TYPICAL
CJ	CONTROL JOINT	LF	LINEAR FEET	TR	TREATED
CKT	CIRCUIT	LG	LONG; LENGTH	TV	TELEVISION
CLG	CEILING	LP	LIGHTING PANEL		
CLO	CLOSET	LTG	LIGHTING	UC	UNDER COUNTER
CLR	CLEAR	LV	LOW VOLTAGE	UG	UNDERGROUND
CMU	CONCRETE MASONRY UNIT			UH	UNIT HEATER
CO	CLEANOUT	MAS	MASONRY	UL	UNDERWRITER'S LABORATORY
COL	COLUMN	MATL	MATERIAL	UNO	UNLESS NOTED OTHERWISE
CONC	CONCRETE	MAX	MAXIMUM		
CONN	CONNECTION	MBH	THOUSAND BTU PER HOUR	V	VOLT
CONST	CONSTRUCTION	MCC	MOTOR CONTROL CENTER	VA	VOLT-AMP
CONT	CONTINUOUS	MDP	MAIN DISTRIBUTION PANEL	VC	VACUUM CLEANER
CONTR	CONTRACTOR	MECH	MECHANICAL	VCT	VINYL COMPOSITION TILE
COP	COPPER	MED	MEDIUM	VERT	VERTICAL
CPT	CARPET (ED)	MET.	METAL	VP	VENT PIPE
CSK	COUNTERSUNK	MFR	MANUFACTURER	VTR	VENT THRU ROOF
CT	CERAMIC TILE	MGR	MANAGER	VWC	VINYL WALL COVERING
CW	COLD WATER, CONTROL WIRE	MIN	MINIMUM		
		MISC	MISCELLANEOUS		
E	EAST	MLO	MAIN LUGS ONLY		
EA	EACH	MO	MASONRY OPENING		
EIFS	EXTERIOR INSULATED FINISH SYSTEM	MTD	MOUNTED		
EJ	EXPANSION JOINT	MTG	MOUNTING		
EL	ELEVATION	N	NORTH		
ELEC	ELECTRIC (AL)	NIC	NOT IN CONTRACT		
ENC	ENCLOSE (URE)	NO.	NUMBER		
EMER	EMERGENCY	NOM	NOMINAL		
EP	ELECTRICAL PANEL	NTS	NOT TO SCALE		
EQ	EQUAL	OC	ON CENTER		
EQUIP.	EQUIPMENT	OD	OUTSIDE DIAMETER		
EW	EACH WAY	OFF	OFFICE		
EWC	ELECTRIC WATER COOLER	OPNG	OPENING		
EXH	EXHAUST	OPP	OPPOSITE		
EXIST.	EXISTING	OPS	OPERATIONS		
EXP	EXPANSION; EXPOSED	OVHD	OVERHEAD		
EXT	EXTERIOR	PCF	POUNDS PER CUBIC FOOT		
		PCP	PRECAST CONC. PANEL		
F	FAHRENHEIT	PH	PHASE		
FA	FIRE ALARM	PL	PLATE		
FD	FLOOR DRAIN; FIRE DAMPER	PLAM	PLASTIC LAMINATE		
FDN	FOUNDATION	PLAS	PLASTER		
FE	FIRE EXTINGUISHER	PLMB	PLUMBING		
FFE	FURNITURE, FIXTURES AND EQUIPMENT	PLYWD	PLYWOOD		
FH	FIRE HYDRANT	PNL	PANEL		
FIN.	FINISH (ED)	POST	POINT OF SALE TERMINAL		
FL	FLOOR; FULL LENGTH	PP	POWER PANEL		
FLG	FLASHING	R	RADIUS; RISER		
FLUOR	FLUORESCENT	RD	ROOF DRAIN		
F/O	FACE OF	REINF	REINFORCEMENT		

PINE TREE SHOPPING CENTER
EXTERIOR CANOPY AND FACADE RENOVATIONS

BRIGHTON AVENUE AND RAND AVENUE
PORTLAND, MAINE

OWNER:
CENTRO HERITAGE SPE 4LLC
40 SKOKIE BLVD. SUITE 600, NORTHBROOK, IL 60062
www.centrowatt.com

ARCHITECT:
SCHNEE ARCHITECTS, INC.
339 AUBURN STREET, AUBURNDALE, MA. 02466
PHONE: 617-630-1900 FAX: 617-630-1959
www.schneearch.com

STRUCTURAL ENGINEER:
FLOOD CONSULTING
56 LAUREL DRIVE, HUDSON, MA. 01749
PHONE: 978-562-6499 FAX: 978-562-6246

LOCUS MAP (NO SCALE)



LIST OF DRAWINGS

GENERAL

A001 COVER SHEET, GENERAL NOTES, ABBREVIATIONS

ARCHITECTURAL

A101 FLOOR PLANS
A102 REFLECTED CEILING PLANS
A103 ROOF PLAN
A201 BUILDING ELEVATIONS
A301 SECTIONS/DETAILS
A302 SECTIONS/DETAILS
SP100 SPECIFICATIONS
SP101 SPECIFICATIONS

STRUCTURAL

S100 STRUCTURAL PLAN AND DETAILS
S102 GENERAL NOTES AND DETAILS

DESIGN DATA

THIS FACADE DESIGN IS BASED ON THE FOLLOWING DESIGN ASSUMPTIONS:

BUILDING CLASSIFICATIONS AND DATA

APPLICABLE CODES:
- 2003 INTERNATIONAL BUILDING CODE
- 2003 INTERNATIONAL PLUMBING CODE
- AMERICAN DISABILITIES ACT
- NATIONAL ELECTRICAL CODE, CURRENT EDITION
- THE NATIONAL FIRE PROTECTION ASSOCIATION LIFE SAFETY CODE, NFPA 101 AND NFPA 72, NAT'L. FIRE ALARM CODE
- THE NATIONAL FIRE PROTECTION ASSOCIATION CODE, NFPA 13 & 231C

OCCUPANCY GROUP CLASSIFICATION (PER ICC CHAPTER 3):
- USE GROUP A2 – ASSEMBLY
- USE GROUP B – BUSINESS
- USE GROUP M – MERCANTILE

TYPE OF CONSTRUCTION CLASSIFICATION:
- TYPE 2B, FULLY SPRINKLERED

SITE ADDRESS:
- 1100 BRIGHTON AVENUE
- PORTLAND, ME 04102-1030

PRICING NOTES

P1. SEE GENERAL NOTES THIS SHEET FOR FURTHER INFORMATION.

P2. EXTERIOR WALL SCONCE TO BE BL-38 AS MANUFACTURED BY ALLIGHTING, 2930 SOUTH FAIRVIEW STREET, SANTA ANA, CA, PH. 714-668-1107.

P3. UNDER CANOPY LIGHT FIXTURE TO BE6783WH213N1 AS MANUFACTURED BY LIGHTOLIER, 631 AIRPORT ROAD, FALL RIVER, MA PH. 508-679-8151.

P4. ALLOW THE SUM OF $75,000 FOR RENOVATIONS TO THE EXISTING SHOPPING CENTER PYLON SIGN.

BID ALTERNATES

ALTERNATE #1:
INCLUDE IN THE BASE BID A PRICE TO PROVIDE/INSTALL DECORATIVE PILASTERS ACROSS THE NORTH AND WEST FACADES AT THE EXISTING KEY BANK.

ALTERNATE #2:
INCLUDE IN THE BASE BID A PRICE TO ELECTROSTATICALLY PAINT EXISTING MILL FINISH ALUMINUM STOREFRONT SCHEDULED TO REMAIN, THE ALUMINUM IS TO BE PAINTED TO MATCH A MEDIUM BRONZE FINISH.

SITE DETAILS





Rev. #	Issue	Description	Date
0	08/14/07	BID	

OWNER: CENTRO HERITAGE SPE 4LLC
40 SKOKIE BLVD, SUITE 600
NORTHBROOK, IL 60062

Drawing Description: FACADE IMPROVEMENTS COVER SHEET

Master/Project Name: PINE TREE SHOPPING CENTER, BRIGHTON AVE, PORTLAND, ME

State: ME
Site: PINE TREE

Phase: BID

Sheet No.: A001

Drawn By: RWB
Checked By: GWB
Date: 08/14/2007
Approved
Scale: AS NOTED

Seal

A/E Project No.: 05120

Architects/Engineer: SCHNEE ARCHITECTS, INC.
339 AUBURN STREET
AUBURNDALE, MA 02466
TEL 617-630-1900 FAX 617-630-1959