THE FOLLOWING BUILDING CODES AND STANDARDS SHALL BE REFERENCED DURING CONSTRUCTION:

IBC 2009	EDITION OF THE IBC INTERNATIONAL BUILDING CODE
ASCE 7	AMERICAN SOCIETY OF CIVIL ENGINEERS, MINIMUM DESIGN LOADS FOR BUILDINGS AND OTHER STRUCTURES
ACI 301	AMERICAN CONCRETE INSTITUTE SPECIFICATION FOR STRUCTURAL CONCRETE
AISC	AMERICAN INSTITUTE OF STEEL CONSTRUCTION
ACI 318	AMERICAN CONCRETE INSTITUTE BUILDING CODE REQUIREMENTS FOR REINFORCED CONCRETE
ASTM	AMERICAN SOCIETY OF TESTING AND MATERIALS
NDS	NATIONAL DESIGN SPECIFICATIONS FOR WOOD CONSTRUCTION BY NATIONAL FOREST PRODUCTS ASSOCIATION, 2005

REFERENCE ARCHITECTURAL PLANS FOR DIMENSIONS NOT SHOWN. REFERENCE MECHANICAL, ELECTRICAL, AND ARCHITECTURAL PLANS FOR SIZES AND LOCATIONS OF WALL AND SLAB OPENINGS, DUCTS, PIPING, CURBS, AND EQUIPMENT PADS. IN THE EVENT OF A CONFLICT BETWEEN THE DRAWINGS, SPECIFICATIONS, OR NOTES ON THE DRAWINGS, THE ENGINEER SHALL BE NOTIFIED PRIOR TO CONSTRUCTION.

EXISTING DIMENSIONS AND CONDITIONS ARE FOR REFERENCE ONLY. CONTRACTOR SHALL VERIFY ALL EXISTING CONSTRUCTION AND DIMENSIONS IN THE FIELD PRIOR TO CONSTRUCTION OR FABRICATION. ALL DISCREPANCIES SHALL BE REPORTED TO THE ENGINEER PRIOR TO COMMENCING WORK.

THE CONTRACTOR SHALL NOTIFY THE ENGINEER IF DEVIATIONS OR CHANGES ARE REQUIRED TO THE CONTRACT DOCUMENTS OR APPROVED SHOP DRAWINGS DUE TO INTERFERENCES, FABRICATION ERRORS, OR OTHER CAUSES.

THE STRUCTURE IS SELF-SUPPORTING AND STABLE AFTER THE ENTIRE BUILDING IS COMPLETELY CONSTRUCTED. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR ERECTION PROCEDURES AND SEQUENCING DURING CONSTRUCTION AND ERECTION TO PROVIDE AND ENSURE LOCAL AND OVERALL STABILITY OF THE BUILDING AND ITS COMPONENTS DURING CONSTRUCTION AND ERECTION. THE CONTRACTOR SHALL RETAIN A LICENSED STRUCTURAL ENGINEER TO DESIGN TEMPORARY BRACING/SHORING AND DETERMINE WHERE THE TEMPORARY BRACING/SHORING IS NEEDED.

GENERAL NOTES

SCALE: NTS

SNOW LOADS:
- GROUND SNOW LOAD, P_g = 60 PSF
- SNOW EXPOSURE FACTOR, C_e = 1.0
- SNOW LOAD IMPORTANCE FACTOR, I = 1.0
- THERMAL FACTOR, C_t = 1.1
- FLAT ROOF SNOW LOAD, P_f = 46.2 PSF + DRIFT

WIND LOADS:
- BASIC WIND SPEED = 100 MPH
- IMPORTANCE FACTOR, I_w = 1.0
- WIND EXPOSURE B
- MAIN WINDFORCE-RESISTING SYSTEM (INCLUDES WINDWARD + LEEWARD) = 13.8 PSF

SEISMIC CRITERIA:
- SOIL SITE CLASSIFICATION = D
- DESIGN SPECTRAL RESPONSE ACCELERATION:
  - S_{ds} = .37
  - S_{d1} = .16
- SEISMIC USE GROUP I
- SEISMIC DESIGN CATEGORY C
- RESPONSE MODIFICATION COEFFICIENT....R = 6.5
- OCCUPANCY IMPORTANCE FACTOR....I = 1.0
- BASE SHEAR....$V_s = C_s * W = 0.08 * W$ (W = SEISMIC WEIGHT)

DESIGN CRITERIA

SCALE: NTS

MASONRY CONSTRUCTION AND MATERIALS SHALL CONFORM TO ALL REQUIREMENTS OF BUILDING CODE REQUIREMENTS FOR MASONRY STRUCTURES [illegible]

[illegible]

MASONRY NOTES

SCALE: NTS

ROOF DECK, ACCESSORIES, AND WORKMANSHIP SHALL CONFORM TO THE THE STEEL DECK INSTITUTE'S [illegible]

[illegible]

ROOF DECK NOTES

SCALE: NTS

ALL STRUCTURAL STEEL WORK SHALL CONFORM TO:

AISC AMERICAN INSTITUTE OF STEEL CONSTRUCTION, MANUAL OF STEEL CONSTRUCTION, NINTH EDITION
AISC CODE OF STANDARD PRACTICE FOR STEEL BUILDINGS AND BRIDGES

[illegible]

2. SHEAR STUDS, WHERE REQUIRED, ARE INDICATED ON THE DRAWINGS AS [XX], WHERE XX IS THE NUMBER OF STUDS EQUALLY SPACED BETWEEN SUPPORTS ON A BEAM OR GIRDER.

STRUCTURAL STEEL NOTES

SCALE: NTS

QUALITY ASSURANCE: CONTRACTOR SHALL PROVIDE QUALITY CONTROL OVER ALL FABRICATION AND ERECTION ACTIVITIES.

STANDARDS: WORK SHALL MEET THE REQUIREMENTS OF THE FOLLOWING STANDARDS:

- AMERICAN IRON AND STEEL INSTITUTE (A.I.S.I.), LATEST EDITION OF "DESIGN OF COLD FORMED STEEL STRUCTURAL MEMBERS"
- AMERICAN WELDING SOCIETY (A.W.S.) D1.3, LATEST EDITION OF "STRUCTURAL WELDING CODE – STEEL SHEET"
- AMERICAN SOCIETY FOR TESTING AND MATERIALS (A.S.T.M.)
- AMERICAN INSTITUTE OF STEEL CONSTRUCTION (A.I.S.C.)
- STEEL STUD MANUFACTURERS ASSOCIATION (S.S.M.A.) ICBO ER-4943P "PRODUCT TECHNICAL INFORMATION"

PRODUCT HANDLING (PROTECTION OF PRODUCTS): MATERIAL SHALL BE PROTECTED FROM RAIN AND SNOW.

PRODUCTS:
1. ALL FRAMING MATERIALS SHALL BE MANUFACTURED IN ACCORDANCE w/ THE LATEST EDITION OF STEEL STUD MANUFACTURERS ASSOCIATION AND BE OF TYPE AND SIZE AS SHOWN ON THE STRUCTURAL DRAWINGS. ALL MATERIAL 16 GAGE AND HEAVIER SHALL BE 50 KSI.
2. GALVANIZED MATERIAL:
   A. ALL GALVANIZED STUDS AND JOISTS SHALL BE FORMED FROM STEEL THAT CORRESPONDS TO THE MINIMUM REQUIREMENTS OF A.I.S.I. STANDARDS.
   B. ALL GALVANIZED STUDS, JOISTS, TRACKS, BRIDGING, AND ACCESSORIES SHALL BE FORMED FROM STEEL HAVING A GALVANIZED COATING MEETING THE REQUIREMENTS OF A.S.T.M. A653.
3. THE PHYSICAL AND STRUCTURAL PROPERTIES LISTED BY SSMA SHALL BE CONSIDERED THE MINIMUM PERMITTED FOR FRAMING MEMBERS. ANY SUBSTITUTIONS SHALL BE SUBMITTED TO THE STRUCTURAL ENGINEER. REPORT DISCREPANCIES TO STRUCTURAL ENGINEER.

POWDER ACTUATED FASTENERS IN CONCRETE SHALL BE 0.145" DIAMETER HILTI X-DNI OR X-EDNI FOR STEEL, U.N.O. PROVIDE MINIMUM 1/2" EMBEDMENT INTO CONCRETE. PROTECTIVE COATINGS ON SCREW FASTENERS SHALL BE COMPATIBLE WITH LIGHT GAGE FRAMING.

TEMPORARY BRACING SHALL BE PROVIDED BY AND BE THE RESPONSIBILITY OF THE CONTRACTOR. PERMANENT BRACING AND BRIDGING SHALL BE IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS AND APPLICABLE CODES. BRIDGING SHALL BE SPACED PER MANUFACTURER'S RECOMMENDATIONS. END BLOCKING SHALL BE PROVIDED FOR STEEL JOISTS WHERE JOIST ENDS ARE NOT OTHERWISE RESTRAINED AGAINST ROTATION.

ALL TRACK BUTT JOINTS, ABUTTING PIECES OF TRACK SHALL BE SECURELY ANCHORED TO A COMMON STRUCTURAL ELEMENT, SUCH AS A STUD, OR THEY SHALL BE BUTT WELDED TOGETHER. SPLICING OF OTHER MEMBERS IS NOT PERMITTED, U.N.O.

JACK STUDS SHALL BE INSTALLED BELOW WINDOW SILLS, ABOVE WINDOW AND DOOR HEADS TO FURNISH SUPPORT AND SHALL BE SECURELY ATTACHED TO SUPPORTING MEMBERS. PROVIDE INSULATION EQUAL TO THAT SPECIFIED IN ARCHITECTURAL DRAWINGS IN ALL DOUBLE OR MORE JAMB STUDS OR HEADERS WHICH WILL NOT BE ACCESSIBLE TO THE INSULATION CONTRACTOR.

ALL WELDING SHALL BE TOUCHED UP WITH A ZINC RICH PAINT.

STEEL TRUSSES SHALL BE LATERALLY SUPPORTED AT ALL PANEL POINTS AND AS SHOWN ON PLANS. REQUIRED X-BRACING SHALL BE INSTALLED IMMEDIATELY AFTER ERECTION OF EACH ROOF TRUSS.

LIGHT GAGE FRAMING NOTES

SCALE: NTS

[illegible]

ABBREVIATIONS

SCALE: NTS



LEGEND

SCALE: NTS

CASCO BAY ENGINEERING
434 Fore Street
Portland, ME 04101

CLIENT
JOHN T. BRENNAN & ASSOCIATES
PO BOX 4285
WINDHAM, NH 03087

SULLIVAN TIRE
1100 BRIGHTON AVE.
PORTLAND, ME

BUILDING RENOVATION

ISSUED

No.	DESCRIPTION	DR BY	CKD BY	DATE
A	FOR REVIEW	SJP	ED	11-6-12
B	FOR PERMIT	SJP	ED	11-20-12

SHEET TITLE

STRUCTURAL NOTES

DESIGNED: SJP
DRAWN: SJP
DATE: 10-25-12
PROJECT NUMBER: 12-104

S000

PRINTED: Nov 20, 2012