

## SECTION 102800 - TOILET, BATH, AND LAUNDRY ACCESSORIES

## PART 1 - GENERAL

## 1.1 SUMMARY

- A. This Section includes the following:
  - 1. Public-use washroom accessories.
  - 2. Custodial accessories.

## 1.2 SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Product Schedule:
  - 1. Identify locations using room designations indicated on Drawings.
  - 2. Identify products using designations indicated on Drawings.

## PART 2 - PRODUCTS

## 2.1 PUBLIC-USE WASHROOM ACCESSORIES

- A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
  - 1. Bobrick Washroom Equipment, Inc.
- B. Toilet Tissue (Roll) Dispenser: #B-2840
  - 1. Description: Single-roll dispenser.
  - 2. Mounting: Surface mounted
  - 3. Operation: Noncontrol delivery with standard spindle
  - 4. Capacity: Designed for 4-1/2- or 5-inch diameter tissue rolls.
  - 5. Material and Finish: Stainless steel, No. 4 finish (satin).
- C. Paper Towel (Folded) Dispenser: #B-359
  - 1. Mounting: Semirecessed
  - 2. Material and Finish: Stainless steel, No. 4 finish (satin).
  - 3. Lockset: Tumbler type.
  - 4. Refill Indicators: Pierced slots at sides or front.
- D. Liquid-Soap Dispenser #B-155:
  - 1. Description: Designed for dispensing soap in liquid or lotion form.
  - 2. Mounting: Vertically oriented, surface mounted.
  - 3. Lockset: Tumbler type.
  - 4. Refill Indicator: Window type.

- E. Grab Bar B-6806 x 36” and 42”:
  - 1. Mounting: Flanges with concealed fasteners.
  - 2. Material: Stainless steel, 0.05 inch (1.3 mm) thick.
    - a. Finish: Smooth, No. 4, satin finish.
  - 3. Outside Diameter: 1-1/2 inches.
  
- F. Mirror Unit B-290 2436:
  - 1. Frame: Stainless-steel angle, 0.05 inch (1.3 mm) thick.
    - a. Corners: Manufacturer's standard
  - 2. Hangers: Produce rigid, tamper- and theft-resistant installation, using method indicated below.
    - a. One-piece, galvanized steel, wall-hanger device with spring-action locking mechanism to hold mirror unit in position with no exposed screws or bolts.
  
- G. Other Items:
  - a. Mop and Broom holder utility shelf: B-224 x 36”
  - b. Robe Hook: B-6727

## 2.2 FABRICATION

- A. Keys: Provide universal keys for internal access to accessories for servicing and resupplying. Provide minimum of 6 keys to Owner's representative.

## PART 3 - EXECUTION

### 3.1 INSTALLATION

- A. Install accessories according to manufacturers' written instructions, using fasteners appropriate to substrate indicated and recommended by unit manufacturer. Install units level, plumb, and firmly anchored in locations and at heights indicated.

END OF SECTION 102800