PHASE II

EVERGREEN CREDIT UNION

225 RIVERSIDE STREET PORTLAND, MAINE

ABBREVIATIONS

AFF	ABOVE FINISH FLOOR
ALUM OR AL	ALUMINUM
AWP	ACOUSTICAL WALL PANEL
BIT	BITUMINOUS
BM	BENCH MARK
BOT	BOTTOM
BRG	BEARING
BRK	BRICK
C	CARPET
CAB	CABINET
CB	CHALK BOARD
CC	CENTER TO CENTER
CH	CONCRETE FLOOR WITH HARDENER
CL	CONTROL JOINT
CL	CENTER LINE
CLG	CEILING
CMU	CONCRETE MASONRY UNIT
CONC	CONCRETE
CONT	CONTINUOUS
CONST	CONSTRUCTION
CONTR	CONTRACTOR
CT	CERAMIC TILE
DBL	DOUBLE
DC	DOOR CLOSER
DIA	DIAMETER
DIM	DIMENSION
DNA	DOES NOT APPLY
DR	DOOR
DTL	DETAIL
DWG	DRAWING
E	EAST
EA	EACH
EF	EACH FACE
EJ	EXPANSION JOINT
EL	ELEVATION
ELEC	ELECTRICAL
ELEV	ELEVATOR
EMHO	ELECTROMAGNETIC HOLD OPEN
EQ	EQUAL
EW	EACH WAY
EWC	ELECTRIC WATER COOLER
EXIST OR EX	EXISTING
EXP	EXPANSION
EXT	EXTERIOR
FCS	FLOOR COATING SYSTEM
FD	FLOOR DRAIN
FDN	FOUNDATION
FE	FIRE EXTINGUISHER
FFE	FINISH FLOOR ELEVATION
FH	FINISH
FH FL OR FF	FINISH FLOOR
FH GR	FINISH GRADE
FL	FLOOR
FR	FIRE RATING
FRPG	FRAMING
FT	FEET (FOOT)
FV	FIELD VERIFY
FWC	FABRIC WALL COVERING
G	GRANITE
GA	GAUGE
GALV	GALVANIZED
GB	GRAB BARS
GC	GENERAL CONTRACTOR
GWB	GYPSUM WALL BOARD
HC	HANDICAP
HD WD	HARDWOOD
HDR	HEADER
HDWE	HARDWARE
HM	HOLLOW METAL
HORIZ	HORIZONTAL
HT	HEIGHT
ID	INSIDE DIAMETER
IF	INSIDE FACE
IN	INCHES
INSUL	INSULATION
INT	INTERIOR
JNT OR JT	JOINT
KEC	KITCHEN EQUIPMENT CONSULTANT
KP	KICK PLATE
L	LAVATORY
LAB	LABEL (FIRE)
LHTL	LINTEL
LOC	LOCATION
LS	LOCKSET
M	MARBLE
MAS	MASONRY
MAX	MAXIMUM
MB	MARKER BOARD
MECH	MECHANICAL
MFGR	MANUFACTURER
MIN	MINIMUM
MISC	MISCELLANEOUS
MO	MASONRY OPENING
MR	MOP OPENING
MRSD	MOISTURE RESISTANT GYPSUM BOARD
MTL	METAL
N	NORTH
NA	NOT APPLICABLE
NIC	NOT IN CONTRACT
NO	NUMBER
NOM	NOMINAL
NTS	NOT TO SCALE
OA	OVERALL
OC	ON CENTER
OD	OUTSIDE DIAMETER
OF	OUTSIDE FACE
OPNG	OPENING
OPP	OPPOSITE
P	PAINT
PTD	PAINTED
PB	PARKING BAR
PL	PLATE
PLY WD	PLYWOOD
PNL	PANEL
PS	PASSAGE LATCH SET
PT.	PRESSURE TREATED
PT & D	PAPER TOWEL AND WASTE DISPENSER
PTN	PARTITION
RD	ROOF DRAIN
REF	REFER
REF	REFRIGERATOR
REINF	REINFORCED
REQD	REQUIRED
RM	ROOM
RO	ROUGH OPENING
S	SOUTH
SAT	SUSPENDED ACOUSTICAL TILE CEILING
SC	SHOWER CURTAIN
SD	SOAP DISPENSER
SCHED	SCHEDULE
SECT	SECTION
SGD	SUSPENDED GYPSUM BOARD CEILING
SHT	SHEET
SIM	SIMILAR
SHD	SANITARY NAPKIN DISPOSAL
SPEC	SPECIFICATIONS
SQ	SQUARE
SRS	SYNTHETIC SPORTS SURFACE
STD	STANDARD
STL	STEEL
STRUCT	STRUCTURAL
STV	STRAIGHT VINYL BASE
SV	SHEET VINYL
T	TEMPERED GLASS
TB	TACK BOARD
TH	THERMAL INSULATION
THK	THICKNESS
TO	TOP OF
TOB	TOP OF BEAM
TOM	TOP OF MASONRY
TOW	TOP OF WALL
TP	TOILET PAPER DISPENSER
TYP	TYPICAL
VB	VAPOR BARRIER
VCT	VINYL COMPOSITION TILE
VERT	VERTICAL
VWC	VINYL WALL COVERING
W	WEST
W/	WITH
WC	WATER CLOSET
WD	WOOD
WF	WATER FOUNTAIN
WG	WIRE GLASS
WP	WOOD PANELING

GENERAL NOTES

1. ALL WORK SHALL CONFORM TO LOCAL AND STATE LAWS, ORDINANCES AND PREVAILING EDITIONS OF ADOPTED BUILDING CODES. IT IS THE CONTRACTOR'S RESPONSIBILITY TO SECURE ALL PERMITS FOR THE WORK.
2. THE CONTRACTOR SHALL VERIFY ALL CONDITIONS AND DIMENSIONS PRIOR TO COMMENCING THE WORK AND REPORT ANY DISCREPANCIES TO THE ARCHITECT. CONTRACTOR SHALL PROCEED WITH THE WORK ONLY AFTER SUCH DISCREPANCIES HAVE BEEN RESOLVED BY THE ARCHITECT. CONTRACTOR SHALL ALLOW A 48 HOUR TIME FRAME FOR RESOLVING DISCREPANCIES ONCE THE ARCHITECT HAS ACKNOWLEDGED THE CONDITION.
3. CONTRACTOR SHALL REVIEW AND VERIFY ALL EXISTING CONDITIONS PRIOR TO STARTING THE WORK IN ANY GIVEN AREA.
4. WORK WITH GIVEN DIMENSIONS AND LARGE SCALE DETAILS. DO NOT SCALE THE DRAWINGS AS THE REPRODUCTIVE PROCESS TENDS TO DISTORT THE ACCURACY OF THE GRAPHIC SCALE INDICATED.
5. ALL CONSTRUCTION ACTIVITIES SHALL BE PERFORMED IN A NEAT, SAFE, AND CLEAN MANNER. ALL CONSTRUCTION WASTE SHALL BE REMOVED FROM THE BUILDING. SITE BURNING IS NOT ALLOWED. LEAVE WORK AREA IN A CLEAN, SAFE CONDITION AT THE END OF EACH WORK DAY.
6. ALL CONSTRUCTION DEBRIS SHALL BE DISPOSED OF AT AN APPROVED OFF-SITE FACILITY IN COMPLIANCE WITH ALL REGULATIONS.
7. ALL WOOD IN CONTACT WITH MASONRY OR CONCRETE SHALL BE PRESSURE TREATED.
8. ALL CEILINGS SHALL BE LEVEL TO TO A TOLERANCE OF 1/8" IN A 20'-0" RADIUS WHEN CHECKED WITH A 10' STRAIGHT EDGE.
9. INSTALL SOLID BLOCKING AT WALL FRAMING BEHIND ALL SURFACE MOUNTED FIXTURES, TRIM AND HANDRAILS.
10. ALL GRAB BARS AND HANDRAILS SHALL BE ABLE TO SUPPORT A DEAD WEIGHT OF 250 LBS AT ANY POINT.
11. THE LOCATION OF ANY DOOR JAMBS NOT DIMENSIONED SHALL BE 6" FROM ADJACENT PERPENDICULAR WALL.
12. ALL WALL PARTITIONS SHALL EXTEND FLOOR TO STRUCTURE ABOVE, UNLESS OTHERWISE NOTED.
13. ALL NEW SHEETROCK IN WET AREAS (PLUMBING FIXTURES) SHALL BE MOISTURE-RESISTANT TYPE, UNLESS OTHERWISE NOTED.
14. ALL EXTERIOR WALLS SHALL HAVE FULL - THICK THERMAL BATT INSULATION (R-19 MIN)
15. ALL INTERIOR WALLS SHALL HAVE FULL- THICK ACOUSTICAL BATT INSULATION.
16. THE OWNER SHALL BE RESPONSIBLE FOR THE REMOVAL OF ALL HAZARDOUS MATERIALS PRIOR TO THE COMMENCEMENT OF THE CONTRACTORS WORK.
17. THESE ARCHITECTURAL DRAWINGS WERE PREPARED FOR THE GENERAL CONTRACTOR/OWNER AS PART OF AN ABBREVIATED SERVICE AGREEMENT, AND AS SUCH, DO NOT DELINEATE ALL ASPECTS OF THE REQUIRED WORK.
18. THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR THE COORDINATION OF ALL ASPECTS OF THE WORK, INCLUDING, BUT NOT LIMITED TO, CIVIL, STRUCTURAL, MECHANICAL, AND ELECTRICAL ENGINEERING DISCIPLINES AND TRADES.
19. REFER TO ACCESSIBILITY DETAIL SHEET FOR AMERICANS WITH DISABILITIES ACT (ADA) AND MAINE HUMAN RIGHTS ACT (MHRA) CONSTRUCTION CRITERIA.

MATERIALS

- CONCRETE
- CONCRETE MASONRY UNIT
- BRICK
- GRAVEL
- SOIL
- STUD PARTITION (NEW)
- STEEL
- WOOD FRAMING
- WOOD BLOCKING
- PLYWOOD
- GYPSUM BOARD
- SUSPENDED ACOUSTICAL TILE
- BATT INSULATION
- RIGID INSULATION
- FINISH WOOD
- ONE HOUR RATED PARTITION
- TWO HOUR RATED PARTITION
- EXISTING PARTITION (SCREENED)
- NEW PARTITION

SYMBOLS

- 101 ROOM NUMBER
- 1 DOOR NUMBER
- A WINDOW NUMBER
- A/A7 BUILDING SECTION
- 1/A0.0 WALL SECTION
- B/A7.0 DETAIL SECTION
- 6/A9 CASEWORK ELEVATION
- 1/A9.0 INTERIOR ELEVATION
- VERTICAL ELEVATION
- PARTITION TYPE
- STRUCTURAL CENTERLINE

LOCATION PLAN



DRAWING INDEX

A0 COVER SHEET
A1 SECOND FLOOR PLAN
A2 ENLARGED FLOOR PLAN
A3 REFLECTED CEILING PLAN
A4 DOORS & FINISHES
A5 DETAILS
A6 ACCESSIBILITY DETAILS & NOTES

PROJECT TEAM

COPYRIGHT
REPRODUCTION OR MISUSE OF THIS DOCUMENT WITHOUT WRITTEN PERMISSION FROM GRANT HAYS ASSOCIATES IS PROHIBITED

LICENSED ARCHITECT
MICHAEL F. HAYS
NO. 1724
STATE OF MAINE

REVISIONS

GRANT HAYS ASSOCIATES

ARCHITECTURE
INTERIOR DESIGN
P.O. BOX 6179 FALMOUTH, MAINE 04105
(207) 871-5900
(207) 871-9308

JOB TITLE
PHASE II
EVERGREEN CREDIT UNION
225 RIVERSIDE STREET PORTLAND, MAINE

DRAWING TITLE
COVER SHEET

SCALE NO SCALE
DATE 12 NOV. 07
DRAWN BY SAM/MFH
JOB NO. 070901
DRAWING NO. A-0