



ACCESSIBILITY ACCESSORY MOUNTING HEIGHTS

GRAB BARS	33"-36"
TOILET PAPER HOLDER	48" MIN
TOWEL BAR/PAPER TOWEL DISPENSER	48" MAX
BUILT IN PAPER TOWEL DISPENSER	48" MAX
SOAP DISP/DESPENSER AT WALL	48" MAX
SANITARY NAPKIN DISPENSER	48" MAX
SANITARY NAPKIN DISPOSAL	48" MAX
MIRROR (BOTTOM)	40" MAX
SHelves/STORAGE	48" MAX
ELECTRICAL SWITCHES/OUTLETS	48" MAX
COAT HOOKS/RODS	48" MAX
SIGNAGE (TO BRILLE COMPONENT)	60" MAX

- ACCESSIBILITY GENERAL NOTES**
- DOORWAYS SHALL HAVE A MINIMUM CLEAR WIDTH OF 32" WITH THE DOOR OPEN 90 DEGREES MEASURED BETWEEN THE FACE OF THE DOOR AND THE OPPOSITE STOP.
 - ALL DOORS SHALL HAVE LEVER HANDLE HARDWARE, EXCEPT AT SECURED STORAGE ROOMS, MECHANICAL ROOMS, AND ELEVATOR MACHINE ROOMS.
 - ALL CLOSETs SHALL BE 5LD FULL MAXIMUM AT DOORS EQUIPPED WITH LEVER HANDLE HARDWARE.
 - ALL DOORS WITH CLOSETs SHALL HAVE 18" CLEAR DISTANCE FROM THE LATCH SIDE OF THE OPENING TO ANY ADJACENT WALL OR OBSTRUCTION ON THE FULL SIDE OF THE OPENING.
 - ALL DOORS WITH CLOSETs SHALL HAVE 18" CLEAR DISTANCE FROM THE LATCH SIDE OF THE OPENING TO ANY ADJACENT WALL OR OBSTRUCTION ON THE PUSH SIDE OF THE OPENING.
 - ALL SIGNAGE SHALL BE MOUNTED 60" AFF TO BRILLE COMPONENT AT LATCH SIDE WALL OF DOORS AND OPENINGS.