

11 Salem st
#03-1482

57-K-17

Component	Plan Reviewer	Inspection/Date/Findings
Soil type/Presumptive Load Value (Table 401.4.1)	min. 2500 bear c city or struc. fill	
Footing Dimensions/Depth (Table 403.1.1 & 403.1.1(1), Section 403.1.2)	min. 4' below grade 20" x 10" for wall 24" x 24" Interior 1'4" x 12'10" x 12" d col. Ftg	OK
Foundation Drainage Dampproofing (Section 406)	Int/Ext drains - sock wrap Asphalt Dampf.	OK
Ventilation (Section 409.1) Crawls Space ONLY	N/A	
Anchor Bolts/Straps (Section 403.1.4)	ASTM A307 conformity notes 6' O.C.	OK
Lally Column Type, Spacing and footing sizes (Table 502.3.4(2))	3 1/2" Conc. Lally	
Built-Up Wood Center Girder Dimension/Type (Table 502.3.4(2))	3-2x12 w/ ledger 2x4 Bearing walls on Ftg	OK
Sill/Band Joist Type & Dimensions		
Sill/Band Joist Species & Dimensions First Floor Joist Spacing (Table 503.3.1(1) & Table 503.3.2(1))	2x6 PT 2x10 2x10 16 O.C.	OK OK
Second Floor Joist Species Dimensions and Spacing Table(503.3.1(1) & Table 503.3.2(1))	4x2 Floor Trusses 16' O.C.	Boise Cascade Specs OK