



755 Banfield Rd., Portsmouth, NH 03801
Tel. 800-441-8489 - Fax. 603-868-3820

GAZEBO DIMENSIONS and DATA

	Gazebo Size	Floor Rim-Joist Dim's			Overall Height	Area In s.f.	Approx. Weight	Crated Dimensions
		D	F	S				
	8x8	96.7"	89.3"	37"	11ft	45.9sf	950 lbs	8ft L x 8ft W x 46-1/2in H
	10x10	120.2"	111"	46"	11ft 6in	70.9sf	1200 lbs	10ft L x 8ft W x 46-1/2in H
	12x12	143.75"	132.8"	55"	12ft	101.4sf	1600 lbs	12ft L x 8ft W x 46-1/2in H
	14x14	165.9"	153.3"	63.5"	12ft 6in	135.1sf	2200 lbs	10ft L x 8ft W x 60-3/4in H +Floor 14ft L x 8ft W x 15in H
10x14	120.2"	L=163.7"		46"	11ft 6in	107.2sf	1800 lbs	10ft 6in L x 8ft W x 63in H

Roof pitch 5/12, Roof loading 23psf, Floor loading without 4x4's 25psf, Cupolas = 27" across flats, 16-1/4" H

Gazebo Screen Dimensions

Gazebo Size	Screen Location	Screen Size	Qty	Door Size
8' octagonal kit	windows	33" w x 85" h	7	
	door	27.75" w x 68" h	1	31" w x 71.25" h**
	over door	33" w x 12" h	1	
	cupola	*22" octagonal across flats	1	(cupola attached w/ brackets)
10' octagonal kit	windows	42" w x 85" h	7	
	door	37" w x 68" h	1	40" w x 71.25" h**
	over door	42" w x 12" h	1	
	cupola	*22" octagonal across flats	1	(cupola attached w/ brackets)
12' octagonal kit	windows	51" w x 85" h	7	
	door	33" w x 68" h	1	36.25" w x 71.25" h**
	over door	51" w x 12" h	1	
	each side of door	7" w x 72.5" h	2	
	cupola	*22" octagonal across flats	1	(cupola attached w/ brackets)
14' octagonal kit	windows	59.5" w x 85" h	7	
	door	33" x 68" h	1	36.25" w x 71.25" h**
	over door	59.5" w x 12" h	1	
	each side of door	10.75" w x 72.5" h	2	
	cupola	*22" octagonal across flats	1	(cupola attached w/ brackets)
10' x 14' oval kit	windows	42" w x 85" h	9	
	door	37" w x 68" h	1	40" w x 71.25" h**
	over door	42" w x 12" h	1	
	cupola	*22" octagonal across flats	1	(cupola attached w/ brackets)
Door Hardware (all)	pull handle	Onway kit model #R-SDK-1	1	Available at hardware stores
	roller door closer		1	Available at hardware stores
	spring hinges		2-3	Available at hardware stores

Notes: *All new gazebos (2002+) have screening inside the walls of the cupola and no longer use the octagonal screens. Cupolas are attached with small metal brackets and screws.
 **Door height changed from 70-3/4" to 71-1/4" in late 2000. If we ship doors from old stock for after-install screen kit orders, installer may need 1/2" door jamb trim (from office) at top header (placing 1x1 door stop on trim after fitting) to fit the shorter doors in stock. All gazebos adding screen kits after install will need 1"x1" door stops added on top and sides, ordered with door, as well as 8 screen slats.
 Door screens & over-the-door screens are installed using self-tapping screws thru their frame.
 Dimension from bottom of 2x4 to top of decking without 4x4 = 4 3/8 (3 3/8 for 2x4 + 1" for decking)

If you are going to put in Sonotubes, please use [Sonotube-Gazebo Octagonal.doc](#) or [Sonotube-Gazebo Oval10x14.doc](#) for the layout of footings.

All gazebos come from factory with five 4x4's (3 long, 2 short) and nine 2" thick concrete blocks.