

# Protection Professionals

325 US Route 1  
 Falmouth, ME 04105  
 Ph 207-775-5755  
 Fax 207-781-2064

# Device List

No. 5068

List Date
3/7/2013

Bill To Name / Address
Barron Center Attn: Gary Jackson 1145 Brighton Avenue Portland, ME 04102

Job Site
Barron Center, BC-II 1145 Brighton Avenue Portland, ME 04102

**CHANGING THIS DEVICE LIST DOES NOT ALTER THE ORIGINAL ESTIMATE**  
**Attach copy to Purchase Order for accounting**

Estimate No.
#035338

Item	Description	Qty To Order	Qty Ordered
	This quote is to replace the existing fire alarm system as is. None of the chime/strobes will be replaced. All of the smoke detectors inside the rooms as well as the remote stations of Oakdale, Libbytown, Stroudwater, Munjoy, and Deering will be removed and blank covers installed over the boxes.		
	This quote is based upon the fire alarm system location being in the same hallway. This current master box will be replaced with a wireless master box.		
	Fire Alarm System		
FC922-UT	S54400-C20-A1 Fire Alarm System 252 points, 300 watts	1	
FHK2002-R3	Red enclosure kit, two height, for FC922 and FC924	1	
FHA2031-U1	S54400-B44-A1 Din Rail Set	1	
DACT-FCA2015-A1	S54400-A63-A1 DACT for FC922 and FC924	1	
FCI2011-U1	S54400-A54-A1 NAC Module	1	
IK-1007	M101 lock set key, multiple cams	5	
Bat 12-18	Battery	2	
IM-RJ31XSET	IM-RJ31XSET	2	
OOH941	S54320-F7-A2, Dual Optical/Heat Detector over fire panel	1	
OP921	S54320-F4-A2, Optical Smoke Detector	43	
HI921	S54320-F5-A2 Heat detector	3	
DB-11	Detector Base	47	
FDCIO422	4 Input/4 output monitor module (sprinkler, master box, and door holders)	4	
06-SSU00672	Fire Document box 12 inches wide X 13.1 inches high X 2.25 inches deep, CAT 30 keyed	1	
500-648507FA	MANUAL PULL STATION DUAL ACTION KEY RESET CAST METAL	23	
500-034000FA	8701 Mini-Module for Contact Devices (pull stations)	23	
AX-AL1002ULADA	NAC power supply, 10 amps, two Class A and four Class B circuits at 2.5 amps/circuit, 1 amp Aux power	1	
Bat 12-7	12V 7AH Batteries SEC-1075	2	

Ordered By: \_\_\_\_\_

Date: \_\_\_\_\_

Received By: \_\_\_\_\_

Date: \_\_\_\_\_

# Protection Professionals

325 US Route 1  
 Falmouth, ME 04105  
 Ph 207-775-5755  
 Fax 207-781-2064

# Device List

No. 5068

List Date
3/7/2013

Bill To Name / Address
Barron Center Attn: Gary Jackson 1145 Brighton Avenue Portland, ME 04102

Job Site
Barron Center, BC-II 1145 Brighton Avenue Portland, ME 04102

**CHANGING THIS DEVICE LIST DOES NOT ALTER THE ORIGINAL ESTIMATE**  
**Attach copy to Purchase Order for accounting**

Estimate No.
#035338

Item	Description	Qty To Order	Qty Ordered
FDBZ492-HR	S54319-B23-A1 Duct detector with relay	1	
OOH941	S54320-F8-A2, Dual Optical/Heat Detector	1	
ST-25	500-649711 2.5 foot sampling tube	1	
FDBZ-RTL	S54319-S27-A1, Remote test station for duct detectors	1	
7788F	Wireless fire subscriber for City of Portland	1	
1640	16.5 Volt AC 40 VA Class 2 Transformer	1	
Bat 12-7	12V 7AH Batteries SEC-1075	1	
Misc Non-Inventory ...	Remote antenna	1	
GI-TSW01S	Tamper Switch for master boxes	1	
Misc Inventory Materi...	Bypass switch	1	
D8004	UL TRANSFORMER KIT	1	
	Add 6 strobes, one in whirlpool room, one in bathroom by whirlpool, and one in shower by whirlpool, one in shower by Deering, and bathrooms across from 103 & 104.		
500-636169	ZR-MC-R Strobe only, red, wall mount, 15cd, 30cd, 75cd, or 110cd	6	
	Add one remote annunciator at Nurse's station at Main Entry		
FT2015-R3	S54400-B16-A1, Remote annunciator, red, with key	1	
FCA2016-A1	S54400-A39-A1: RS 485 module for annunciator	1	
	Add two horn/strobes to utility rooms in lower area; one below Deering and one below Stroudwater		
500-636161	ZH-MC-R Horn/strobe, red, wall mount, Hi or Lo volume, 15cd, 30cd, 75cd, or 110cd	2	

Ordered By: \_\_\_\_\_

Date: \_\_\_\_\_

Received By: \_\_\_\_\_

Date: \_\_\_\_\_