10 THIRD FLOOR PART PLAN D
SCALE: 1/4" = 1'-0"

KEY NOTES:

1. REPLACE LIGHT FIXTURES IN KITCHEN, BATHROOM, PANTRY, COMMON CORRIDORS, STAIRWAYS, AND EXTERIOR. VERIFY QUANTITY AND LOCATIONS IN FIELD.
2. PROVIDE NEW GFI RECEPTACLES IN EXISTING LOCATIONS IN KITCHENS AND BATHROOMS, WITH NEW COVERPLATE.
3. PROVIDE NEW HARD WIRED SMOKE ALARM WITH BATTERY BACKUP IN EXISTING LOCATION IN APARTMENT LIVING AREA. CONNECT TO EXISTING WIRING.
4. PROVIDE NEW HARDWIRED, INTERCONNECTED COMBINATION SMOKE/CARBON MONOXIDE ALARM WITH BATTERY BACK UP IN APARTMENT BEDROOMS. WIRE TO EXISTING SMOKE ALARM
5. PROVIDE NEW E-CALL PULL STATION DEVICES AT EXISTING LOCATIONS IN APARTMENT BATHROOMS, BEDROOMS, AND LIVING AREAS. PROVIDE NEW DOME LIGHT IN CORRIDOR OUTSIDE UNIT. CONNECT TO EXISTING WIRING. VERIFY LOCATIONS IN FIELD.
6. OMITTED 12/10/15
7. RELOCATE EXISTING RECEPTACLES TO NO LESS THAN 16" ABOVE FLOOR AND SWITCHES TO NO LOWER THAN 48" ABOVE FLOOR IN HANDICAP APARTMENTS. VERIFY LOCATIONS AND QUANTITY IN FIELD.
8. PROVIDE J-BOX ABOVE RANGE AND SWITCHES ON FRONT OF BASE CABINET FOR RANGE HOOD FAN AND LIGHT IN HANDICAP APARTMENTS.
9. PROVIDE NEW GFI RECEPTACLES IN NEW LOCATIONS IN KITCHENS AND BATHROOMS IN HANDICAP APARTMENTS.
10. PROVIDE HARD WIRED COMBINATION SMOKE/CARBON MONOXIDE ALARM IN BEDROOM AND HARDWIRED INTERCONNECTED SMOKE ALARM IN LIVING AREA OF HANDICAP UNITS.
11. PROVIDE NEW RANGE RECEPTACLE AND REFRIGERATOR RECEPTACLE IN NEW LOCATIONS IN HANDICAP UNITS.
12. PROVIDE NEW ELECTRICAL PANELS AT 48" TO HIGHEST BREAKER IN HP ACCESSIBLE APARTMENTS. PROVIDE NEW CIRCUIT WIRING TO NEW DEVICES AS SHOWN.
13. **HEARING IMPAIRED UNITS SCOPE NOTE:**
    IN ALL ELEVEN ACCESSIBLE UNITS AND THREE TYPICAL APARTMENTS (SEE ARCHITECTURAL PLANS FOR LOCATIONS) APPLY THE FOLLOWING SCOPE OF WORK FOR HEARING AND VISUALLY IMPAIRED:
    1. PROVIDE STROBE IN BEDROOM INTERCONNECTED WITH SMOKE ALARMS.
    2. PROVIDE STROBE IN BATHROOM INTERCONNECTED WITH SMOKE ALARMS.
    3. PROVIDE STROBE IN LIVING AREA INTERCONNECTED WITH SMOKE ALARMS.
    4. PROVIDE DOORBELL WITH DOORBELL STROBE IN LIVING AREA AND BEDROOM.
    5. PROVIDE STROBE IN LIVING AREA, BEDROOM, AND BATHROOM CONNECTED TO THE CENTRAL BUILDING FIRE ALARM SYSTEM.
14. PROVIDE NEW 208V/3P/50A CIRCUIT FROM EXISTING PANEL # 2 OR PANEL # 3 IN SECOND FLOOR CORRIDOR TO NEW MAKE UP AIR UNIT ON ROOF. PROVIDE NEW # 6 CONDUCTORS WITH A # 10 GROUND IN NEW 3/4" C FROM NEW 50A CIRCUIT BREAKER IN PANEL TO FACTORY INSTALLED DISCONNECT ON MAKE UP AIR UNIT. EXISTING CIRCUITS TO EXISTING AIR HANDLING UNIT ABOVE CEILING OF APARTMENT 223 SHALL BE ABANDONED AND/OR REUSED FOR NEW EQUIPMENT. VERIFY PANEL LOCATION, PANEL CAPACITY, AND EXISTING CIRCUIT IN FIELD.

Reviewed for Code Compliance
Inspectional Services Division
Approved with Conditions
Date: 06/10/16

tat
the architectural team

The Architectural Team, Inc.
50 Commandant's Way at Admiral's Hill
Chelsea MA 02150
T 617.889.4402
F 617.884.4329
www.architecturalteam.com
©2011 The Architectural Team, Inc.

Consultant:

Richard Melling, PE
MEP DESIGN CONSULTANT
8824 Gotherstone Ct.
Raleigh, NC 27615
email: rmelling@mellingengineering.com

Revision:
11/25/15
12/10/15

Engineer of Record:

STATE OF MAINE
RICHARD A MELLING
13940
LICENSED
PROFESSIONAL ENGINEER
11/25/15

Drawn: RM
Checked: RM
Scale: 1/4" = 1'-0"
Key Plan:

Project Name:
LORING HOUSE

1125 Brighton Avenue
Portland, ME 04102

Sheet Name:
Part Plan D
Third Floor

Project Number:
14165

Issue Date:
October 19, 2015

Sheet Number:
E2.03d

Friday, December 11, 2015 1:24:46 PM
Z:\2015\15012 - Loring House\E2\03R2.dwg