KEY NOTES:

1. REPLACE LIGHT FIXTURES IN KITCHEN, BATHROOM, PANTRY, AND COMMON CORRIDORS. VERIFY QUANTITY AND LOCATIONS IN FIELD.
2. PROVIDE NEW GFI RECEPTACLES IN EXISTING LOCATIONS IN KITCHENS AND BATHROOMS, WITH NEW COVERPLATE.
3. PROVIDE NEW HARD WIRED SMOKE ALARM WITH BATTERY BACKUP IN EXISTING LOCATION IN APARTMENT LIVING AREA. CONNECT TO EXISTING WIRING.
4. PROVIDE NEW HARDWIRED, INTERCONNECTED, COMBINATION SMOKE/CARBON MONOXIDE ALARM WITH BATTERY BACKUP IN APARTMENT BEDROOMS. WIRE TO EXISTING SMOKE ALARMS.
5. PROVIDE NEW E-CALL PULL STATION DEVICES AT EXISTING LOCATIONS IN APARTMENT BATHROOMS, BEDROOMS, AND LIVING AREAS. PROVIDE NEW DOME LIGHT IN CORRIDOR OUTSIDE UNIT. CONNECT TO EXISTING WIRING. VERIFY LOCATIONS IN FIELD.
6. PROVIDE ONE NEW 208V/1P/20A CIRCUIT FROM EXISTING PANEL #4 IN UTILITY ROOM #18 ON SECOND FLOOR TO SERVE ALL SEVEN NEW AIR HANDLING UNITS IN CORRIDORS OF ALL FLOORS ON THIS WING. PROVIDE MOTOR RATED SWITCH FOR LOCAL DISCONNECT AT EACH AIR HANDLER. COORDINATE WITH M.C.

ELECTRICAL SYMBOLS

	WALL SWITCH
SM	SMOKE ALARM
SC	COMBINATION SMOKE AND CARBON MONOXIDE ALARM
	30 CD SMOKE ALARM STROBE
	DOORBELL STROBE
	DOORBELL
	ELECTRICAL PANEL
WP/GFI	WEATHERPROOF/GFCI RECEPTACLE
GFI	GFCI RECEPTACLE
	120V RECEPTACLE
	240V RECEPTACLE
	CABLE TV OUTLET
	EXHAUST FAN
	E-CALL STATION

Reviewed for Code Compliance
Inspection Division
Approved with Conditions
Date: 06/10/16

tat
the architectural team

The Architectural Team, Inc.
50 Commandant's Way at Admiral's Hill
Chelsea MA 02150
T 617.889.4402
F 617.884.4329
www.architecturalteam.com
©2011 The Architectural Team, Inc.

Consultant:

Richard Melling, PE
MEP DESIGN CONSULTANT
8824 Gotherstone Ct.
Raleigh, NC 27615
email: rmelling@mellingengineering.com

Revision:

- 11/25/15
- 12/10/15
- 1/6/16

Engineer of Record:

STATE OF MAINE
RICHARD A MELLING
13940
LICENSED
PROFESSIONAL ENGINEER

11/25/15

Drawn: RM
Checked: RM
Scale: 1/4" = 1'-0"
Key Plan:

Project Name:
LORING HOUSE

1125 Brighton Avenue
Portland, ME 04102

Sheet Name:
Part Plan A
Fourth Floor

Project Number:
14165

Issue Date:
October 19, 2015

Sheet Number:
E2.04a

Thursday, January 07, 2016 2:51:54 PM
Z:\2015\15012 - Loring House\E204R3.dwg