



- ### NOTES
- Anchor Bolt size, location, length and other requirements shall be indicated in detail and shall be indicated in detail and shall be indicated in detail.
 - Concrete shall not be placed until it has been inspected by the independent agency retained by the owner.
 - See Drawing S10 for additional notes and requirements.
 - Provide temporary support and shoring, as necessary to prevent undermining of existing structure.
 - Footing shall be on plain with 1" shall have #4 @ 12" reinforcing each way at top of footing.
 - Footing shall be based on data provided by Mason in Drawing 1 of 4 dated October 14, 2004, entitled, "Anchor Bolt Plan and Details". If there are any changes to this information, the foundation plan must be updated by the Structural Engineers, Inc. to verify that the footing sizes are compatible with the proposed loads.
 - Top of concrete foundation wall at door openings at locations where no concrete walls exist shall be 11,700 (unless otherwise noted on Architectural Drawings).
 - See S10, S20, and S21 for required special details.
 - Locate Pier P1 centerline at 1' from corner where shown (UON).

ISSUED FOR PERMIT ONLY
PRELIMINARY
NOT FOR CONSTRUCTION

UNDER NO CIRCUMSTANCES SHALL THIS DRAWING BE USED TO DEVELOP SHOP DRAWINGS OR FABRICATE NEW MATERIALS. SHOP DRAWINGS PREPARED USING THIS DRAWING WILL BE REJECTED WITHOUT REVIEW.

CWS Architects
 Architecture
 Space Planning
 Value Design
 431 Commercial Avenue
 Portland, ME 04101
 Phone: (207) 774-4444
 Fax: (207) 774-4116
 www.CWSArch.com

R. P. ROSS
 REGISTERED PROFESSIONAL ENGINEER
 FROZEN ROPES SPORTS CENTER
 ISSUED FOR PERMIT
 OCTOBER 22, 2004

DESTERANO AND ASSOCIATES, INC.
 2158 Lafayette Road
 Portland, ME 02801
 603.430.3239

Drawing Title: **FOUNDATION PLAN AND DETAILS**
 Scale: As noted
 Date: 10/22/04
 POC Project No.: 08104
 Designer: [Signature]

Drawing Number: **S2.0**