

263 Main Rd Portiano

Sandra McDonald

Material:

- Rim Joist 2x8x8 PT
- Ledger 2x10x8 PT
- Joist 2x8x8
- Corner supports 4x4 PT
- Joist hangers 2x8
- Footings - Frost piers
- Footings base anchor plates
- Decking 5/4 composite
- Railing - Composite Rail System
- 6" Ledger lock screws

Stairs: Rise 7"
Run 10"

Estimated cost \$2,560.-

nails

