

**City of Portland, Maine – Building or Use Permit Application** 389 Congress Street, 04101, Tel: (207) 874-8703, FAX: 874-8716

Location of Construction: 145 Taft Ave		Owner: Mary A. McLaughlin		Phone:		Permit No: 971201	
Owner Address: 145 Taft Ave.		Lessee/Buyer's Name:		Phone:		Business Name:	
Contractor Name: Thompson's Remodeling		Address: 317 Brown St., Westbrook, ME 04092		Phone: 207-854-4514		Permit Issued: <b>PERMIT ISSUED</b> NOV - 6 1997	
Past Use: single-family dwelling		Proposed Use: same w/ second floor addition		COST OF WORK: \$ 13,800		PERMIT FEE: \$ 90.00	
Proposed Project Description: 1 construction of second floor		FIRE DEPT. <input type="checkbox"/> Approved <input type="checkbox"/> Denied		INSPECTION: Use Group R3 Type 5B BOCA 96		Zone: CBL: R-3 273-PLAND4	
		Signature:		Signature: [Signature]		Zoning Approval: Special Zone or Reviews: <input type="checkbox"/> Shoreland <input type="checkbox"/> Wetland <input type="checkbox"/> Flood Zone <input type="checkbox"/> Subdivision <input type="checkbox"/> Site Plan maj <input type="checkbox"/> minor <input type="checkbox"/> mm <input type="checkbox"/>	
Permit Taken By: Meg Hall		Date Applied For: October 27, 1997		PEDESTRIAN ACTIVITIES DISTRICT (P.A.D.) Action: <input type="checkbox"/> Approved <input type="checkbox"/> Approved with Conditions <input type="checkbox"/> Denied		Signature: _____ Date: _____	

1. This permit application does not preclude the Applicant(s) from meeting applicable State and Federal rules.
2. Building permits do not include plumbing, septic or electrical work.
3. Building permits are void if work is not started within six (6) months of the date of issuance. False information may invalidate a building permit and stop all work..

call at 761-4429 when ready

273-E-1

**CERTIFICATION**

I hereby certify that I am the owner of record of the named property, or that the proposed work is authorized by the owner of record and that I have been authorized by the owner to make this application as his authorized agent and I agree to conform to all applicable laws of this jurisdiction. In addition, if a permit for work described in the application is issued, I certify that the code official's authorized representative shall have the authority to enter all areas covered by such permit at any reasonable hour to enforce the provisions of the code(s) applicable to such permit

Signature of Applicant: *[Signature]* ADDRESS: 145 Taft Ave DATE: 10/27/97 PHONE: 761-4429

RESPONSIBLE PERSON IN CHARGE OF WORK, TITLE PHONE:

CEO DISTRICT **4**

**City of Portland, Maine - Building or Use Permit Application 389 Congress Street, 04101, Tel: (207) 874-8703, FAX: 874-8716**

Location of Construction: 145 Taft Ave Owner: Mary A. McLaughlin Phone: \_\_\_\_\_

Owner Address: 145 Taft Ave. Lessee/Buyer's Name: \_\_\_\_\_ Phone: \_\_\_\_\_ Business Name: \_\_\_\_\_

Contractor Name: Thompson's Remodeling Address: 317 Bryn St., Westbrook, ME Phone: 207-854-4514

Past Use: single-family dwelling Proposed Use: same w/ second floor addition

Proposed Project Description: 1 construction of second floor

Permit Taken By: Meg Hall Date Applied For: October 27, 1997

Signature: \_\_\_\_\_ PEDESTRIAN ACTIVITIES DISTRICT (P.A.D.)  
 Action:  Approved  Denied  
 Approved with Conditions:  Denied

1. This permit application does not preclude the Applicant(s) from meeting applicable State and Federal rules.  
 2. Building permits do not include plumbing, septic or electrical work.  
 3. Building permits are void if work is not started within six (6) months of the date of issuance. False information may invalidate a building permit and stop all work.

call at 761-4429 when ready

**CERTIFICATION**

I hereby certify that I am the owner of record of the named property, or that the proposed work is authorized by the owner of record and that I have been authorized by the owner to make this application as his authorized agent and I agree to conform to all applicable laws of this jurisdiction. In addition, if a permit for work described in the application is issued, I certify that the code official's authorized representative shall have the authority to enter all areas covered by such permit at any reasonable hour to enforce the provisions of the code(s) applicable to such permit

Signature of Applicant: [Signature] Address: 145 Taft Ave Date: 10/27/97 Phone: 761-9923

RESPONSIBLE PERSON IN CHARGE OF WORK, TITLE \_\_\_\_\_ PHONE: \_\_\_\_\_

Permit No. **971201**

Permit Issued: **NOV - 6 1997**

Zone: CB-1 PORTLAND  
 Zoning Approval: [Signature]  
 Special Zone or Reviews: 10/31/97

Variance  
 Miscellaneous  
 Conditional Use  
 Interpretation  
 Approved  
 Denied

Historic Preservation  
 Not In District or Landmark  
 Does Not Require Review  
 Requires Review

Action:

Approved  
 Approved with Conditions  
 Denied

Date: 10/28/97

[Signature]

CEO DISTRICT **4**

COMMENTS

NOT NOTIFIED OF INSPECTION.

9-24-95  
Kedney  
Shed is all complete, smooth exterior w/ a  
Kedney

Inspection Record

Type

Date

Foundation: \_\_\_\_\_

Framing: \_\_\_\_\_

Plumbing: \_\_\_\_\_

Final: \_\_\_\_\_

Other: \_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

# BUILDING PERMIT REPORT

DATE: 4/Nov/97 ADDRESS: 145 Taft Ave.

REASON FOR PERMIT: To Construct a second floor addition.

BUILDING OWNER: Mary A. McLaughlin

CONTRACTOR: Thompson's Remodeling

PERMIT APPLICANT: \_\_\_\_\_ APPROVAL: \*1,\*2,\*3,\*4,\*5,\*6,\*7,\*8,\*9,\*10,\*11,\*12,\*16,\*26,\*28 \*29,\*30,\*31,\*32


USE GROUP R-3 BOCA 1996 CONSTRUCTION TYPE 5-B

## CONDITION(S) OF APPROVAL

- \*1. This permit does not excuse the applicant from meeting applicable State and Federal rules and laws.
- \*2. Before concrete for foundation is placed, approvals from the Development Review Coordinator and Inspection Services must be obtained. (A 24 hour notice is required prior to inspection)
3. Precaution must be taken to protect concrete from freezing.
4. It is strongly recommended that a registered land surveyor check all foundation forms before concrete is placed. This is done to verify that the proper setbacks are maintained.
5. Private garages located beneath habitable rooms in occupancies in Use Group R-1, R-2, R-3 or I-1 shall be separated from adjacent interior spaces by fire partitions and floor/ceiling assembly which are constructed with not less than 1-hour fire resisting rating. Private garages attached side-by-side to rooms in the above occupancies shall be completely separated from the interior spaces and the attic area by means of ½ inch gypsum board or the equivalent applied to the garage means of ½ inch gypsum board or the equivalent applied to the garage side. (Chapter 4 Section 407.0 of the BOCA/1996)
- \*6. All chimneys and vents shall be installed and maintained as per Chapter 12 of the City's Mechanical Code. (The BOCA National Mechanical Code/1993).
7. Sound transmission control in residential building shall be done in accordance with Chapter 12 section 1214.0 of the city's building code.
- \*8. Guardrails & Handrails: A guardrail system is a system of building components located near the open sides of elevated walking surfaces for the purpose of minimizing the possibility of an accidental fall from the walking surface to the lower level. Minimum height all Use Groups 42", except Use Group R which is 36". In occupancies in Use Group A, B, H-4, I-1, I-2 M and R and public garages and open parking structures, open guards shall have balusters or be of solid material such that a sphere with a diameter of 4" cannot pass through any opening. Guards shall not have an ornamental pattern that would provide a ladder effect. (Handrails shall be a minimum of 34" but not more than 38". Use Group R-3 shall not be less than 30", but not more than 38".)
- \*9. Headroom in habitable space is a minimum of 7'6".
- \*10. Stair construction in Use Group R-3 & R-4 is a minimum of 10" tread and 7 3/4" maximum rise. All other Use group minimum 11" tread, 7" maximum rise.
- \*11. The minimum headroom in all parts of a stairway shall not be less than 80 inches. (6' 8")
- \*12. Every sleeping room below the fourth story in buildings of use Groups R and I-1 shall have at least one operable window or exterior door approved for emergency egress or rescue. The units must be operable from the inside without the use of special knowledge or separate tools. Where windows are provided as means of egress or rescue they shall have a sill height not more than 44 inches (1118mm) above the floor. All egress or rescue windows from sleeping rooms shall have a minimum net clear opening height dimension of 24 inches (610mm). The minimum net clear opening width dimension shall be 20 inches (508mm), and a minimum net clear opening of 5.7 sq. ft.
13. Each apartment shall have access to two (2) separate, remote and approved means of egress. A single exit is acceptable when it exits directly from the apartment to the building exterior with no communications to other apartment units.
14. All vertical openings shall be enclosed with construction having a fire rating of at least one (1) hour, including fire doors with self closer's.
15. The boiler shall be protected by enclosing with (1) hour fire-rated construction including fire doors and ceiling, or by providing automatic extinguishment.
- \*16. All single and multiple station smoke detectors shall be of an approved type and shall be installed in accordance with the provisions of the City's Building Code Chapter 9, Section 19, 920.3.2 (BOCA National Building Code/1996), and NFPA 101 Chapter 18 & 19. (Smoke detectors shall be installed and maintained at the following locations):
  - In the immediate vicinity of bedrooms
  - In all bedrooms

• In each story within a dwelling unit, including basements  
In addition to the required AC primary power source, required smoke detectors in occupancies in Use Groups R-2, R-3 and I-1 shall receive power from a battery when the AC primary power source is interrupted. (Interconnection is required)

- 17. A portable fire extinguisher shall be located as per NFPA #10. They shall bear the label of an approved agency and be of an approved type.
- 18. The Fire Alarm System shall be maintained to NFPA #72 Standard.
- 19. The Sprinkler System shall maintained to NFPA #13 Standard.
- 20. All exit signs, lights, and means of egress lighting shall be done in accordance with Chapter 10 Section & Subsections 1023. & 1024. Of the City's building code. (The BOCA National Building Code/1996)
- 21. No construction or demolition work shall begin until you have obtained permits for dumpsters or containers. A work Stop Order shall be issued if this requirement is not met.
- 22. Section 25-135 of the Municipal Code for the City of Portland states, "No person or utility shall be granted a permit to excavate or open any street or sidewalk from the time of November 15 of each year to April 15 of the following year".
- 23. The builder of a facility to which Section 4594-C of the Maine State Human Rights Act Title 5 MRSA refers, shall obtain a certification from a design professional that the plans commencing construction of the facility, the builder shall submit the certification to the Division of Inspection Services.
- 24. This permit does not excuse the applicant from obtaining any license which may be needed from the City Clerk's office.
- 25. Ventilation shall meet the requirements of Chapter 12 Sections 1210. of the City's Building Code.
- \* 26. All electrical, plumbing and HVAC permits must be obtained by a Master Licensed holders of their trade.
- 27. All requirements must be met before a final Certificate of Occupancy is issued.
- \* 28. All building elements shall meet the fastening schedule as per Table 2305.2 of the City's Building Code. (The BOCA National Building Code/1996).
- \* 29. Ventilation of spaces within a building shall be done in accordance with the City's Mechanical Code (The BOCA National Mechanical Code/1993).
- \* 30. *The proposed 2x8" floor joists has a maximum allowable span of 10'*
- \* 31. *The proposed 2x6" Ceiling joists has a maximum allowable span of 12'*
- \* 32. *This building is to remain a single family dwelling.*
- 33. \_\_\_\_\_
- 34. \_\_\_\_\_

  
P. Samuel Hoffses, Code Enforcement

cc: Lt. McDougall, PFD  
Marge Schumuckal

building materials		quantity
2x8x16	floor joists	64
2x6x12	ceiling joists	
2x8x8	floor joists	
2x6x8	exterior walls	
exterior plywood 1/2"	lateral	34
shingles	Roofing of Supreme Sect.	
2x4x8	interior walls	
	sub floor	
	insulation - wall & roof	
	drywall	
	interior doors	
	windows	
	stair	
	tread&riser	
	electrical	
	heating	
	plumbing	
tyvec	barrier	
tar paper	barrier	
roof vent		

DEPT. OF BUILDING INSPECTION  
CITY OF PORTLAND, ME  
OCT 27 1997  
RECEIVED

Applicant:

Date: 10/31/97

Address: 145 TAFT AVE

C-B-L: 273-E-1464

CHECK-LIST AGAINST ZONING ORDINANCE

Date - Existing 1980

Zone Location - R-3

Interior or corner lot - 19-25 Dale St

Proposed Use/Work - Construct Dammer Addition - Make Renovations

Sewage Disposal - City

Lot Street Frontage -

Front Yard - 25' req - 35' shown

Rear Yard - 25' req 50' shown

Side Yard - 20' on side st - 35' shown  
14' req - 30' 48" shown

Projections -

Width of Lot -

Height -

Lot Area - 11,175

Lot Coverage/ Impervious Surface -

Area per Family -

Off-street Parking - 24 x 40

Loading Bays - 8 x 16

Site Plan -

Shoreland Zoning/ Stream Protection - N/A

Flood Plains - N/A

to remain  
1 Family