

Specifications

Advantage Oil Boiler Model #	No. Sections	DOE Heating Capacity (btu/hr)	IBR Net Rating (btu/hr)	Burner Capacity GPH	AFUE (%)	Tankless Heater GPM	Chimney Size In. x In. x Ft.	Dimension (Inches)		Flue Collar Diameter (Inches)	Shipping Weight (Approx.)
								A	B		
A-03	3	80,000	70,000	0.65	86.1*	2.75	8 x 8 x 15	16-1/2	8-1/4	6	560
A-03	3	91,000	79,000	0.75	85.8*	3	8 x 8 x 15	16-1/2	8-1/4	6	560
A-03	3	120,000	104,000	1.00	84.3	3.25	8 x 8 x 15	16-1/2	8-1/4	6	560
A-04	4	152,000	132,000	1.25	85.1*	3.75	8 x 8 x 15	21-1/2	10-3/4	7	680
A-04	4	179,000	156,000	1.50	84	4	8 x 8 x 15	21-1/2	10-3/4	7	680
A-05	5	210,000	183,000	1.75	85.1*	4.25	8 x 8 x 15	26-1/2	13-1/4	8	800
A-05	5	238,000	207,000	2.00	84.7	4.75	8 x 8 x 15	26-1/2	13-1/4	8	800

Burner Part Numbers

Mfr. #	Description
104095-01	Beckett AFG - 3 Section Burner
104096-01	Beckett AFG - 4 Section Burner
104097-01	Beckett AFG - 5 Section Burner

*Energy Star qualified



1. Specifications and dimensions are subject to change without notice.
2. Consult factory if unusual piping or pickup requirements exist.
3. The Net I=B=R Water Ratings shown are based on a piping and pickup allowance of 1.15.
4. Firing rate in GPH based on having a heat value of 140,000 BTU/GAL

