

Foundation - Re-use of existing concrete Sauna tubes 10"
Spaced 9' apart - Tubes to be 4' Below Grade
Column to be anchored with Simpson Post base and
1/2" concrete bolts

Columns - 6x6 Pressure treated lumber anchored
with Simpson post base & bolts

Framing - all Pressure treated lumber

~~2x10~~ 2x8 ledger
2x8 Joists - 10' span 2' overhang
2-2x10 Beam - 9' span 1' overhang
2- 1/2" Lag bolts 16" OC between ledger & house
ledger is existing - copper flashing
Joist hangers to be used on ledger board
5/4 x 6 PT Decking

Guardrails - 36" height
4" Baulister spacing

Stairs - 7-7/4 Rise
1" nosing
10" Tread
42" Width