

Client: Jen & James Fields
 326 Cudlow St.
 Portland, ME 04102
 #442-0201

Builder: Mrs. Woodwells / Mark D'Alto
 101 Allison Rd
 Windham, ME 04092
 #318-2209

Existing House

Existing Steps
 Garage Roof
 Overhang.

4 3 2 1

- Framing: 2x10 (PT)
- Carrying Beam: 2x8 (PT)
- Posts: 4x4 (PT)
- Decking: 5/4 or Cedar.
- Treads: 4" x 4"
- Elevation: 18" +/- (Raining not needed)
- Fasteners: Framing: 16 pen. Hot dip Galv nails
 Joist Hangers: 10 pen. Hot dip Galv nails
 Decking to Frame: Decking Screws
 Ledger to House: 2 Lag Bolts 2 1/2"
- Spans: Not needed as deck is tying into existing steps.
- Septic/Backflow: Only on front side of house.

