



- GENERAL REMOVALS NOTES**
- 1 REMOVE EXISTING BOLLARD ASSEMBLY COMPLETE. PATCH AND REPAIR FLOOR AS REQUIRED TO MATCH EXISTING.
 - 2 REMOVE EXISTING MASONRY WALL ASSEMBLY WITHIN LIMITS SHOWN AND PREPARE OPENING FOR INSTALLATION OF NEW PAIR OF INSULATED HOLLOW METAL DOORS AND DOOR FRAME ASSEMBLY. PROVIDE GALVANIZED STEEL LIMITS AT HEAD CONDITION.
 - 3 REMOVE EXISTING ROLL-UP DOOR ASSEMBLY COMPLETE. REPAIR EXISTING OVERHEAD DOOR ASSEMBLY COMPLETE. PREPARE OPENING AS REQUIRED FOR INSTALLATION OF NEW EXTERIOR WALL ASSEMBLY.
 - 4 REMOVE EXISTING STEEL POST COMPLETE. PATCH AND REPAIR FLOOR AS REQUIRED TO MATCH EXISTING.
 - 5 REMOVE EXISTING WINDOW ASSEMBLY COMPLETE. REMOVE EXISTING MASONRY WALL ASSEMBLY COMPLETE BELOW EXISTING WINDOW. PREPARE OPENING FOR INSTALLATION OF NEW DOOR AND DOOR FRAME ASSEMBLY.
 - 6 REMOVE EXISTING DOOR AND DOOR FRAME ASSEMBLY COMPLETE. INFILL OPENING TO MATCH EXISTING.
 - 7 REMOVE EXISTING DOOR AND DOOR FRAME ASSEMBLY COMPLETE.
 - 8 REMOVE EXISTING WALL ASSEMBLY COMPLETE WITHIN LIMITS SHOWN.
 - 9 REMOVE EXISTING COUNTER/CASEWORK ASSEMBLY COMPLETE. REMOVE EXISTING FINISH FLOORING COMPLETE. PREPARE SUBFLOOR FOR NEW FLOOR FINISHES AS RECOMMENDED BY FLOOR MANUFACTURER. REFERENCE ROOM FINISH SCHEDULE FOR MORE INFORMATION.
 - 10 REMOVE EXISTING TOILET PARTITION ASSEMBLY COMPLETE.
 - 11 REMOVE EXISTING WINDOW ASSEMBLY COMPLETE.
 - 12 REMOVE EXISTING PLUMBING FIXTURE AND ASSOCIATED PIPING COMPLETE.
 - 13 REMOVE EXISTING SHELVING COMPLETE.
 - 14 PREPARE/CLEAN EXISTING CMU WALL ASSEMBLY FOR NEW PAINT APPLICATIONS PER PAINT MANUFACTURER'S RECOMMENDATIONS.
 - 15 REMOVE ALL EXISTING ACOUSTICAL CEILING TILES COMPLETE. SALVAGE TILES IN GOOD CONDITION AND HOLD FOR REINSTALLATION IN NEW CEILING LAYOUT.
 - 16 REMOVE AND SALVAGE ALL EXISTING LIGHTING FIXTURES COMPLETE. REPAIR OR REPLACE ALL BULBS, BALLASTS, ETC. AS REQUIRED TO ENSURE PROPER FUNCTIONALITY. PROVIDE MATCHING FIXTURES IF/WHERE REQUIRED.
 - 17 REMOVE EXISTING ACOUSTICAL CEILING TILE GRID SYSTEM COMPLETE.
 - 18 TEMPORARILY RELOCATE EXISTING FIRE EXTINGUISHER UNTIL NEW WALL FURNISH IS INSTALLED. MOUNT EXISTING FIRE EXTINGUISHER ON NEW FURNISH.
 - 19 REMOVE EXISTING ACUSTICAL CEILING TILE GRID SYSTEM COMPLETE.
 - 20

Drawing Title:
ENLARGED REMOVALS FLOOR PLAN

Scale:
3/8" = 1'-0"

Date:
September 20 2006

CNS Proj. No.:
06491Add

Revision	Description	Date

Owner:
HAPPY TAILS DOG CENTER
119 BEAVER STREET
PORTLAND, MAINE 04105

207-450-0924

CWS Architects

434 Cumberland Avenue
Portland, ME 04101
Phone: (207) 774-4441
Fax: (207) 774-4016
www.CWSarch.com

Drawing Number:
DA1.2