

DISPLAY THIS CARD ON PRINCIPAL FRONTAGE OF WORK



CITY OF PORTLAND BUILDING PERMIT



This is to certify that
BISHOP HOLDINGS LLC

Located at
17 BISHOP ST

PERMIT ID: 2018-00301 ISSUE DATE: 07/25/2018 CBL: 293 A016001

has permission to **Install commercial hood for kitchen.**

provided that the person or persons, firm or corporation accepting this permit shall comply with all of the provisions of the Statutes of Maine and of the Ordinances of the City of Portland regulating the construction, maintenance and use of the buildings and structures, and of the application on file in the department.

Notification of inspection and written permission procured before this building or part thereof is lathed or otherwise closed-in. 48 hour notice is required.	A final inspection must be completed before this building or part thereof is occupied. If a certificate of occupancy is required, it must be procured prior to occupancy.
---	---

/s/ Chris Pirone

/s/ Michael Russell, MS, Director

Fire Official

Building Official

**THIS CARD MUST BE POSTED ON THE STREET SIDE OF THE PROPERTY
THERE IS A PENALTY FOR REMOVING THIS CARD**

Approved Property Use - Zoning

Building Inspections

Fire Department

BUILDING PERMIT INSPECTION PROCEDURES
Please call 874-8703
or email: buildinginspections@portlandmaine.gov

**Check the Status of Permit or Schedule an Inspection at
<http://www.portlandmaine.gov/planning/permitstatus.asp>**

With the issuance of this permit, the owner, builder or their designee is required to provide adequate notice to the City of Portland Inspections Division for the inspections listed below. Appointments must be requested 48 to 72 hours in advance. The inspection date will need to be confirmed by this office.

- **Please read the conditions of approval that are attached to this permit.**
- **Permits expire in 6 months if the project is not started or ceases for 6 months.**
- **If the inspection requirements below are not followed, then additional fees may be incurred due to the issuance of a "Stop Work Order" and subsequent release to continue.**
- **Per Section 107.3.1 of the Maine Uniform Building and Energy Code (MUBEC), one set of printed approved stamped construction documents will be kept at the site of work and open to inspection by building officials.**

REQUIRED INSPECTIONS:

Final - Fire

The project cannot move to the next phase prior to the required inspection and approval to continue.

If the permit requires a certificate of occupancy, it must be paid and issued to the owner or designee before the space may be occupied.

City of Portland, Maine - Building or Use Permit		Permit No: 2018-00301	Date Applied For: 03/07/2018	CBL: 293 A016001
389 Congress Street, 04101 Tel: (207) 874-8703, Fax: (207) 874-8716				
Proposed Use: Same. Intermediate care residential facility on first floor and day program/offices on second floor.		Proposed Project Description: Install commercial hood for kitchen.		
Dept: Fire	Status: Approved w/Conditions	Reviewer: Chris Pirone	Approval Date: 06/04/2018	
Note:				Ok to Issue: <input checked="" type="checkbox"/>
Conditions:				
<p>1) All construction shall comply with City Code Chapter 10. http://www.portlandmaine.gov/citycode/chapter010.pdf Installation shall comply with City Code Chapter 10. Pay special attention that the duct systems and terminations, adjacent buildings, property lines, combustible construction, electrical equipment and closest point of all air intakes or doors or windows within the distances specified in Section 7.8 of NFPA 96: and equipment, clearance reduction methods, rated enclosures, and cleanouts. A separate Non-Water Based Suppression System permit is required. This review does not include approval of the suppression system design or installation. Hood suppression system shall comply with NFPA 17A, 96, and UL 300. Activation of the suppression system shall activate the fire alarm system if available. A letter of compliance will be required at the time of final inspection stating: the date the system was tested for operation, fuel gas shut off, and fire alarm connection if applicable. Through-penetrations and membrane penetrations in fire walls, fire barrier walls, and fire resistance rated horizontal assemblies shall be protected by firestop systems or devices in conformance with NFPA 101:8.3.5 (ASTM E 814 or ANSI/UL 1479). Providing firestop labels at each firestop system or device and an onsite manual containing the detail for each firestop system or device used for the project will streamline final inspection approvals.</p> <p>Compliance letter stating applicable codes and standards shall be referenced and document submitted electronically.</p> <p>Installation shall comply with City Code Chapter 10 and NFPA 96, Standard for ventilation Control and Fire Protection of Commercial Cooking Operations, 2008 edition. A signed letter of certification is required.</p> <p>A separate Non-Water Based Suppression System permit is required. This review does not include approval of the suppression system design or installation.</p>				