

SECTION 085800 – SECURITY SCREENS

PART 1 - GENERAL

1.1 SECTION REQUIREMENTS

- A. Submittals: Product Data and Shop Drawings.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Products of Kane Manufacturing Company, Kane, PA.

2.2 SECURITY SCREENS

- A. Model A-PRO-Z fixed security screen, recessed mounting.
 - 1. Horizontal brace for screens exceeding 48 inches in height.
- B. Frame: Aluminum extrusion.
- C. Frame finish: powder coated, color as selected from manufacturer's standard colors.
- D. Screen cloth: stainless steel, 12 mesh .028-inch wire.
- E. Mounting angle: continuous extruded aluminum angle screwed to wood jambs.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install screens in accordance with shop drawings and specifications.
- B. Plumb and align faces in a single plane and erect screens square and true, adequately anchored.

END OF SECTION 085800