

SECTION 088000 - GLAZING

PART 1 - GENERAL

1.1 SECTION REQUIREMENTS

- A. Submittals: Product Data.
- B. Fire-Resistance-Rated Assemblies: Provide products that comply with NFPA 80 and are listed and labeled by a testing and inspecting agency acceptable to authorities having jurisdiction for applications indicated.
- C. Safety Glass: Category II materials complying with testing requirements in 16 CFR 1201 and ANSI Z97.1.
- D. Glazing Publications: Comply with published recommendations of glass product manufacturers and organizations below, unless more stringent requirements are indicated.
 - 1. GANA Publications: GANA's "Glazing Manual."

PART 2 - PRODUCTS

2.1 GLASS

- A. Heat-Treated Float Glass: ASTM C 1048, Condition A (uncoated), Type I, Class 1 (clear), Quality Q3, Kind FT (fully tempered).

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Comply with combined recommendations of manufacturers of glass, sealants, gaskets, and other glazing materials, unless more stringent requirements are contained in GANA's "Glazing Manual."
- B. Set glass lites in each series with uniform pattern, draw, bow, and similar characteristics.
- C. Remove nonpermanent labels, and clean surfaces immediately after installation.

END OF SECTION 088000