

SECTION 096816 - SHEET CARPETING

PART 1 - GENERAL

1.1 SECTION REQUIREMENTS

- A. Submittals: Product Data and Samples.
- B. Extra Materials: Deliver to Owner full-width carpet equal to 5 percent of each type and color carpet installed, packaged with protective covering for storage.

PART 2 - PRODUCTS

2.1 CARPET CPT-1:

- A. Products:
 - 1. Shaw Style 5A153 "Gradient", color as noted on drawings.
- B. Primary Backing: Manufacturer's standard material.
- C. Secondary Backing: Manufacturer's standard material.

2.2 CARPET CPT-2:

- A. Products:
 - 1. Shaw Style 5A151 "Tint", color as noted on drawings.
- B. Primary Backing: Manufacturer's standard material.
- C. Secondary Backing: Manufacturer's standard material

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Comply with CRI 104.
- B. Installation Method: Direct glue-down.
- C. Maintain uniformity of carpet direction and lay of pile. At doorways, center seams under door in closed position. Bind or seal cut edges as recommended by carpet manufacturer.

- D. Install pattern parallel to walls and borders.

END OF SECTION 096816