

SECTION 113100 - RESIDENTIAL APPLIANCES

PART 1 - GENERAL

1.1 SECTION REQUIREMENTS

- A. Submittals: Product Data.
- B. Regulatory Requirements: Comply with provisions of the following product certifications:
 - 1. NFPA: Provide electrical appliances listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
 - 2. UL and NEMA: Provide electrical components required as part of residential appliances that are listed and labeled by UL and that comply with applicable NEMA standards.
 - 3. ANSI: Provide gas-burning appliances that comply with ANSI Z21 Series standards.
 - 4. NAECA: Provide residential appliances that comply with NAECA standards.
- C. Accessibility: Where residential appliances are indicated to comply with accessibility requirements, comply with the U.S. Architectural & Transportation Barriers Compliance Board's "Americans with Disabilities Act (ADA), Accessibility Guidelines for Buildings and Facilities (ADAAG)."

PART 2 - PRODUCTS

2.1 RESIDENTIAL APPLIANCES

- A. Electric Cooktop: 30-inch, built-in cooktop with four burner elements.
 - 1. Products:
 - a. GE Model JP328WKWW.
- B. Electric Wall Oven: Built-in, double, electric, wall oven with broiler unit.
 - 1. Products:
 - a. GE Model JTP35WMWW.
- C. Refrigerator/Freezer: Freestanding, frost-free, two-door refrigerator with top-mounted freezer.
 - 1. Products:
 - a. GE Model JTP35WMWW.
- D. Freezer: Freestanding, frost-free, upright freezer.

1. Products:
 - a. GE Model FUF17SVRWW.
- E. Dishwasher: Built-in, undercounter, automatic dishwasher.
 1. Products:
 - a. GE Model GLDA690MWW.
- F. Clothes Washer: Freestanding, front-loading, automatic clothes washer
 1. Products:
 - a. Whirlpool Model WFW9200SQ.
- G. Gas Clothes Dryer: Freestanding, front-loading clothes dryer, with stack mounting kit for mounting on top of clothes washer.
 1. Products:
 - a. Whirlpool Model WGD9400SW.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Built-in Appliances: Securely anchor to supporting cabinetry or countertops with concealed fasteners. Verify that clearances are adequate for proper functioning and rough openings are completely concealed.
- B. Freestanding Appliances: Place in final locations after finishes have been completed in each area. Verify that clearances are adequate to properly operate equipment.
- C. Test each item of residential appliances to verify proper operation. Make necessary adjustments.
- D. Verify that accessories required have been furnished and installed.

END OF SECTION 113100