Package Steel Systems, Inc. Manufacturer of the *Packag*

15 Harback Road
Sutton, MA 01590

Tel 800.225.7242 | Tel 508.865.5871
Fax 508.865.9130

RESURGAM CITY OF PORTLAND, MAINE
Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 10/07/14

Customer:
Biskup Construction Inc.
16 Danielle Drive
Windham, ME 04062

Project:
Holmes #3
421 Warren Ave.
Portland, ME 04103

Date: 7/2
Project 1

Width:	Length:	Lt. Eave:	Rt. Eave:	Pitch:
110 ft.	101 ft.	18.71 ft.	21 ft.	0.25:12
70 ft.	199 ft.	19.54 ft.	21 ft.	0.25:12

To Whom It May Concern,

This letter is to certify that the subject building is designed and fabricated in accordance with the order documentation; The 13th Edition of The American Institute of Steel Construction (AISC) "Manual of Steel Construction"; the 2007 Edition of the North American United States Manual (NAUS); the MBMA Low Rise Building Systems Manual and any applicable sections of the American Welding Society (AWS D1.1) specifications for the loads indicated.

The criteria for application of design loads are as follows:

GOVERNING CODE: IBC 09 BUILDING CLASS: II - Normal

Dead Load:	3.00 psf	Ground Snow,Pg:	60.00 psf
Collateral Load:	3.00 psf	Flat Roof Snow,Pf:	42.00 psf
Live Load:	20.00 psf	Snow Exp. Factor,Ce:	1.00
Live Load Reduction:	No	Snow Therm. Factor,Ct:	1.00
Basic Wind Speed:	94 mph	Snow Imp. Factor,Is:	1.00
Wind Exposure:	B	Seis.Imp. Factor,Ie:	1.00
Enclosure Type:	Closed	Seis.Design Cat.,SDC:	C
Wind Imp. Factor,Iw:	1.00	Site Class:	E
Int.Pres.Coef.,GCpi:	0.18	Spec.Resp.Coef.,Sds:	0.41
Auxillary Load:	None	Spec.Resp.Coef.,Sd1:	0.18

Note:
Additional components, such as panel and trims, may be fabricated and provided for use in a Package Steel Systems, Inc. (PSS) building by other manufacturers.

This Letter of Certification applies solely to the building frames and components as supplied by PSS and specifically excludes any foundation, masonry, general contract work, and materials not furnished by PSS. It also excludes any unauthorized modification to the PII framing systems. The Buyer is responsible for verifying that the loads, specified above, are in compliance with those required by the local regulatory authorities.

STATE OF MAINE
ZACK R. McCAIN, III
6869
REGISTERED PROFESSIONAL ENGINEER

Sincerely,

Zack R McCain III, P.E.